

# *Industry Foundation Classes - Release 2.0*

---

## *Specifications Volume 1*

### *AEC/FM Processes Supported By IFC*



*Final Release --15-March-99*



*International Alliance for Interoperability*  
*Enabling Interoperability in the AEC/FM Industry*



***Industry Foundation Classes - Release 2.0***  
***Specifications Volume 1***

# ***AEC/FM Processes supported by IFC***

***Enabling Interoperability in the AEC/FM Industry***

Copyright © 1996-99 - International Alliance of Interoperability (IAI)

*Mailing address: 2960 Chain Bridge Road - Suite 143  
Oakton, Virginia 22124*

Email address: [IAI@Interoperability.com](mailto:IAI@Interoperability.com)

*Web Address: [www.Interoperability.com](http://www.Interoperability.com)*

*All rights reserved. No part of the contents of this document may be reproduced or transmitted in any form or by any means without the written permission of the copyright holder (IAI).*

## Document Editor

Editor	Richard See
Development committee	Specification Task Force

## Document Control

Project reference	IFC Release 2.0
Document reference	AEC/FM Processes supported by IFC
Document version	IFC Release 2.0 – Final
Release date	March 15, 1999
Status	For Comments
Distribution	IAI Member Companies
Distribution format	PDF file

## Revisions

[illegible]

# Table of Contents

<b>1. INTRODUCTION, SCOPE AND ASSUMPTIONS .....</b>	<b>1</b>
1.1. PURPOSE OF THESE DOCUMENTS.....	1
1.2. IFC RELEASE DOCUMENT SUITE.....	1
1.3. SCOPE.....	2
1.3.1. Scope for IFC Release 2.0 .....	2
1.3.2. Scope of this document.....	4
1.4. ASSUMPTIONS AND ABBREVIATIONS .....	5
1.5. INTERNATIONAL ALLIANCE FOR INTEROPERABILITY (IAI) .....	6
<b>2. AEC/FM INDUSTRY PROCESS FRAMEWORK.....</b>	<b>7</b>
2.1. GENERAL PHASES OF A BUILDING PROJECT .....	7
2.1.1. Feasibility Phase.....	8
2.1.2. Design Phase .....	9
2.1.3. Construction Phase .....	10
2.1.4. Operation Phase.....	12
1.1. WORK IN PROCESS - REFERENCE AEC/FM PROCESS MODEL .....	12
2.1.5. General Phases of a Building Project.....	12
<b>3. REQUIREMENTS DEFINITION PROJECT SUMMARIES .....</b>	<b>15</b>
3.1. [AR-1] ARCHITECTURAL MODEL EXTENSIONS.....	15
3.2. [AR-2] COMPARTMENTATION OF BUILDINGS .....	16
3.3. [BS-1] HVAC SYSTEM DESIGN .....	17
3.4. [BS-3] PATHWAY DESIGN AND COORDINATION .....	19
3.5. [BS-4] HVAC LOADS CALCULATION .....	21
3.6. [CS-1] CODE CHECKING - ENERGY CODES .....	22
3.7. [CS-2] CODE CHECKING EXTENSIONS.....	24
3.8. [ES-1] COST ESTIMATING.....	25
3.9. [FM-3] PROPERTY MANAGEMENT (BUILDING OWNER'S VIEWPOINT).....	27
3.10. [FM-4] OCCUPANCY PLANNING.....	29
3.11. [SI-1] PHOTO ACCURATE VISUALISATION .....	30
3.12. [XM-2] PROJECT DOCUMENT MANAGEMENT .....	31
<b>4. AEC/FM INDUSTRY PROCESS DEFINITIONS .....</b>	<b>34</b>
4.1. [AR-1] ARCHITECTURAL MODEL EXTENSIONS.....	34
4.1.1. Process: Building Shell Design.....	34
4.1.2. Process: Building Core Design.....	37
4.1.3. Process: Stair Design .....	40
4.1.4. Process: Restroom Design.....	43
4.1.5. Process: Roof Design .....	45
4.2. [AR-2] COMPARTMENTATION OF BUILDINGS .....	48
4.2.1. Process: Compartmentation of buildings.....	48
4.3. [BS-1] HVAC SYSTEM DESIGN .....	50
4.3.1. Process: HVAC Duct System Design .....	51
4.3.2. Process: HVAC Piping System Design .....	57
4.4. [BS-3] PATHWAY DESIGN AND COORDINATION .....	62
4.4.1. Process: Pathway Design and Coordination .....	62
4.5. [BS-4] HVAC LOADS CALCULATION .....	67
4.5.1. Process: Building Heating and Cooling Load Calculation.....	67
4.6. [CS-1] CODE CHECKING - ENERGY CODES .....	70
4.6.1. Process: Commercial and Residential Energy Code Compliance Checking .....	70
4.7. [CS-2] CODE CHECKING EXTENSIONS.....	79
4.7.1. Commercial, Residential and Institutional Code Compliance Checking for Disable Access and Escape Route .....	79
4.8. ES-1 COST ESTIMATING.....	86
4.8.1. Cost Estimating .....	86

4.9. [FM-3] PROPERTY MANAGEMENT (BUILDING OWNER'S VIEWPOINT) .....	94
4.9.1. Property Management .....	94
4.10. [FM-4] OCCUPANCY PLANNING.....	100
4.10.1. Occupancy Planning.....	100
4.10.2. Design of Workstations .....	103
4.10.3. Floor Layout of Workstations for an Open Office .....	106
4.11. [SI-1] PHOTO ACCURATE VISUALIZATION.....	112
4.11.1. Photo Accurate Visualization .....	112
4.12. [XM-2] PROJECT DOCUMENT MANAGEMENT .....	114
4.12.1. Project Document Management.....	114
<b>5. INFORMATION REQUIREMENTS ANALYSIS .....</b>	<b>117</b>
5.1. [AR-1] ARCHITECTURAL MODEL EXTENSIONS.....	117
5.1.1. Process: Building Shell Design.....	117
5.1.2. Process: Building Core Design.....	121
5.1.3. Process: Stair Design .....	124
5.1.4. Process: Public Restroom Design.....	127
5.1.5. Process: Roof Design.....	130
5.2. [AR-2] COMPARTMENTATION OF BUILDINGS .....	136
5.2.1. Process: Compartmentation of buildings.....	136
5.3. [BS-1] HVAC SYSTEM DESIGN .....	138
5.3.1. Process: HVAC Duct System Design .....	138
5.3.2. Process: HVAC Piping System Design .....	149
5.4. [BS-3] PATHWAY DESIGN AND COORDINATION .....	160
5.4.1. Process: Pathway Design and Coordination .....	160
5.5. [BS-4] HVAC LOADS CALCULATION .....	165
5.5.1. Process: Building Heating and Cooling Load Calculation.....	165
5.6. [CS-1] CODE CHECKING - ENERGY CODES .....	170
5.6.1. Process: Commercial and Residential Energy Code Compliance Checking .....	170
5.7. [CS-2] CODE CHECKING EXTENSIONS.....	174
5.7.1. Codes for Access and Escape .....	175
5.8. [ES-1] COST ESTIMATING.....	179
5.8.1. Cost Estimating .....	179
5.9. [FM-3] PROPERTY MANAGEMENT (BUILDING OWNER'S VIEWPOINT) .....	186
5.9.1. Grouping IFC objects.....	186
5.9.2. Linking the maintenance objects to the IFC objects.....	189
5.10. [FM-4] OCCUPANCY PLANNING.....	192
5.10.1. Occupancy Planning.....	192
5.10.2. Design of Workstations .....	203
5.10.3. Floor Layout of Workstations for an Open Office .....	215
5.11. [SI-1] PHOTO ACCURATE VISUALIZATION.....	224
5.11.1. Photo Accurate Visualization .....	224
5.12. [XM-2] PROJECT DOCUMENT MANAGEMENT .....	227
5.12.1. Project Document Management.....	227
<b>6. OBJECT TYPE DEFINITION TABLES .....</b>	<b>231</b>
6.1. [AR-1] ARCHITECTURAL MODEL EXTENSIONS.....	231
6.2. [AR-2] COMPARTMENTATION OF BUILDINGS .....	253
6.3. [BS-1] HVAC SYSTEM DESIGN .....	254
6.4. [BS-3] PATHWAY DESIGN AND COORDINATION .....	264
6.5. [BS-4] HVAC LOADS CALCULATION .....	265
6.6. [CS-1] CODE CHECKING - ENERGY CODES .....	265
6.7. [CS-2] CODE CHECKING EXTENSIONS.....	267
6.8. [ES-1] COST ESTIMATING.....	271
6.9. [FM-3] PROPERTY MANAGEMENT (BUILDING OWNER'S VIEWPOINT) .....	271
6.10. [FM-4] OCCUPANCY PLANNING.....	272
6.11. [SI-1] PHOTO ACCURATE VISUALIZATION.....	283
6.12. [XM-2].....	284

# 1. Introduction, Scope and Assumptions

## 1.1. Purpose of these documents

The purpose of this document suite is to provide a detailed specification of the Industry Foundation Classes (IFC) as defined by the Industry Alliance for Interoperability (IAI). The intended audience is the IAI membership, industry domain experts, and software developers interested in implementing IFC.

## 1.2. IFC Release Document Suite

IFC will be documented for two readers. The AEC professional and the software profession serving the AEC industry. Documents in this release include:

### An Introduction to IAI and IFC

The "*An Introduction to IAI and IFC*," as the name implies, provides AEC/FM industry professionals with an introduction to the organization, including its mission and organization. It also introduces the shared project model concept, end user benefits in using IFC compliant applications and summarizes the AEC Industry processes that are supported by this release of IFC. Finally, it provides a preview of what will be added in future releases.

### IFC Specification Development Guide

The "*IFC Specification Development Guide*" defines the process used by the IAI in developing IFC. It also provides various references supporting parts of this process such as development of process diagrams, development of detailed requirement definitions and reading/creating EXPRESS (data model) definitions and EXPRESS-G diagrams.

### IFC Object Model Architecture Guide


The "*IFC Object Model Architecture Guide*" defines the architecture used in the design of the IFC object model. This architecture is modular and layered which allows independent development and evolution of sub-schemata. This document is written for software developers who will develop applications supporting IFC.

### Volume 1: AEC/FM Processes Supported by IFC

THIS DOCUMENT -- The "*AEC/FM Processes Supported by IFC*" volume documents the AEC/FM industry processes that the IFC Project Model in this release is designed to support. Therefore, this document effectively defines the scope of AEC project information included in this Release. Volumes 2 and 3 structure this information for use in applications. Note that this IFC release is limited to the information content of the foundation classes defined. Behavior for these objects, and thus the implementation of software that will support these AEC industry processes, will be defined by the implementing software vendors.

### Volume 2: IFC Object Model Guide

The "*IFC Object Model Guide*" defines model design and use concepts for IFC object model. These key concepts include: an overview of model architecture, capturing design intent, sharing semantic relationships,



model extension by application developers. It also describes some implementation strategies such as file based model exchange, Client-Server architectures and runtime interoperability supported through standard software interfaces of the IFC model. This includes provides an overview and example of the physical file format for file based model exchange.

### **Volume 3: IFC Object Model Reference**

The "*IFC Object Model Reference*" provides detailed definitions for each of the classes and data types defined in the IFC object model. This includes all of the information required by the AEC processes defined in volume 1, structured in an information model detailing object class data, relationships, standard interfaces, type definitions and geometry schema use for shape representation. Additionally, it provides a data model view defined in EXPRESS and a standard interfaces view defined in IDL. Each of these code sets will be used by application developers as input into Computer Aided Software Engineering (CASE) tools to semi-automate development of applications supporting IFC. Finally, a on-line version of this information is provided using an HTML document set that is cross linked for easy access to information related to or supporting a particular class or data type.

### **Volume 4: IFC Software Implementation Certification Guide**

The "*IFC Software implementation Certification Guide*" provides detailed information about conformance certifications issues and the methodology that will be used by the IAI to certify applications for multiple levels of IFC conformance. This includes an overview of the concepts for conformance assessment and certification, definition of various "Exchange Set" subsets of the IFC model for which certification can be assessed and an overview of the testing suites that will be used for certification testing.

### **Volume 5: IFC Software Implementation Guide**

The "*IFC Software implementation Guide*" provides detailed information addressing the issues of implementing the IFC object model in software products. In this release, it's content is limited to the topics of implementing property sets (previously called "Pset Guide") and the differences from the previous release (previously called "Migration Guide"). Over the next couple of IFC releases, many more topics will be addressed.

## **1.3. Scope**

### **1.3.1. Scope for IFC Release 2.0**

Enabling interoperability between applications by different software vendors is the ultimate goal of the IAI. This is a very ambitious goal and will be achieved through a series of incremental steps.

In general, the IAI is focused on providing three things in IFC:

1. Standard definitions for the attributes associated with entities comprising an AEC/FM project model (objects)
2. Structure and relationships between these entities from the point of view of various AEC/FM professionals
3. Standard formats/protocols for two methods of sharing this information:
  - *exchange via a standard file format*
  - *exchange via standard software interfaces*

It is important to note that the software interface specifications in this release will not include any application-specific behavior. Instead, these interfaces will be limited to get and set methods for the attribute and relationship information defined in the data model.

Release 1.5 of IFC provided the infrastructure that supports this release, plus reasonable models for architecture, some HVAC, estimating, scheduling and Facilities Management. This release will build on these foundations and extend the model in several areas.



The scope for this release of the IFC Specifications is limited to:

1. Six AEC/FM domains - Architecture, HVAC engineering, codes and standards, cost estimating, facilities management and simulation
2. Only a specific subset of the processes in these domains (defined in Volume 1 of these specifications).

These domains and processes are:

### **Architectural Design**

- *Building 'shell' design*
- *Building 'core' design*
  - *Stair design*
  - *Public toilet design*
- *Roof design*
- *Fire Compartmentation*

### **HVAC Engineering**

- *HVAC Duct System Design*
- *HVAC Piping System Design*
- *Pathway Design and Coordination*
- *Building Heating and Cooling Load Calculation*

### **Codes and Standards**

- *Commercial and Residential Energy Code Compliance Checking*
- *Handicapped access code checking*
- *Escape from Fire code checking*

### **Cost Estimating**

- *Cost Estimating*
  - *Identify Objects*
  - *Identify Tasks Needed to Install Objects*
  - *Identify Resources Needed to Perform Tasks*
  - *Quantify*
  - *Costing and Cost Summarization*

### **Facilities Management**

- *Property Management*
  - *Enabling the use of IFC objects in property management*
  - *Grouping IFC objects*
  - *Linking the maintenance objects to the IFC objects*
- *Occupancy Planning*
- *Design of Workstations*
- *Floor Layout of Workstations for an Open Office*

### **Simulation**

- *Photo Accurate Visualization*

### **All AEC domains**

- *Document references (from model to document only)*

## 1.3.2. Scope of this document

This document includes the following information:

### 1. Introduction, Scope and Assumptions

*This section provides the reader with an introduction to the set of seven documents comprising this release of the IFC Specifications. This section outlines the information included in this document versus related documents. It will also define the scope for this release and assumptions about knowledge of the reader.*

### 2. AEC/FM Process Framework

*This section provides an overview of the AEC industry processes that are performed through out the design, engineer, build, and management of a built facility. The diagrams are meant to be a framework for the reader of these documents to provide an orientation for indicating where a process fits into the building lifecycle. Processes defined and supported in previous releases are indicated as gray shaded process boxes. Processes defined in this release are indicated with by black shaded process boxes.*

### 3. Domain Team Project Summaries

*This section provides the reader with an overview of the AEC/FM domain projects that developed the requirements for this release. An description of the project team, and overview of the industry processes for which requirements are defined and an overview of the resources required for the project are provided.*

### 4. AEC Process Definitions and Usage Scenarios

*This section includes the process definitions and usage scenarios which are the basis for the information requirements specified in the next section - and ultimately, for the extensions to the IFC model in this release. The specified processes were prioritized and selected as processes that would see significant improvements (efficiency, cost avoidance, etc.) if supported by IFC. There are a few criteria used to do this. First, IFC support for the process must provide an increase in productivity and must be concise enough to be completed in a single IFC release cycle. Second, the process should deliver a benefit to other domains in the building life cycle. Third, there must be a minimum of two software companies that have committed that they will implement support for the process and associated IFC objects in a shipping software product.*

*Such processes obviously vary between companies and certainly between regions. The definitions specified represent the IAI domain groups' consensus on a generalized definition that sufficiently represents the diversity across companies and regions. It is anticipated that future releases of IFC will reflect some regional differences.*

*Each process in this section contains three parts. The first provides an overview process description, written to AEC professionals, to indicate where the process fits into their overall processes. The second part is a process diagram which illustrates each task in the process and its informational input/output sources. The third part provides text book style task definitions and a running series of usage scenarios using real project graphics and data. These are organized according to the tasks in the process diagram.*

### 5. Information Requirement Analyses

*This section provides a detailed analysis for all of the input information required and output information supplied by each of the process tasks defined in the previous section.*

### 6. Object Type Definition Tables

*This section organizes information requirements by 'object type' and provides detailed information about data types, limits and defaults for all information.*

## *1.4. Assumptions and Abbreviations*

This document assumes the reader is reasonably familiar with the following:

- AEC/FM market and project terminology
- Software industry terminology
- Concepts and terminology associated with object oriented software

The following abbreviations are used throughout the IFC Specifications:

- AEC/FM Architectural, Engineering, Construction and Facilities Management
- IAI Industry Alliance for Interoperability
- AP Application Protocol
- Arch Architecture
- CM Construction Management
- CORBA Common Object Request Broker Architecture
- COM Microsoft's Component Object Model
- DCE Distributed Computing Environment
- DCOM Microsoft's Distributed Component Object Model
- DSOM IBM's Distributed System Object Model
- FM Facilities Management
- FTP File Transfer Protocol
- GUID Globally Unique Identifier
- HVAC Heating, Ventilating and Air Conditioning
- HTTP Hypertext Transport Protocol
- IAI International Alliance for Interoperability
- IDL Interface Definition Language
- IFC Industry Foundation Classes
- ISO International Standards Organization
- FM Facilities Management
- MIDL Microsoft's Interface Definition Language
- ODL Microsoft's Object Description Language
- OMG Object Management Group
- ORB Object Request Broker
- OSF Open Software Foundation
- RPC Remote Procedure Call
- SOM IBM's System Object Model
- STEP Standard for the Exchange of Product Model Data
- TCP/IP Transmission Control Protocol/Internet Protocol
- TQM Total Quality Management
- URL Universal Resource Location

## ***1.5. International Alliance for Interoperability (IAI)***

The IAI is a 'not for profit' industry alliance of companies. Its membership is comprised of visionary companies representing all sectors of the AEC industry worldwide.

The IAI was first formed in September of 1995, by 12 industry leading companies who, during the previous year had worked together to develop proof of concept prototypes demonstrating the viability of interoperability between AEC software applications. This demonstration was shown publicly at the AEC Systems '95 conference in Atlanta, Georgia. This is the third release of IFC since that time. There are currently 50 organizations implementing software to support IFC, a number that is growing quite rapidly now.

As of this printing, the IAI includes 9 international chapters with hundreds of member companies in the following regions:

- *Australasian countries*
- *French speaking region of Europe*
- *German speaking region of Europe*
- *Japan*
- *Korea*
- *Nordic countries of Europe*
- *North America*
- *Singapore*
- *United Kingdom*

***The IAI stated Vision, Mission and Values can be summarized as:***

### **VISION**

*Enabling Interoperability in the A/E/C/FM Industry*

### **MISSION**


*To define, promote and publish specifications for the Industry Foundation Classes (IFC) as a basis for information sharing through the project life cycle, globally, across disciplines and technical applications.*

### **VALUES**

- Not for profit industry organization
- Action oriented (Alliance v. Association)
- Consensus based decision making
- Incremental delivery (rather than prolonged study)
- Global solution
- Industry to define IFC
- IFC to be "open" (for implementation/use by all software vendors)
- Design for IFC to be extensible
- IFC will evolve over time
- Membership open to any company working in construction industry

## 2. AEC/FM Industry Process Framework


This section includes diagrams expressing a high level framework for the AEC/FM industry processes. Three levels of diagrams are provided. The first diagram represents the four phases of a project as an index into the decision to study, design, construct, and operate a facility through its entire lifecycle. The second set of diagrams presents each phase as a series of processes that are accomplished by participating disciplines. The third set of diagrams provide a process breakdown (sub-processes). Processes supported by this release of IFC are highlighted. Those that are not highlighted will be considered in future IFC releases.



KEY:


### 2.1. General Phases of a Building Project

The diagrams below represent the traditional AEC/FM processes where the four phases are represented as linear processes accomplished over time even though cycles exist within the phases and between phases. Each of the phases has a discipline which is responsible contractually for the completion of the phase. Disciplines may span across the phase but usually their input represents overseeing previous work for which they were responsible. Each of the following phases is described to provide the reader with a brief background.




## 2.1.1. Feasibility Phase

The Feasibility Phase involves the need to expand or re-arrange a facility or facilities. The process involves defining the best method for the building owner, developer, or corporation to fill their long term need for space. The decision may be between renovating an existing building, leasing space, building a new facility, or any combination of the above. At this point, a program is created by the client, facility programming consultant, or an architect to determine the capacity of the facility. Other related issues are researched that may impact the project both legally or financially.



## 2.1.2. Design Phase


Depending on the decision in the previous Feasibility Phase, the Design Phase may range from just the interior layout and design of existing space up to the design of a new facility using the full range of disciplines, ie. architecture, interior, engineering, and specialty consultants. The traditional project has the architect, through contracts with the client, responsible for the final product of this phase, which is a set of drawing and specifications in electronic or paper format. The drawings provided by the rest of the team in this process such as the engineers are rolled up with the architects as a single set of information for the construction of the facility.



## 2.1.3. Construction Phase


The Construction Phase begins with an analysis of the drawings and specification documents to create an estimate on time, equipment, material, and manpower needed to construct the facility. The contractor is selected usually as part of a Bid Process where competing estimates allow the client to determine the appropriate company to build the project. A construction manager may be hired by the client to oversee the transition between the design phase and construction phase and provide scheduling and financial management for the project.

### 2.1.3.1. Project Estimation Processes






### 2.1.3.2. Construction Process




### 2.1.3.3. Close-Out Processes



## 2.1.4. Operation Phase

By far the Operation Phase is the longest and most expensive of the four phases outlined. The Operation Phase begins after the contractor turns over a finished building and the client receives an occupancy permit that indicate that the facility is inhabitable. The operation phase has many cycles and involves a large array of specialties to manage, track, operate, and maintain the facility through its continued life.




## 1.1. Work in process - Reference AEC/FM Process Model

The IAI's CB-1 team was formed in 1997. Their charter states they mission as "specify data required at each stage of the project process, and the operation of the building from the client viewpoint. This information should then form part of the Brief to each of the other domain groups as they determine object specifications." The process framework in the previous section will be replaced by the model developed by this team. This section gives you a glimpse of the approach being taken.

## 2.1.5. General Phases of a Building Project

The diagram below indicates how a building project is developed out of a building owners business processes. It shows the overall framework in which business and building processes take place. A key feature of this model is to illustrate how activities in a building project can be seen being delivered out of generic concurrent processes.



The generic business processes are 'Business Planning' and 'Facilities Management'. These take place concurrently with any development project (s). The lower part of the model comprises the building process model and comprises 'Development'; 'Planning'; 'Implementing' and Controlling processes. The building process model also comprises of key stages. These are described below:


## PRE -PROJECT PHASES

## PROJECT PHASES

PHASE 0 <u>Establish Need</u>	PHASE ONE <u>Conception of Need</u>	PHASE TWO <u>Outline Feasibility</u>	PHASE THREE <u>Substantive Feasibility (&amp; financial auth')</u>	PHASE FOUR <u>Outline Concept Design</u>	PHASE FIVE <u>Full Concept Design</u>	PHASE SIX <u>Co-ord' Design (&amp; full financial authority)</u>	PHASE SEVEN <u>Production Information</u>	PHASE EIGHT <u>Construction</u>
----------------------------------	--	---	---	---	--	---	--	------------------------------------

The pre-project phases run from Phase 0 to Phase 4. During these phases the Brief for the project is determined and sufficient design work is carried out to ensure that a robust business case, with sufficient briefing and design information is produced. This will enable a project team to deliver the project to targets set by the building owner and agreed at the end of phase 3.

During Phases 4 to 8 the team is responsible for both the on-going brief development; design and construction. The processes ensure that the right skills are available in the team at each stage to meet the demands of the project. In Phase 3 the initial product data model is developed (although this could happen earlier) and the model is then enhanced with more attribute information to produce the electronic prototype of the proposed facility. During stages 5 and 6, in particular, simulation technologies are used to optimise the design to ensure the closest possible fit with the Brief. During Phase 7, the construction process is simulated to ensure that a properly informed and optimised plan is established before assembly and construction take place. In Phase 8, construction takes place as planned and the facility is handed over in accordance with the building project plan.



All the work of the team within a building project should be customer focussed. The business process model articulates customer-focussed measures. It is these measures that every process and sub-process should be focussed on achieving.

The key processes in the are illustrated in the above diagram.

**Development process.** This is the process that receives the output from the Business Planning process, where customerst needs are first identified. The Development Process, analyses the Statement of Need and should the process identify that the need will be best met through a building project, then resources are identified and a project Brief called a Statement of Requirements. Concurrent with this process is a Planning Process where an overall strategy for achieving the building project is developed. The Planning Process is where all the detailed plans for delivering the project to meet the development requirements are formulated.

It is in the Implementation Process, where the detailed Briefing, Design (and where the development of Product Data Model is produced). It is where Procurement and Construction take place, as the building project evolves from a design solution to constructed reality.

Concurrent with the Implementing process is the Controlling Process. This is where controls are established to ensure that the building project proceeds in accordance with the planned process. It is here where outputs from the Development Process and the Implementation Process are reviewed against the Brief and the various plans to ensure conformance with requirements. It is here too, where change is controlled and the implications of change on the building project are understood.

A key implication of concurrent processes is the need to manage information exchanges in a much more controlled manner than with linear processes. Object technology is a key enabler to effective information management. In developing processes and sub-processes the information exchanges are modelled and the attribute data for objects is defined. As objects inherit attribute data they 'carry' it from one process to the next, and so facilitate the information exchanges.

## 3. Requirements Definition Project Summaries

### 3.1. [AR-1] Architectural Model Extensions

#### 3.1.1. Project Description

**AEC Industry Processes described in this project:**

- Shell Design
- Core Design
- Stair Design
- Restroom Design
- Roof Design

This project will define these five processes in an effort to complete the basic Architectural Model for a commercial office building. These processes span from the Schematic design phase of Architecture through refinement in the Construction Document phase.

#### 3.1.2. Project Team

**Project Leader**    **Ken Herold - North America** – [Ken.Herold@hok.com](mailto:Ken.Herold@hok.com)

<u>Chap</u>	<u>Name</u>	<u>Company</u>	<u>Phone</u>	<u>Email</u>	<u>Hrs / Wk</u>
NA	Gustavo A. Lima	Cannon		<a href="mailto:glima@cannon.com">glima@cannon.com</a>	?
	Bill O'Malley	Hammel Green and Abrah...		<a href="mailto:BOMalley@EMAIL.HGA.COM">BOMalley@EMAIL.HGA.COM</a>	?
	Barbara Golte...	Heller & Metzger, PC		<a href="mailto:74212.354@compuserve.com">74212.354@compuserve.com</a>	?
	Ken Herold	HOK		<a href="mailto:iaexec@interoperability.com">iaexec@interoperability.com</a>	5
	Steve Stevens	Intergraph		<a href="mailto:festeven@ingr.com">festeven@ingr.com</a>	3
	Juniper Russell	Juniper Russell & Assoc.		<a href="mailto:juniper@novimundi.com">juniper@novimundi.com</a>	?
	Ed Ebbing	MC2		<a href="mailto:eebbing@mc2-ice.com">eebbing@mc2-ice.com</a>	1
	Martin Rozmanith	RMW Architecture + Design		<a href="mailto:marty_rozmanith@rmw.com">marty_rozmanith@rmw.com</a>	?
	Ardie Aliandust	RTKL		<a href="mailto:2350@la.rtkl.com">2350@la.rtkl.com</a>	3
	Bill Houstoni	RTKL		<a href="mailto:bhouston@balt.rtkl.com">bhouston@balt.rtkl.com</a>	?
	Nick Reveliotty	The Kling Lindquest Pa...			?
	Tony Sinisi	The Kling Lindquest Pa...		<a href="mailto:76636.1043@compuserve.com">76636.1043@compuserve.com</a>	?
	Beth Brucker	USA-CERL		<a href="mailto:B-Brucker@cecer.army.mil">B-Brucker@cecer.army.mil</a>	2
	Paul Lewis	Visio		<a href="mailto:paul@visio.com">paul@visio.com</a>	?
	Rob Wakeling	Visio		<a href="mailto:robw@visio.com">robw@visio.com</a>	?
				<b>Team total =</b>	<b>14</b>

#### 3.1.3. Scope of Work

# of AEC processes to be supported	- 6	Est. total AEC expert time (days)	- 30.2
Expected IFC Model Impact (1 ( <i>min</i> ) to 5)	- 4	Est. total Info Modeling expert time (days)	- ??
Degree of technical difficulty (1 ( <i>min</i> ) to 5)	- 4	Est. total Project Mgmt. expert time (days)	- ??

#### 3.1.4. Resources Required / Committed

<i>Member Company Resources</i>	<i>Required Days</i>	<i>Market Value</i>	<i>Days Committed</i>	<i>Resource shortfall</i>
Process Model	30	\$10,195	nn	nn
Usage Requirements	30	\$10,195	nn	nn

Object Model development	30	\$10,195	nn	nn
Integration	7.5	\$2,600	nn	nn
Test Case development	37.75	\$12,740	nn	nn
Implementation technical support	7.5	\$2,600	nn	nn
Management and Review	7.5	\$2,600	nn	nn
<b>Total Member Company Resources</b>	<b>151</b>	<b>\$51,000</b>	nn	nn
<b>Travel</b>		<b>\$68,000</b>		
<b>Project Support</b>	<b>Required Days</b>	<b>Market Value</b>		
Technical support	nn	\$nn		
Project management	nn	\$nn		
Publication and Administration	nn	\$nn		
Equipment and software	nn	\$nn		
Travel and subsistence	nn	\$nn		
<b>Total Project Support</b>	<b>nn</b>	<b>\$nn</b>		
<b>Total for Project</b>	<b>nn</b>	<b>\$nn</b>		

## 3.2. [AR-2] Compartmentation of Buildings

### 3.2.1. Project Description

**AEC Industry Processes described in this project:**

- Compartmentation of Building

It is assumed that the fire usually starts in one place, and spreads to other parts of the building. In order to allow the occupants of the building to escape, the first thing is to stop the spread of fire and smoke to other parts of the building, as well as to maintain common escape routes free of fire and smoke. Compartmentation allows the control of fire within a limited space, allowing occupants of the building to escape and to control the fire.

On receipt of Architects drawings, identify primary and secondary Use Classes, for the total project. In doing so define shape and size of each Use Class compartments will be defined. Use Class compartments [Proposed Compartments] may need to be sub-divided into Occupancy type [Owners/Tenants] compartments and if necessary sub-divided further to meet the maximum permitted floor area or the volume for a given compartment. Final result is the Fire compartment.

### 3.2.2. Project Team

**Project Leader** Jay Patankar - [patankar@dial.pipex.com](mailto:patankar@dial.pipex.com)

<u>Chap</u>	<u>Company</u>	<u>Member</u>	<u>Phone</u>	<u>Email</u>	<u>Hrs / Wk</u>
UK		Jay Patankar		<a href="mailto:patankar@dial.pipex.com">patankar@dial.pipex.com</a>	
UK		Steve Race		<a href="mailto:darcyrate@dial.pipex.com">darcyrate@dial.pipex.com</a>	
UK		John Cann			
UK		David Clarke		<a href="mailto:David.clarke@eur.autodesk.com">David.clarke@eur.autodesk.com</a>	
UK		Jeffrey Wix		<a href="mailto:100125.2426@compuserve.com">100125.2426@compuserve.com</a>	
UK		Donald Ross		<a href="mailto:ssi@ltd.net">ssi@ltd.net</a>	
UK		Richard Harpham		<a href="mailto:richard_harpham@compuserve.com">richard_harpham@compuserve.com</a>	

### 3.2.3. Scope of Work

# of AEC processes to be supported	- 3	Est. total AEC expert time (days)	- 30
Expected IFC Model Impact (1 ( <i>min</i> ) to 5)	- 5	Est. total Info Modeling expert time (days)	- 40
Degree of technical difficulty (1 ( <i>min</i> ) to 5)	- 4	Est. total Project Mgmt. expert time (days)	- ??

### 3.2.4. Resources Required / Committed

<b>Member Company Resources</b>	<b>Required Days</b>	<b>Market Value</b>	<b>Days Committed</b>	<b>Resource shortfall</b>
<b>Requirements definition</b>				
Process Model	30	£13200		
Usage Scenaria	20	£8800		
<b>Model design</b>				
Object Model development ( <i>w/ tech.Support</i> )	40	£17600		
Integration ( <i>w/ tech.Support</i> )	10	£4400		
<b>Design and Implementation validation</b>				
Test Case development	20	£8800		
Review/feedback on implementations	40	£17600		
<b>Project Management</b>				
Project management and administration	34	£14960		
Travel and Meetings	80	£35200		
<b>Total Member Company Resources</b>	<b>274</b>	<b>120560</b>		

<b>Model/Specification development support</b>	<b>Required Days</b>	<b>Market Value</b>		
Technical support	50	£12500		
Project management	24	£10500		
Publication and Administration	10	£2200		
Equipment and software		£2000		
Travel and subsistence		£2000		
<b>Total Project Support</b>		<b>£29200</b>		
<b>Total for Project</b>		<b>£149760</b>		

## 3.3. [BS-1] HVAC System Design

### 3.3.1. Project Description

AEC Industry Processes described in this project:

- HVAC Duct Design
- HVAC Piping Design

These processes will involve utilizing the network object types defined in the IFC 2.0 Core model. This effort will be led by the North American Building Services Committee, but will be an international collaborative effort. This will ensure that the resulting system design extensions are globally applicable.

Engineers responsible for the design of duct and piping systems may be consulted during the building conceptual stage. However, the major design effort occurs after the architect has substantially completed the building drawings. The design process includes both the schematic and detailed description of duct and piping components. These components include sections of duct and pipe, fittings, accessories such as dampers, valves, and terminals. This process also includes the connection of these components to equipment such as fans and pumps. Object types for equipment were defined in IFC Version 1.x, and are not elaborated in this proposal. The system design process also includes construction cost estimates. However, these estimates are typically performed by contractors using the drawings and specifications prepared by the Building Services engineer.

Significant cost savings will result from the application of IFC's to systems design in Building Services.

- Building geometry and construction materials used in the design of HVAC load calculations and the fluid distribution systems.
- The exchange of data between engineering design and analysis programs with manufacturers' equipment selection programs.
- The production of schedules of bill of materials for the system components.
- Producing the data for engineers cost estimates and for contractors actual construction cost estimates.
- The opportunity for integration of control components used for the operation of these systems.

### 3.3.2. Project Team

**Project Leader** James Forester - [jim@marinsoft.com](mailto:jim@marinsoft.com)

<u>Chap</u>	<u>Company</u>	<u>Name</u>	<u>Phone</u>	<u>Email</u>	<u>Hrs / Wk</u>
NA		John Deal		<a href="mailto:75601.1346@compuserve.com">75601.1346@compuserve.com</a>	4
NA		Rod Dougherty		<a href="mailto:rod.dougherty@landis+gyr.sprint.com">rod.dougherty@landis+gyr.sprint.com</a>	4
NA		James Forester		<a href="mailto:jim@marinsoft.com">jim@marinsoft.com</a>	4
NA		Scott Frank		<a href="mailto:sfrank@pipeline.com">sfrank@pipeline.com</a>	2
NA		Kirk McGraw		<a href="mailto:k-mcgraw@cecer.army.mil">k-mcgraw@cecer.army.mil</a>	2
NA		Larry Schaefer		<a href="mailto:larry.schaefer@carrier.wtk.com">larry.schaefer@carrier.wtk.com</a>	2
NA		Tony Sherfinski		<a href="mailto:tony.sherfinski@greenheck.com">tony.sherfinski@greenheck.com</a>	2
UK		Jeff Wix		<a href="mailto:100342.2537@compuserve.com">100342.2537@compuserve.com</a>	2
<b>Total for project team =</b>					<b>22</b>

### 3.3.3. Scope of Work

# of AEC processes to be supported	- 2	Est. total AEC expert time (days)	- 40
Expected IFC Model Impact (1 (min) to 5)	- 3	Est. total Info Modeling expert time (days)	- 40
Degree of technical difficulty (1 (min) to 5)	- 3	Est. total Project Mgmt. expert time (days)	- 40

### 3.3.4. Resources Required / Committed

<b>Member Company Resources</b>	<b>Required Days</b>	<b>Market Value</b>	<b>Days Committed</b>	<b>Resource shortfall</b>
<b>Requirements definition</b>				
Process Model	10	\$12000	10	0
Usage Scenaria	15	\$18000	15	0
<b>Model design</b>				



Object Model development (w/ tech.Support)	10	\$12000		5	5
Integration (w/ tech.Support)	20	\$24000		10	10
<b>Design and Implementation validation</b>					
Test Case development	15	\$18000		10	5
Review/feedback on implementations	15	\$18000		??	??
<b>Project Management</b>					
Project management and administration	15	\$18000		30	nn
Travel and Meetings	10	\$12000		10	nn
<b>Total Member Company Resources</b>	<b>110</b>	<b>\$132000</b>		<b>85+</b>	<b>40+</b>

<b>Model/Specification development support</b>	<b>Required Days</b>	<b>Market Value</b>	<b>Days Committed</b>	<b>Resource shortfall</b>
Technical support	5	\$6000		
Project management	10	\$12000		
Publication and Administration	10	\$12000		
Equipment and software	5	\$6000		
Travel and subsistence	10	\$12000		
<b>Total Project Support</b>	<b>40</b>	<b>\$48000</b>		
<b>Total for Project</b>	<b>150</b>	<b>\$180000</b>		

### 3.4. [BS-3] Pathway Design and Coordination

#### 3.4.1. Project Description

**AEC Industry Processes described in this project:**

- Pathway Design and Coordination

The design of pathways contains the draft layout, the coordination and the representation of mechanical and electrical system-pathways to be installed.

This design process is carried out after the first coordination with the architect and structural engineers, and includes load estimates, energy and systems definitions required for a building.

The process ends with drawings containing the coordinated pathways for the mechanical and electrical installations (i.e. heating, cooling, air-conditioning, plumbing, fire-protection and electrical power) within a building.

#### 3.4.2. Project Team

**Project Leader**     **Rolf Tonke / Bertram Witz - German Chapter**

<b>Chap</b>	<b>Company</b>	<b>Member</b>	<b>Phone</b>	<b>Email</b>	<b>Hrs</b>
Germany	vögtlin engineering	Felix Brückner		<a href="mailto:100737.1421@compuserve.com">100737.1421@compuserve.com</a>	0
Austria	PHi-Tech	Bernhard Fragner		<a href="mailto:fragner@phitech.co.at">fragner@phitech.co.at</a>	0
Germany	GTS	Rainer Hirschberg		<a href="mailto:Rh@gts-software.com">Rh@gts-software.com</a>	40
Austria	'ESS	Doris Huber		<a href="mailto:ess@klima2000.co.at">ess@klima2000.co.at</a>	0

Germany	Softtech	Eberhard Michaelis	<a href="mailto:EMichaelis@softtech.com">EMichaelis@softtech.com</a>	80
Germany	Ziegler Informatics	Ulrich Paar	<a href="mailto:ziegler@caddy.de">ziegler@caddy.de</a>	0
Swiss	RoCAD Informatik	Robert Rottermann	<a href="mailto:100041.2347@compuserve.com">100041.2347@compuserve.com</a>	80
Germany	Triplan GmbH	Willi Spiegel	<a href="mailto:willi.spiegel@triplan.com">willi.spiegel@triplan.com</a>	0
Germany	Planungsgruppe M+M AG	Rolf Tonke	<a href="mailto:100436.705@compuserve.com">100436.705@compuserve.com</a>	120
Germany	Pit-cup GMBH	Kurt Weber	<a href="mailto:pit-cup@t-online.de">pit-cup@t-online.de</a>	0
Germany	Planungsgruppe M+M AG	Bertram Witz		80
Germany	Kuehn Bauer Partner	Michael Kuehn jr.	<a href="mailto:mkj@kbp-futures.com">mkj@kbp-futures.com</a>	0
			<b>Total for project team</b>	<b>400</b>

### 3.4.3. Scope of Work

# of AEC processes to be supported	- 7	Est. total AEC expert time (days)	- 18
Expected IFC Model Impact (1 ( <i>min</i> ) to 5)	- 3	Est. total Info Modeling expert time (days)	- 15
Degree of technical difficulty (1 ( <i>min</i> ) to 5)	- 2	Est. total Project Mgmt. expert time (days)	- 15

### 3.4.4. Resources Required / Committed

<b>Member Company Resources</b>	<b>Required Days</b>	<b>Market Value</b>	<b>Days Committed</b>	<b>Resource shortfall</b>
<b>Requirements definition</b>				
Process Model	10	\$7060	nn	nn
Usage Scenaria	7	\$4942	nn	nn
<b>Model design</b>				
Object Model development ( <i>w/ tech.Support</i> )	5	\$3530	nn	nn
Integration ( <i>w/ tech.Support</i> )	8	\$5648	nn	nn
<b>Design and Implementation validation</b>				
Test Case development	10	\$7060	nn	nn
Review/feedback on implementations	5	\$3530	nn	nn
<b>Project Management</b>				
Project management and administration	2	\$1412	nn	nn
Travel and Meetings	3	\$2118	nn	nn
<b>Total Member Company Resources</b>	<b>50</b>	<b>\$35300</b>	<b>nn</b>	<b>nn</b>

<b>Model/Specification development support</b>	<b>Required Days</b>	<b>Market Value</b>	<b>Days Committed</b>	<b>Resource shortfall</b>
Technical support	nn	\$nn		
Project management	nn	\$nn		
Publication and Administration	nn	\$nn		
Equipment and software	nn	\$nn		
Travel and subsistence	nn	\$nn		
<b>Total Project Support</b>	<b>nn</b>	<b>\$nn</b>		
<b>Total for Project</b>	<b>nn</b>	<b>\$nn</b>		

## 3.5. [BS-4] HVAC Loads Calculation

### 3.5.1. Project Description

#### AEC Industry Processes described in this project:

- Building Heating and Cooling Load Calculation

Load calculations serve as the basis for all design stages of the building services design. The results of the load calculations enable the designer to dimension the plant equipment and to determine the required space for plant room.

Load calculations are an official proofing method in Germany for example the proof for heat loss protection must be given in the course of a project), a mode for calculating the heating cooling load or for the yearly dynamic load simulation:

The process terminates in the complete calculations and the data exchange into the IFC model.

### 3.5.2. Project Team

#### Project Leader Rolf Tonke / Rainer Hirschberg - German Chapter

<u>Chap</u>	<u>Company</u>	<u>Member</u>	<u>Phone</u>	<u>Email</u>	<u>Hrs</u>
Germany	vögtlin engineering	Felix Brückner		<a href="mailto:100737.1421@compuserve.com">100737.1421@compuserve.com</a>	0
Austria	PHI-Tech	Bernhard Fragner		<a href="mailto:fragner@phitech.co.at">fragner@phitech.co.at</a>	0
Germany	GTS	Rainer Hirschberg		<a href="mailto:Rh@gts-software.com">Rh@gts-software.com</a>	140
Austria	'ESS	Doris Huber		<a href="mailto:ess@klima2000.co.at">ess@klima2000.co.at</a>	0
Germany	Softtech	Eberhard Michaelis		<a href="mailto:EMichaelis@softtech.com">EMichaelis@softtech.com</a>	140
Germany	Ziegler Informatics	Ulrich Paar		<a href="mailto:ziegler@caddy.de">ziegler@caddy.de</a>	0
Swiss	RoCAD Informatik	Robert Rottermann		<a href="mailto:100041.2347@compuserve.com">100041.2347@compuserve.com</a>	80
Germany	Triplan GmbH	Willi Spiegel		<a href="mailto:willi.spiegel@triplan.com">willi.spiegel@triplan.com</a>	0
Germany	Planungsgruppe M+M AG	Rolf Tonke		<a href="mailto:100436.705@compuserve.com">100436.705@compuserve.com</a>	160
Germany	Pit-cup GMBH	Kurt Weber		<a href="mailto:pit-cup@t-online.de">pit-cup@t-online.de</a>	0
Germany	Planungsgruppe M+M AG	Bertram Witz			80
Germany	Kuehn Bauer Partner	Michael Kuehn jr.		<a href="mailto:mkj@kbp-futures.com">mkj@kbp-futures.com</a>	40
				<i>Total for project team =</i>	640

### 3.5.3. Scope of Work

# of AEC processes to be supported	- 6	Est. total AEC expert time (days)	- 30
Expected IFC Model Impact (1 (min) to 5)	- 5	Est. total Info Modeling expert time (days)	- 20
Degree of technical difficulty (1 (min) to 5)	- 2	Est. total Project Mgmt. expert time (days)	- 20

### 3.5.4. Resources Required / Committed

<b>Member Company Resources</b>	<b>Required Days</b>	<b>Market Value</b>	<b>Days Committed</b>	<b>Resource shortfall</b>
<b>Requirements definition</b>				
Process Model	14	\$9884	nn	nn
Usage Scenaria	12	\$8472	nn	nn
<b>Model design</b>				
Object Model development (w/ tech.Support)	5	\$3530	nn	nn
Integration (w/ tech.Support)	8	\$5648	nn	nn
<b>Design and Implementation validation</b>				

Test Case development	15	\$10590		nn	nn
Review/feedback on implementations	8	\$5648		nn	nn
<b>Project Management</b>					
Project management and administration	5	\$3530		nn	nn
Travel and Meetings	5	\$3530		nn	nn
<b>Total Member Company Resources</b>	<b>72</b>	<b>\$50832</b>		nn	nn

<b>Model/Specification development support</b>	<b>Required Days</b>	<b>Market Value</b>	<b>Days Committed</b>	<b>Resource shortfall</b>
Technical support	nn	\$nn		
Project management	nn	\$nn		
Publication and Administration	nn	\$nn		
Equipment and software	nn	\$nn		
Travel and subsistence	nn	\$nn		
<b>Total Project Support</b>	<b>nn</b>	<b>\$nn</b>		
<b>Total for Project</b>	<b>nn</b>	<b>\$nn</b>		

## 3.6. [CS-1] Code Checking - Energy Codes

### 3.6.1. Project Description

#### AEC Industry Processes described in this project:

- Commercial and Residential Energy Code Compliance Checking

This project has two parts: CS-1A - **Code Compliance Enabling Mechanism** and CS-1B **Energy Code Compliance Checking**. These two parts have been combined into a single project for administrative efficiency. Part A of the project will define a generic code compliance enabling mechanism that will be applicable to codes of various types; e.g., accessibility, egress, and energy. The mechanism will likely involve defining new abstract classes for code compliance in the core model. Part A will be an international collaborative effort, which will ensure that the resulting enabling mechanism is broadly applicable. Part B, Energy Code Compliance, will serve an important role in validation of the generic mechanism for a set of code applications. This work will be performed primarily by the North American Chapter and will enable established energy code compliance applications to be made IFC compliant.

Code compliance checking is performed by building designers, systems designers, and code enforcement officials. Compliance with codes begins during the programming phase when designers determine which codes apply to the building project. Preliminary code reviews are frequently performed during schematic design, and more thorough reviews are performed by members of the design team late in the design process before construction documents are complete. Building code officials perform plan reviews as part of the building permit process. Designers and code official perform drawing dimension takeoffs as necessary to ensure compliance. Information about building systems, assemblies, layout, etc. is gathered during this process and compared to the requirements for each applicable code.

Codes impact virtually all disciplines involved in building design and construction processes, and code considerations persist throughout a building's life cycle. Energy codes are strongly related to architectural, HVAC, and electrical design processes. While it would be difficult to establish a reliable estimate of time and cost savings from IFC support of code checking, the tedious nature of code review and the large cost and schedule impacts that code violations can cause suggest that there will be high demand for code checking

applications. Energy codes represent an attractive application for IFC support because of their extensive requirements for building data that are already in electronic form (e.g., geometric data and lighting fixture data) and demonstrated strong demand--thousands of copies of these applications currently in use.

### 3.6.2. Project Team

**Project Leader**    **Rob Briggs - North America Chapter**

<u>Chap</u>	<u>Company</u>	<u>Member</u>	<u>Phone</u>	<u>Email</u>	<u>Hrs / Wk</u>
N. America		Rob Briggs		<a href="mailto:rs_briggs@pnl.gov">rs_briggs@pnl.gov</a>	10
Singapore		Tan You Tong		<a href="mailto:youtong@iti.gov.sg">youtong@iti.gov.sg</a>	2
France		Philippe Debras		<a href="mailto:debras@cstb.fr">debras@cstb.fr</a>	2
UK		Robert Amor		<a href="mailto:trebor@bre.co.uk">trebor@bre.co.uk</a>	1
				Total for project team =	15

### 3.6.3. Scope of Work

# of AEC processes to be supported	- 1	Est. total AEC expert time (days)	- 5
Expected IFC Model Impact (1 ( <i>min</i> ) to 5)	- 2	Est. total Info Modeling expert time (days)	- 2
Degree of technical difficulty (1 ( <i>min</i> ) to 5)	- 3	Est. total Project Mgmt. expert time (days)	- 2

### 3.6.4. Resources Required / Committed

<i>Member Company Resources</i>	<i>Required Days</i>	<i>Market Value</i>	<i>Days Committed</i>	<i>Resource shortfall</i>
<b>Requirements definition</b>				
Process Model	5	\$4,000	5	0
Usage Scenaria	5	\$4,000	5	0
<b>Model design</b>				
Object Model development (w/ tech. Support)	10	\$8,000	10	0
Integration (w/ tech. Support)	8	\$6,400	8	0
<b>Design and Implementation validation</b>				
Test Case development	5	\$4,000	5	0
Review/feedback on implementations	5	\$3,840	5	0
<b>Project Management</b>				
Project management and administration	5	\$4,000	5	0
Travel and Meetings	5	\$7,000	5	0
<b>Total Member Company Resources</b>	<b>48</b>	<b>\$41,240</b>	<b>48</b>	<b>0</b>

<i>Model/Specification development support</i>	<i>Required Days</i>	<i>Market Value</i>	<i>Days Committed</i>	<i>Resource shortfall</i>
Technical support	nn	\$nn		
Project management	nn	\$nn		
Publication and Administration	nn	\$nn		
Equipment and software	nn	\$nn		
Travel and subsistence	nn	\$nn		
<b>Total Project Support</b>	<b>nn</b>	<b>\$nn</b>		

<b>Total for Project</b>	<b>nn</b>	<b>\$nn</b>			
--------------------------	-----------	-------------	--	--	--

## 3.7. [CS-2] Code Checking Extensions

### 3.7.1. Project Description

**AEC Industry Processes described in this project:**

- Code Compliance - Disabled Access
- Code Compliance - Escape Routes

The project covers specific application of the code compliance enabling mechanism (R2\_CS-1) in serving the disabled access and escape routes code compliance.

Disable access code compliance is a process of assessing whether **the access provisions and facilities** of a building complies with one or more codes or standards **that serve the needs of the wheelchair user and ambulant disabled** enforced by various codes and standards promulgation entities.

Escape route code compliance is a process of assessing whether **the exit provisions and facilities** of a building complies with one or more codes or standards **that provide safe means of escape for occupants** enforced by various codes and standards promulgation entities.

The processes are performed by building designers and code enforcement officials during early design and submission stages, respectively. Automatic code compliance software based on the IFC models created in this project will help building designers to carry out self-checking of their designs in order to detect code violations as early as possible while design changes are still relatively cheap to make. Similarly, it also help the code enforcement officials to verify the plans submitted by the designers for building approvals.

The resources required to produce the IFC model for the disabled access and escape route are estimated to be 160 man-days over 20 elapse calendar weeks. Based on market value of \$200 (Singapore) per man-days, a total of \$32000 is required for the project.

### 3.7.2. Project Team

**Project Leader**    **Mr. Wong Wai Ching - Singapore**

#### **Disable Access**

<u>Chapter</u>	<u>Name</u>	<u>Email</u>	<u>Hrs / Week</u>
Singapore	Mr. Wong Wai Ching (leader)	- <a href="mailto:keewee@ncb.gov.sg">keewee@ncb.gov.sg</a>	2
Singapore	Mr. Zhong Qi (info modeling)	<a href="mailto:Zhongqi@ncb.gov.sg">Zhongqi@ncb.gov.sg</a>	22
Singapore	Mr. Liew Pak San (software)	<a href="mailto:paksan@ncs.com.sg">paksan@ncs.com.sg</a>	4
Singapore	Dr. Tan Kee Wee	<a href="mailto:Keewee@ncb.gov.sg">Keewee@ncb.gov.sg</a>	4

A total of 32 man-hrs/week is required which is equivalent to 4 man-days/week (based on 8 hrs/days). Over 20 calender weeks, a total of 80 man-days is required.

#### **Escape Route**

<u>Chapter</u>	<u>Name</u>	<u>Email</u>	<u>Hrs / Week</u>
Singapore	Mr. Wong Wai Ching (leader)	- <a href="mailto:keewee@ncb.gov.sg">keewee@ncb.gov.sg</a>	2
Singapore	Mr. Zhong Qi (info modeling)	<a href="mailto:Zhongqi@ncb.gov.sg">Zhongqi@ncb.gov.sg</a>	22
Singapore	Mr. Liew Pak San (software)	<a href="mailto:paksan@ncs.com.sg">paksan@ncs.com.sg</a>	4

Singapore	Dr. Tan Kee Wee	<a href="mailto:Keewee@ncb.gov.sg">Keewee@ncb.gov.sg</a>	4
-----------	-----------------	--	---

A total of 32 man-hrs/week is required which is equivalent to 4 man-days/week (based on 8 hrs/days). Over 20 calendar weeks, a total of 80 man-days is required.

### 3.7.3. Scope of Work

AEC processes to be supported	- 2	Est. total AEC expert time (weeks)	- 2
Expected IFC Model Impact (1 ( <i>min</i> ) to 5)	- 3	Est. total Info Modeling expert time (weeks)	- 10
Degree of technical difficulty (1 ( <i>min</i> ) to 5)	- 3	Est. total Software/PM expert time (weeks)	- 4

### 3.7.4. Resources Required / Committed

<b>Member Company Resources</b>	<b>Required Days</b>	<b>Market Value</b>	<b>Days Committed</b>	<b>Resource shortfall</b>
Process Model	4	S\$200	4	0
Usage Requirements	20	S\$200	20	0
Object Model Development	80	S\$200	80	0
Integration	20	S\$200	20	0
Test Case Development	10	S\$200	10	0
Implementation Technical Support	10	S\$200	10	0
Management and Review	16	S\$200	16	0
<b>Total Member Company Resources</b>	<b>160</b>	<b>S\$32000</b>	<b>160</b>	<b>0</b>
<b>Project Support</b>	<b>Required Days</b>	<b>Market Value</b>		
Technical support	30	\$15000		
Project management	5	\$2500		
Publication and Administration	-	\$500		
Equipment and software	-	\$1000		
Travel and subsistence	0	\$0		
<b>Total Project Support</b>	<b>35</b>	<b>\$19000</b>		
<b>Total for Project</b>	<b>195</b>	<b>\$51000</b>		

## 3.8. [ES-1] Cost Estimating

### 3.8.1. Project Description

**AEC Industry Processes described in this project:**

- Code Compliance - Disabled Access

This project is designed to increase the ability of the model to support cost estimating. The model already supports cost estimating to some degree. This project focuses refining and expanding that capability.

Most of the information used by cost estimating will be entered into the model by earlier design processes. At various times during the evolution of the design, an estimator will use the model to do cost estimating. During early design stages, very little information will be available, and only a rough estimate will be possible. As the model becomes more detailed, more accurate estimates are possible. When different designs are under

consideration, “what if” or “alternate” estimates may be used to compare their cost impact. After a design and estimate are approved, inevitably, changes will be proposed and “change order” estimates will be required to determine the cost impact of the proposed change.

Using the IFC Model to do cost estimating saves time by using information provided by the design processes. It can also save time by making the task and resource data that it creates available to later processes such as scheduling. Using the model as the primary information source for estimating can also reduce errors and omissions that occur when data is entered into an estimating system by hand.

### 3.8.2. Project Team

**Project Leader**     **Mike Cole - North American Chapter**

<u>Chapter</u>	<u>Name</u>	<u>Email</u>	<u>Hrs / Wk</u>
NA	Mike Cole	mikec@timberline.com	10
NA	Ray Brungard	rbrungard@tcco.com	.5
UK	Jeffrey Wix	10342.2537@compuserve.com	?
NA	Peggy Woodall	peggy@bsdsoftlink.com	?
NA	Annette Stumph	a-stumpf@cecer.army.mil	?
NA	Roger Grant	rgrant@rsmeans.com	?
DE	Hans-Peter Sanio	San@mail.rib.de	?
<b>Total for project</b>			

### 3.8.3. Scope of Work

AEC processes to be supported	- 1	Est. total AEC expert time (days)	- nn
Expected IFC Model Impact (1 ( <i>min</i> ) to 5)	- 1	Est. total Info Modeling expert time (days)	- nn
Degree of technical difficulty (1 ( <i>min</i> ) to 5)	- 1	Est. total Software/PM expert time (days)	- nn



### 3.8.4. Resources Required / Committed

<i>Member Company Resources</i>	<i>Required Days</i>	<i>Market Value</i>		<i>Days Committed</i>	<i>Resource shortfall</i>
<b>Requirements definition</b>					
Process Model	2	\$1000		2	0
Usage Scenaria	4	\$2000		4	0
<b>Model design</b>					
Object Model development (w/ tech.Support)	10	\$5000		10	0
Integration (w/ tech.Support)	6	\$3000		6	0
<b>Design and Implementation validation</b>					
Test Case development	6	\$3000		6	0
Review/feedback on implementations	8	\$4000		8	0
<b>Project Management</b>					
Project management and administration	8	\$4000		8	0
Travel and Meetings	50	\$25000		50	0
<b>Total Member Company Resources</b>	<b>94</b>	<b>\$47000</b>		<b>86</b>	

<b>Model/Specification development support</b>	<b>Required Days</b>	<b>Market Value</b>		<b>Days Committed</b>	<b>Resource shortfall</b>
Technical support	nn	\$nn			
Project management	nn	\$nn			
Publication and Administration	nn	\$nn			
Equipment and software	nn	\$nn			
Travel and subsistence	nn	\$nn			
<b>Total Project Support</b>	<b>nn</b>	<b>\$nn</b>			
<b>Total for Project</b>	<b>nn</b>	<b>\$nn</b>			

## 3.9. [FM-3] Property management (Building Owner's viewpoint)

### 3.9.1. Project Description

Property management is a process starting from requirement programming and continuing through the building's life cycle. In this phase the FM-3 project covers just a subset of this process focusing on grouping of spaces and other possible objects for different purposes, like maintenance, administration, public registers, mapping etc. This process is based on objects provided by the design and construction process and uses mainly the attributes in the current model. The main user is the building owner and the benefit is more efficient use of the building data and through this cost savings in the administrative work. This process starts after the building is completed and is carried out through the whole life cycle of the building.

### 3.9.2. Project Team

**Project Leader**    **Poul Sorgenfri Ottosen - Nordic Chapter**

<u>Chapter</u>	<u>Name</u>	<u>Email</u>	<u>Hrs / Wk</u>
Nordic	Poul Sorgenfri Ottosen	psa@aua.auc.dk	10
Nordic	Jan Karlshøj	jakbyg@carlbro.dk	3
Nordic	Arto Kiviniemi	arto.kiviniemi@vtt.fi	5
NA	Kevin Yu		1
		<b>Total for project team =</b>	<b>19</b>

### 3.9.3. Scope of Work

AEC processes to be supported	- 3	Est. total AEC expert time (days)	- 30
Expected IFC Model Impact (1 ( <i>min</i> ) to 5)	- 1	Est. total Info Modeling expert time (days)	- 15
Degree of technical difficulty (1 ( <i>min</i> ) to 5)	- 1	Est. total Software/PM expert time (days)	- 10

### 3.9.4. Resources Required / Committed

<i>Member Company Resources</i>	<i>Required Days</i>	<i>Market Value</i>	<i>Days Committed</i>	<i>Resource shortfall</i>
<b>Requirements definition</b>				
Process Model	10	\$5 000	10	0
Usage Scenaria	20	\$10 000	20	0
<b>Model design</b>				
Object Model development ( <i>w/ tech.Support</i> )	6	\$3 000	?	?
Integration ( <i>w/ tech.Support</i> )	9	\$4 500	?	?
<b>Design and Implementation validation</b>				
Test Case development	5	\$2 500	?	?
Review/feedback on implementations	5	\$2 500	?	?
<b>Project Management</b>				
Project management and administration	10	\$5 000	10	0
Travel and Meetings	10	\$10 000	10	0
<b>Total Member Company Resources</b>	<b>75</b>	<b>\$42 500</b>	<b>50 + ?</b>	<b>?</b>

<b>Model/Specification development support</b>	<b>Required Days</b>	<b>Market Value</b>	<b>Days Committed</b>	<b>Resource shortfall</b>
Technical support	nn	\$nn		
Project management	nn	\$nn		
Publication and Administration	nn	\$nn		
Equipment and software	nn	\$nn		
Travel and subsistence	nn	\$nn		

<b>Total Project Support</b>	<b>nn</b>	<b>\$nn</b>			
<b>Total for Project</b>	<b>nn</b>	<b>\$nn</b>			

## 3.10. [FM-4] Occupancy Planning

### 3.10.1. Project Description

This project includes the following three processes:

- Occupancy Planning
- Design of Workstations
- Layout of Workstations for an Open Office

The occupancy planner (includes interior designers, facilities managers, architects, furniture dealers' designers, etc.) applies standards during the assignment of people and organizations to interior spaces. It also involves the planning and moving of building assets such as equipment and furniture. This process occurs during the initial planning of space occupancy, and whenever that occupancy needs to change (company reorganization, company growth, or new hires, etc.). The layout and design of typical workstations can be sub-processes of the occupancy planning when it involves systems furniture planning for open offices. These processes require information about the building floor spaces. They also generate space occupancy data for future use of office planning.

Automatic input and utilization of the IFC supported object data, such as building elements and spaces as well as FF&E and occupants, may improve the efficiency of the processes. New objects generated will also be IFC compliant so that they can be used by various FM processes during the operation of the facility.

### 3.10.2. Project Team

**Project Leader**    **Kevin Yu - NA**

<u>Chapter</u>	<u>Name</u>	<u>Email</u>	<u>Hrs / Wk</u>
NA	Rick Bartling / Karen Smith-Hosner	rbartling@hermanmiller.com ksmithhosner@hermanmiller.com	3.5
NA	Vicky Borchers	vicky@mksinfo.qc.ca	7
NA	Francois Grobler	f-grobler@cecer.army.mil	7
NA	Kevin Yu	kevin@naoki.ca	12.5
NA	Rob Wakeling	Robw@visio.com	5
UK	Paul Chadwick	fax: 117-943-4113	?
<b>Total for project</b>			<b>35</b>

### 3.10.3. Scope of Work

AEC processes to be supported	- 3	Est. total AEC expert time (days)	- 29
Expected IFC Model Impact (1 ( <i>min</i> ) to 5)	- 5	Est. total Info Modeling expert time (days)	- 61.5
Degree of technical difficulty (1 ( <i>min</i> ) to 5)	- 4	Est. total Software/PM expert time (days)	- 32

### 3.10.4. Resources Required / Committed

<b>Member Company Resources</b>	<b>Required Days</b>	<b>Market Value</b>	<b>Days Committed</b>	<b>Resource shortfall</b>
---------------------------------	----------------------	---------------------	-----------------------	---------------------------

<b>Requirements definition</b>					
Process Model	15	\$4,725		15	0
Usage Scenarios	15	\$4,725		15	0
<b>Model design</b>					
Object Model development (w/ tech.Support)	30	\$9,450		30	0
Integration (w/ tech.Support)	15	\$4,725		15	0
<b>Design and Implementation validation</b>					
Test Case development	25	\$7,875		15	10
Review/feedback on implementations	7.5	\$2,363		0	7.5
<b>Project Management</b>					
Project management and administration	15	\$4,725		11	4
Travel and Meetings	60	\$4,800		60	0
<b>Total Member Company Resources</b>	<b>132.5</b>	<b>\$43,388</b>		<b>161</b>	<b>21.5</b>

<b>Model/Specification development support</b>	<b>Required Days</b>	<b>Market Value</b>		<b>Days Committed</b>	<b>Resource shortfall</b>
Technical support	nn	\$nn			
Project management	nn	\$nn			
Publication and Administration	nn	\$nn			
Equipment and software	nn	\$nn			
Travel and subsistence	nn	\$nn			
<b>Total Project Support</b>	<b>nn</b>	<b>\$nn</b>			
<b>Total for Project</b>	<b>nn</b>	<b>\$nn</b>			

### 3.11. [SI-1] Photo Accurate Visualisation

#### 3.11.1. Project Description

In the design of a building or other structure, the architect or designer may want to see what the building or the structure will look like, or may want to render images for the client's benefit. Such visualization may be desired at any time from the earliest architectural design or retrofitting to the final interior design. Visualization is the key to solving lighting and daylighting design problems, and is also important in assessing building performance and human comfort issues. IFC support of this process may reduce input preparation time by 75-85% process (through automatic acquisition of building geometry and all surface properties) and thus make the use of the corresponding applications economically feasible.

#### 3.11.2. Project Team

**Project Leader: Vladimir Bazjanac, North American Chapter**

<u>Chapter</u>	<u>Name</u>	<u>Email</u>	<u>Hrs / Week</u>
North American	Vladimir Bazjanac	vlado@gundog.lbl.gov	as /possible
U.K.	Sandy Kinghorn	100412.3254@compuserve.com	?


### 3.11.3. Scope of Work

AEC processes to be supported	- 3	Est. total AEC expert time (days)	- 1
Expected IFC Model Impact (1 ( <i>min</i> ) to 5)	- 1	Est. total Info Modeling expert time (days)	- 1
Degree of technical difficulty (1 ( <i>min</i> ) to 5)	- 1	Est. total Software/PM expert time (days)	- 1

### 3.11.4. Resources Required / Committed

<b>Member Company Resources</b>	<b>Required Days</b>	<b>Market Value</b>	<b>Days Committed</b>	<b>Resource shortfall</b>
Process Model	3	\$2,250	0	\$2,250
Usage Requirements	1	\$750	0	\$750
Object Model development	.5	\$375	0	\$375
Integration	0	\$0	0	\$0
Test Case development	5	\$3,750	0	\$3,750
Implementation technical support	0	\$0	0	\$0
Management and Review	1	\$750	0	\$750
<b>Total Member Company Resources</b>	<b>10.5</b>	<b>\$7,875</b>	<b>0</b>	<b>\$7,875</b>
<b>Project Support</b>	<b>Required Days</b>	<b>Market Value</b>		
Technical support	0	\$0		
Project management	0	\$0		
Publication and Administration	0	\$0		
Equipment and software	0	\$0		
Travel and subsistence	0	\$0		
<b>Total Project Support</b>	<b>0</b>	<b>\$0</b>		
<b>Total for Project</b>	<b>10.5</b>	<b>\$7,875</b>		

## 3.12. [XM-2] Project Document Management

### 3.12.1. Project Description

Project Document Management refers to all information pertaining to the documents used to estimate, bid, purchase, and manage the building process as well as for use within the Facilities Management domain. This data identifies the document, the author of the document, changes to the document since the last change, and relationships to other documents.

•

It is being suggested to the group that the first concentration of our work will be on the Contract Drawings represented in the model. It is acknowledged that this is only a small subset of the related documents of the model. We will continue to review the areas affected and complete a framework for our section of work with

a complete understanding of what will be reflected in the first pass of our work into the model by the end of our first full meeting to be held at the end of January.

- 
- *Who performs this process?*

All software vendors that use drawings, specifications, and sketches during the life cycle of a project. This would include (the Architect's use of) CAD, estimating, scheduling, management, and facilities management software vendors.

- 
- *When in the project lifecycle it is performed?*

From the very inception of the project, where these documents are used to define the project, through the construction of the project with all of its changes, through the management of the "building" once the project is complete.

- 
- *What other processes does it relate to (input from/output to/controlled by)?*

This process starts in the creation and modification of the documents and outputs to all processes that use the documents as a means of identification. This would include estimating where changes to the work are usually quantified by document, management, where the documents are used to control the flow of work on a project and establish what is being built by document, and Facilities Management, where documents are the prime method of identifying actual conditions in a facility.

- 
- *What is the benefit (time or cost savings) in IFC based application support of these processes?*

The control of the project over time depends upon the comparison of many baselines of data from one point in time to another. These baselines are reflected as (can be seen as) documents with a reflection in time. Without the identification and use of these documents, such as a Change Estimate, applications would not be able to identify themselves as distinct from others. In this way, applications such as Estimating, Purchasing, Scheduling, and Management packages are enabled to provide these standard views of a project model. In addition, where documents are still being used as the preferred method of delivery of information regarding a project, such as various government agencies requiring drawings and members of the project team who are not CAD enabled.

- 

### 3.12.2. Project Team

**Project Leader**    **Raymond H. Brungard - North American**

Please note that the team makeup for this work will be international and cross domain in nature. There are a number of individuals who are interested in this work and I am at this time arranging for the final team size and makeup, without the undue disruption of other groups. It is my intention to make sure that the project team includes members from the CAD and Architectural backgrounds to round out the view of Contract Documents.

<u>Chapter</u>	<u>Name</u>	<u>Email</u>	<u>Hrs / Week</u>
NA	Raymond H. Brungard	rbrungard@tcco.com	7
UK	Graham Storer	G_Storer@tel-consult.co.uk	7
UK	To be named later		4
NA	Ken Herold (part time)	iaexec	1
	As yet Named CAD Software		7
Nordic	Arto Kiminieri	arto.kiminieri@vtt.fi	7
NA	Mike Cole (part time)		.5
<b>Total for Project</b>			33.5

### 3.12.3. Scope of Work

AEC processes to be supported	-most	Est. total AEC expert time (days)	- 50
Expected IFC Model Impact (1 ( <i>min</i> ) to 5)	- 2	Est. total Info Modeling expert time (days)	- 5
Degree of technical difficulty (1 ( <i>min</i> ) to 5)	- 4	Est. total Software/PM expert time (days)	- 15

### 3.12.4. Resources Required / Committed

<b>Member Company Resources</b>	<b>Required Days</b>	<b>Market Value</b>	<b>Days Committed</b>	<b>Resource shortfall</b>
<b>Requirements definition</b>				
Process Model	25	\$1,250	25	\$1,250
Usage Scenaria	25	\$1,250	25	\$1,250
<b>Model design</b>				
Object Model development ( <i>w/ tech.Support</i> )	5	\$250	5	\$250
Integration ( <i>w/ tech.Support</i> )	5	\$250	5	\$250
<b>Design and Implementation validation</b>				
Test Case development	10	\$500	nn	nn
Review/feedback on implementations	5	\$250	nn	nn
<b>Project Management</b>				
Project management and administration	5	\$250	nn	nn
Travel and Meetings		\$12,000	n/a	nn
<b>Total Member Company Resources</b>	<b>80</b>	<b>\$16,000</b>	nn	nn

<b>Model/Specification development support</b>	<b>Required Days</b>	<b>Market Value</b>		
Technical support	3	\$200		
Project management	5	\$340		
Publication and Administration	5	\$340		
Equipment and software	2	\$130		
Travel and subsistence	5	\$340		
<b>Total Project Support</b>	<b>20</b>	<b>\$1,350</b>		
<b>Total for Project</b>		<b>\$nn</b>		

## 4. AEC/FM Industry Process Definitions

This section defines the end user domain processes to be supported by this release of the IFC Project Model. Requirements for information to be included in the project model were derived from these end user processes. TQM process diagramming has been used to help document these process definitions.

To further elaborate requirements for software applications that will support these processes, detailed task definitions and user usage scenarios are also provided. In general, these usage scenarios define how the AEC domain professionals expect to be able to use applications (supporting IFC) to accomplish the associated processes specified.

Please note the model validation section which follows. It contains a series of test cases which should enable application developers to test and validate that their applications do indeed satisfy the end user requirements for each process.

As for most sections of this specification, this one is organized by AEC domains in the following order: Architectural design, HVAC engineering, Codes and Standard, Cost Estimating, Facilities Management, Simulation and All Domains.

### 4.1. [AR-1] Architectural Model Extensions

#### Processes Defined in this project:

1. Building Shell Design
2. Building Core Design
3. Stair Design
4. Restroom Design
5. Roof Design

#### 4.1.1. Process: Building Shell Design

The architect balances the building massing with the elevation aesthetics while performing exterior shell design. Both processes (massing and shell design) evolve and cycle back and forth as each may change aspects of the other. The exterior shell design involves making the massing interesting while using glass fenestration, cladding materials, and details in adornment that create a scale and design motif. Other aspects of this process, that are balanced, are the need for visual access and illumination of the spaces behind the shell, and the issues of attaching and waterproofing the shell. The shell design starts typically after a preliminary space layout and during the building massing studies.

##### 4.1.1.1. Introduction

#### Overview:

The architect starts the shell design by working with the preliminary stacking and blocking diagrams to determine a massing of the building, based on the floor plates created in the space layout phase. After the massing, the architect will determine the proper aesthetics effect for the building, whether the facade is connected to the outside of the structure or integrated within the structure. The fenestration is determined based on the amount of light and visual impact of the glass and openings on the facade. After the designer determines the type of materials used, preliminary heat gain/heat loss can be calculated for operational cost impact of the building shell. With the final selection of material and fenestration, a detailed design of the adornment of the facade proceeds using reveals, treatment of the materials, cornices, and other building design elements.

#### Process Scope:

- None defined



**Out-of-Scope:**

- block and stacking
- site analysis
- location of the building

**Definitions:**

- Shell - The exterior wall of a building. Other terms used (facade, elevation, building envelope)
- Massing - The exterior shape of a building. A volumetric view of the building


**References:**

- None defined

**Contributors:**

- Project team

**4.1.1.2. Process Diagram: Building Shell Design**



**4.1.1.3. Process Definition: Building Shell Design**


**4.1.1.3.1. Overview**

None provided

#### 4.1.1.3.2. Task 1 - Preliminary Building Massing

##### Task Description:

The preliminary building massing is a process that is the definition of the volume of the building shape. The massing may be constrained by regional height restrictions and open area standards which are to balance the open area on a site compared to the building footprint area. The massing will also be driven by considering the size of each floor based on a preliminary block and stacking. Client requirement such as optimizing the amount of the occupational space against the exterior wall or the number of corner offices may suggest a shape to the designer. Other subjective issues such as a desire to step the building down to a human scale may drive the massing and shape of the exterior envelope of the building. The floor to floor height of the interior spaces required by the program has a vertical impact on the massing. At this point in the process the designer will start to think about a preliminary structural grid based on a design.




##### Example Usage Scenario:

None provided

#### 4.1.1.3.3. Task 2 - Determine the Relationship between Shell and Structure

##### Task Description:

The relationship of the shell and structure is based on the effect the architect wants to achieve with the design. For example, the shell may be attached to an edge of slab and column so the shell hangs and covers the structure. On the other hand, the designer may desire to express the structure and allow the columns and floor slabs to protrude past the shell, in effect using the structure to frame the shell areas. Other design scenarios such as using the structure to shade glass areas may suggest to the designer to extend the structure past the shell.



##### Example Usage Scenario:

None provided

#### 4.1.1.3.4. Task 3 - Determine Fenestration

##### Task Description:

The fenestration is the design and placement of glass area on the shell to permit natural lighting of building spaces and views from the building. The fenestration is based on the rhythm and aesthetics effect the facade should have with respect to glass area. At this stage, a decision on the shape and size of windows are made but not detailed. The amount of glass area may be driven by the energy criteria and regional location and climate. Each facade or elevation of the shell may have a different fenestration due to the orientation of each building face compared to the direction of the sun during different seasons.

##### Example Usage Scenario:

None provided

#### 4.1.1.3.5. Task 4 - Define Shell Materials

##### Task Description:

The selection of the shell material is based on a diverse set of criteria. The material may be picked based on the need to fit into other buildings in the area or a regional style or culture. The climate may drive the material selection process along with desires by the client to achieve a style for the building. The durability may create a narrower palate of material. There are also regional construction methods, ease of use, cost, and availability of certain materials that would affect its selection.

##### Example Usage Scenario:

None provided

#### 4.1.1.3.6. Task 5 - Costs

##### Task Description:

A preliminary analysis may be run to determine the effect of the shell design on the construction and operational cost of the building. The upkeep on the materials along with the construction cost drive the overall life cycle cost of the shell. On the operational side of the equation the quantity and cost of energy to maintain a temperate environment will be determined by the fenestration and materials selected during the design process. Both will have an overall impact on the heat gain and loss of the building shell.

##### Example Usage Scenario:

None provided


#### 4.1.1.3.7. Task 6 - Visual Design Refinements

##### Task Description:

At this point in the process, the shell is refined and detailed. This may include finishes, additions or treatment to materials such as flame/rough/polished stone, reveals, setting back panels, cornices, or parapets. Each of the adornments, construction techniques, and use of materials are used to apply a character to the design of the facade.

##### Example Usage Scenario:

None provided



### 4.1.2. Process: Building Core Design

The core design is a balance between making available ancillary spaces and program requirement. The size and location on a floor is determined by the structural systems, program requirements including number of occupants and building codes such as ADA. The design of the core follows the initial layout of the spaces defined in the building program. The spaces that make up the core are typically not defined in the program but are extracted by information about the floor size and occupants.

#### 4.1.2.1. Introduction

##### Overview:

The core design starts by determining the size of the items needed in the core. Calculations for the number of elevators are based on building occupants and number of floors. The restroom size is based on the

number of occupants on the floor and in the building. The floor to floor height is used to determine the length of the stairs which determines the size of the stairwell. The circulation around the core is determined by the type of occupancy and fire codes. The layout of the pieces of the core are driven by the structural grid and distances determined by codes, etc.

**Process Scope:**

- Assumptions /presumptions: space program (owners' criteria); occupancy, building, floor; parking garage impacts (structural grids); materials handling (site delivery, building services). The core is defined as items for circulation and service delivery for occupants. It does not have to be in the center of the building.

**Out-of-Scope:**

- This process does not address the actual design of stairs, restrooms, parking design and lobby design. Also materials handling and entering and exiting the building are not included in the core design.

**Definitions:**

- None defined


**References:**

- None defined

**Contributors:**

- project team

**4.1.2.2. Process Diagram: Building Core Design**



### **4.1.2.3. Process Definition: Building Core Design**

#### **4.1.2.3.1. Overview**

None provided

#### **4.1.2.3.2. Task 1 - Determine Core Spaces Needed**

##### **Task Description:**

The types of core spaces are determined by a range of issues and codes. The floor occupancy, building type, and building codes determine the type and number of spaces needed as part of the core. The types of building services that are needed in the building will determine additional types of spaces to allow passage and access to services central to the buildings operation.

##### **Example Usage Scenario:**

None provided

#### **4.1.2.3.3. Task 2 - Determine Core Space Sizes**

##### **Task Description:**

After the determination of which spaces are included in the core for each floor the overall sizes for each needs to be calculated. Apply codes and other processes to determine the size and shape of core spaces. The size of service spaces such as chases and shafts are determined by the overall amount of the material such as fluids, gases, and electrical/Telecommunications that have to be passed through and distributed to floors. Spaces used for transporting occupants such as stairs and elevators are calculated based on the volume of circulation determined by the occupancy of the floor and the building they serve. The final areas provided for occupant support such as restrooms are determined by the occupants of each of the floor they reside on.

##### **Example Usage Scenario:**


None provided



#### **4.1.2.3.4. Task 3 - Layout Core Spaces**

##### **Task Description:**

The location of the varied spaces in the core is determined by many factors. One of the strongest constraints is the circulation needs for both providing effective space utilization and egress/access to the floor through stairs and elevators. The loads and timing of occupant circulation will determine the number of cabs and ultimately the number of elevator stacks and size of their corresponding shafts. The need to efficiently stacking building services forces the stacking of spaces. The structural needs for sheer walls and the spacing of vertical elements such as columns affects the placement of spaces. If the building includes levels of parking, the trade off between structural bay size and efficient parking layout to optimize the number of parking spaces will affect core element placement.



##### **Example Usage Scenario:**

None provided

#### **4.1.2.3.5. Task 4 - Detailed Design of Stairs**

**Task Description:**

*Covered in this document under Stair design Process.*

#### **4.1.2.3.6. Task 5 - Detailed Design of Restrooms**

**Task Description:**

*Covered in this document under Stair design Process.*

### **4.1.3. Process: Stair Design**

Stair design is accomplished by working with the major elements, such as treads, landings, and railings, to determine the appropriate size of the stair and its elements. The process is an iterative process where the answer for one of the elements may change the size of another. The two factors that determine many of the size related decisions are based on the occupancy load and the exiting requirement.

#### **4.1.3.1. Introduction**

**Overview:**

The architect starts the stair design by working with information about the building such a location of the stair based on egress. The width and depth is defined during a process of working back and forth. The width is determined by the number of occupants traveling through the stairwell during an emergency. The width is typically defined in the local building and fire codes. The floor to floor heights of the story are used to determine the length of the stairs, based on a rise and run. The designer may then design the depth of the landing based on codes. As the design progresses to the handrail, its design can potentially affect the width of the stairs and landing, depending on the distance it protrudes into the stairwell. At the point where the size of the treads, landing, and the handrail are set, the materials and construction methods are determined. The final design involves adding items such as exit signs, doors and hardware, and emergency lighting.

**Process Scope:**

- The process described is for fire stairs in a building. Include fire stair materials. ADA safe haven concept should be included (telecommunications, extra design space, area impact)

**Out-of-Scope:**

- Ornamental stairs not in scope and not required for exiting a floor, ladders.

**Definitions:**

- ADA safe haven


**References:**

- Safe haven documentation
- Calculation of stair rise and run

**Contributors:**

- project team

### 4.1.3.2. Process Diagram: Stair Design



Created with

### 4.1.3.3. Process Definition: Stair Design

#### 4.1.3.3.1. Overview

The blocking and stacking process as an element of conceptual design begins after a building program is defined between the client and architect. The designer starts by creating graphic spaces according to the sizes defined in the building program. While reviewing the adjacency and space size, the spaces are moved around to determine their location horizontally on a floor in the building. The non-programmed spaces such as grouped core elements and circulation are added to the diagram. The process progresses when the vertical location of the space in the building (i.e. stacking is determined). The architect moves between the blocking and stacking tasks until the spaces are organized in an optimal manner. The building structural grid may be refined during this iterative stacking and blocking process.

#### 4.1.3.3.2. Task 1 - Locate Stairs

##### Task Description:

*Covered in this document under the Core design Process*

#### 4.1.3.3.3. Task 2 - Determine Width

##### Task Description:

The width of the stairs are determined by building codes which indicate the minimum sizes based on the number of occupants using the stairwell over a certain amount of time. The designer should take into consideration the depth of the handrail as it protrudes into the stair and cuts down on the actual width of the tread.

##### Example Usage Scenario:

None provided

#### **4.1.3.3.4. Task 3 - Determine Tread and Risers**

**Task Description:**

The length or run of the stairs is dependent on the height between the floors being calculated. There are appropriate height and depth of treads based on what is comfortable for occupants to walk up and down steps without stumbling. The rise/run of the stairs are defined in tables in local building codes.

**Example Usage Scenario:**

None provided

#### **4.1.3.3.5. Task 4 - Determine Landing**

**Task Description:**

The landing performs two functions. First it allows the occupants a place to exit out of a floor onto the stair well. The second function is that it is a location to change directions in the stair well. The landing width and depth is determined by stairs connected to the landing and the number of occupants switching between stair flights. The local building codes describe the appropriate size based on the occupants on each of the floors. A new requirement is the inclusion of a safe haven, which is an alcove on the stair landing where a wheel chair can reside out of the way of stair traffic until help can arrive.

**Example Usage Scenario:**

None provided

#### **4.1.3.3.6. Task 5 - Guardrail design**

**Task Description:**

None provided

**Example Usage Scenario:**

None provided

#### **4.1.3.3.7. Task 6 - Handrail design**

**Task Description:**

None provided

**Example Usage Scenario:**

None provided

#### **4.1.3.3.8. Task 7 - Construction and Materials**

**Task Description:**

As the design of the stair is taking shape, a decision on materials is made. The designer selects the material for the stairs such as concrete, steel, or a combination of both. The decision may be based on regional standards, ease of construction, or local fire codes. The materials on the tread and the type and construction of the nosing are also made at this point in the process. The final stage of deciding on the construction the designer determines how the stringer connects the tread, riser, and connects it to the stair well.



**Example Usage Scenario:**

None provided

#### **4.1.3.3.9. Task 8 - Finalize Design**

**Task Description:**

The final detail of stair design evolves other objects connected or part of the stair. This may include deciding on the type of exit doors, signage, standpipe location, location of vents and hatches. Also design of emergency lighting and ventilation should be performed by fire safety engineers at this point in the process.

**Example Usage Scenario:**

None provided

### **4.1.4. Process: Restroom Design**

The design of restrooms involves effective movement of building occupants, ADA codes, and aesthetic use of materials. The minimum number of fixtures is determined by the number of occupants that reside on a floor or visit a floor.

#### **4.1.4.1. Introduction**

**Overview:**

At the start of restroom design, the number of fixtures are determined by the floor occupancy. The designer will also determine items such as partition type, fixture type, stall sizes, based on codes such as ADA and any client requirements. The next level of design involves locating the restroom fixtures and lavatories to use the most effective amount of space to contain cost but provide effective circulation. The next level of design involves locating the lavatories, mirrors, towel racks, grab bars, hand dryers, and any other object that services the restroom occupants. Appropriate location of fixtures and other items in the restroom may be determined by effective use of other building services such as plumbing stacks, etc. The final step of design is more aesthetic in that it involves the visual character of the restroom in selecting material type, sizes and objects such as faucets etc.

**Process Scope:**

- Commercial Public Restroom associated with the building core

**Out-of-Scope:**

- Locker Rooms, Showers.

**Definitions:**

- None defined


**References:**

- None defined

**Contributors:**

- project team

#### 4.1.4.2. Process Diagram: Restroom Design



#### 4.1.4.3. Process Definition: Restroom Design

##### 4.1.4.3.1. Overview

None provided

##### 4.1.4.3.2. Task 1 - Determine Requirements

###### Task Description:

The number of fixtures which is considered toilets, urinals and sinks is determined by codes and the floor occupancy. The ADA requirements define how many of the fixtures are designed for handicapped access.

###### Example Usage Scenario:

None provided

##### 4.1.4.3.3. Task 2 - Layout


###### Task Description:

Layout involves the location of the major fixtures and the stalls that surround them while creating appropriate circulation for occupants and handicapped. The effective delivery of services such as water and getting rid of waste will set a common plumbing wall which makes is cost effective by stacking all plumbing services for the building.

###### Example Usage Scenario:

None provided

##### 4.1.4.3.4. Task 3 - Construction Detailing, Finishes and Lighting



**Task Description:**

hand dryers, trash receptacles, outlets, etc. A closer look at other trades, such as Plumbing, HVAC, and Electrical. The final step of the restroom design involves selecting the materials and lighting appropriate for the building type and clients' requirements. The selection of the style of partitions, faucets, and other fixtures such as whether the toilet is wall hanging or rests on the floor is based on the designer's preferences.

**Example Usage Scenario:**

None provided

## **4.1.5. Process: Roof Design**

The process of roof design is a mixture of aesthetics, weather dissipation, and hiding other building objects such as telecommunications, mechanical, and elevators. The process is iterative, the designer works back and forth between the massing and roof design to create a building design which expresses a character appropriate to the area, client wishes, and building type.

### **4.1.5.1. Introduction**

**Overview:**

The architect determines a type of roof based on the design direction and the character of the building. Using the building massing, the architect lays out the roof. On pitched roofs, refinement of the intersection of the roof planes will be necessary. The architect then determines and designs the drainage. The intersection of the roof with the elevations are designed and detailed. The layout and penetration of other services that are hosted on the roof are considered. Materials are selected.

**Process Scope:**

- Design inputs would cover the process of exterior and interior programs including eaves and overhangs. Interior issues need to address cathedral ceilings, dormers, etc. Exterior roof issues include steeples, parapet roof ventilation, electrical, drainage, recreational areas, planters, irrigation, window washing, skylights, smoke evacuators, access hatches, mechanical screens, roof walk pads, lighting control, and FAA lighting.

**Out-of-Scope:**

- Actual design of electrical, venting, access hatches, smoke evacuators, sidewalk protection canopies.

**Definitions:**

- Dormers (space projection from sloped roof, may be considered standard roof, not unique)
- Recreation areas
- Helipads
- Steeples can also be used as a screen or just ornate
- Screening
- Chimneys
- Vents
- Drainage
- Telecommunications: Transmission Tower


**References:**

- None defined

**Contributors:**

- project team

### 4.1.5.2. Process Diagram: Roof Design



### 4.1.5.3. Process Definition: Roof Design

#### 4.1.5.3.1. Overview

None provided


#### 4.1.5.3.2. Task 1 - Design Roof

##### Task Description:

The determination of roof type is a balance between form and function of the building. The decision on style or shape of the roof is a combination of styles of the neighbor buildings along with the desire of the client. The roof type refers to flat, pitched, gabled, etc. An understanding of the types of services supported by the roof may determine the type of roof selected. The regional climate may dictate a shape of the roof structure to support the amount of wind, precipitation, snow, and also radiation of heat from the sun. After the selection of the roof type, a preliminary design is produced to determine the actual shape and its impact on the building form. The slopes of the roof elements to provide the correct shedding of the climatic element will determine pitches. The changes in the massing elements will force the roof to change as new building masses intersect each other. The function of the spaces below the roof may determine the shape along with the need to enclose building services. The type of material used will have a direct impact into the shape of the roof depending on the material constructability. Finally the surrounding building roof-scapes may dictate a direction for the shape.

##### Example Usage Scenario:

None provided



#### 4.1.5.3.3. Task 2 - Skylight/Clear Story

##### Task Description:

After the shape is created, the integration of any skylights or clear story windows will be integrated into the roof to evaluate the impact and location based on preliminary structural needs. A skylight may not be as simple as a pre-manufactured domed square skylight but could be a complicated barrel vault that runs the length of the building. The intersection of the skylight with the roof becomes critical and may force certain decisions on pitches of roof plains to direct the outside elements away from the glass area.

##### Example Usage Scenario:

None provided


#### 4.1.5.3.4. Task 3 - Layout of Services

##### Task Description:

With the major roof shape determined and items such as skylights, etc. placed, the designer then looks at the projections through the roof of items such as vents, stair/elevator, telecommunications, glass cleaning, and mechanical. Depending on the size of the projection techniques such as providing screens and other methods to hide the services may be required. Depending on the building program areas such as heliports, health and fitness, and walkways may be required to be included in the roof design.

##### Example Usage Scenario:

None provided




#### 4.1.5.3.5. Task 4 - Design Rain/Snow Drainage

##### Task Description:

At this point, after the building services are located the shedding of water needs to be addressed. The runoff of water is calculated based on the roof planes and slopes and a design concept is created to use roof drains, scuppers, or gutters to empty the water from the roof. The weather (water, snow, heat) are the major cause of roof failure. Details are created to communicate how to keep moisture out of the building and delineate the intersection of materials at joints.

##### Example Usage Scenario:

None provided



## 4.2. [AR-2] Compartmentation of Buildings

### Processes Defined in this project:

1. Compartmentation of buildings

### 4.2.1. Process: Compartmentation of buildings

#### 4.2.1.1. Introduction

##### Overview:

The overall process is split into two stages as defined below:

**Stage 1** is concerned with limiting the spread of fire and smoke within the building.

- The building is sub-divided into compartments, enclosed by fire resisting construction.

The building can be sub-divided into compartments by any or all of the following constraints:

- Main Uses
- Spaces occupied by individual owners and/or tenants
- Regulatory geometrical limits set on floor area or space volume.

**Stage 2** is concerned with providing a satisfactory means of escape from a building or part of a building to a place of safety.

- By providing enough Escape Routes of the correct capacity, and which are adequately lit and suitably located.

A satisfactory Means of Escape is provided by ensuring :

- *There is an adequate number of exits, to serve a known number of occupants, within a Space, Compartment or Storey.*
- *There are enough Escape Routes of adequate capacity within a Space, Compartment or Storey, to serve all the occupants, likely to use the route in the event of fire.*
- *That, if any Space, Compartment or Storey is likely to render any Escape Route unusable due to the emission of smoke, then either, smoke seals to exit doors, or a pressurized lobby to control the passage of smoke are provided.*
- *That Escape Routes are adequately spaced to limit the travel distance to the nearest exit.*
- *That Escape Routes are adequately lit by means of an independent power supply.*

This IFC R2 project will focus on Stage 1 -- the process for identifying fire compartments and the fire protection at their notional boundaries, in order to limit the spread of fire and smoke within the building.

### Process Scope:

- None provided

### Out-of-Scope:

- Fire Protection to Elements of structure.
- Fire Protection to Electrical, Mechanical and Plumbing Services.
- Fire Fighting Equipment
- Fire Resistance and Surface Spread of Flame
- Interrelationship with adjoining buildings and to the boundary.

### Definitions:

- **Fire Use Classification:** classification listing the different possible uses of a building or space for the purposes of fire compartmentation
- **Fire Use:** A member of a Fire Use Classification.
- **Main Use Space:** Is a building or part of a building considered significant for Fire Compartmentation.
- **Ancillary Use Space:** Is a part of a building which supports a Main Use and which is not considered significant for Fire Compartmentation. An Ancillary Use may be considered a Main Use in its own right if it meets certain criteria.
- **Fire Compartment:** A building, or part, comprising one or more spaces constructed so as to prevent the spread of fire to or from another part of the same or adjoining buildings and which meets the area, volume, or occupancy limits set by Statutory Requirement.
- **Single Occupancy Space:** A space possessed and used by only one person or organisation.
- **Height Above Grade:** Height of floor of top storey of Fire Compartment above accessible horizontal surface external to the Fire Compartment.
- **IsSprinklered:** The building is filled throughout with an automatic sprinkler system.


### References:

- Building Regulations 1991. Approved Document B: Fire Safety.
- Uniclass classification.
- Ci/SfB classification - space classification.
- British Standards.

### Contributors:

- Project Team (see project summary)

## 4.2.1.2. Process Diagram: Compartmentation of buildings



### **4.2.1.3. Process Definition: Compartmentation of buildings**

#### **4.2.1.3.1. Overview**

It is assumed that the fire usually starts in one place, and spreads to other parts of the building. In order to allow the occupants of the building to escape, the first priority is to stop the spread of fire and smoke to other parts of the building, as well as to maintain common escape routes free of fire and smoke. Compartmentation controls fire within a limited space, allowing occupants of the building to escape from the seat of the fire to a place of safety.

Note: Tasks A through D are repeated for each building storey.

#### **4.2.1.3.2. Task A - Identify Main/Ancillary Use Spaces**

**Task Description:**

For each building identify the Main Use Spaces and Ancillary Use Spaces.

**Example Usage Scenario:**

None provided

#### **4.2.1.3.3. Task B - Adjust Main/Ancillary Use Spaces according to Code**

**Task Description:**

Analyse the Ancillary Use Spaces with reference to regulations to see if they need to be treated as Main Use Spaces in their own right. If not subsume Ancillary Use Spaces into their corresponding Main Use Spaces.

**Example Usage Scenario:**

None provided

#### **4.2.1.3.4. Task C - Identify Single Occupancy Spaces**

**Task Description:**

For each building identify all the Single Occupancy Spaces contained within the building.

**Example Usage Scenario:**

None provided

#### **4.2.1.3.5. Task D - Check Areas/Volumes to Design Fire Compartments**

**Task Description:**

Specify the boundaries of Main Use Spaces and Single Occupancy Spaces as Fire Compartment boundaries.

Analyse the Fire Compartments defined by the boundaries specified in task C. For each compartment check the regulations governing the maximum dimensions for the Fire Use into which its use is classified. Subdivide each Fire Compartment as necessary in order to meet the rules. NB. the maximum allowable dimensions of a Fire Compartment are likely to also depend on whether or not the building in which the compartment is located is sprinklered and on the height above grade of the top floor of the building in which the Fire Compartment is located.

**Example Usage Scenario:**

None provided

## **4.3. [BS-1] HVAC System Design**

**Processes Defined in this project:**



1. HVAC Duct System Design
2. HVAC Piping System Design

### **4.3.1. Process: HVAC Duct System Design**

#### **4.3.1.1. Introduction**

**Overview:**

See Project summary.

**Process Scope:**

- Select and locate components to be connected in the duct system
- Connect components with ducts and fittings
- Locate other system components: dampers, etc.
- Facilitate sizing ducts and fittings
- Facilitate interference checking
- Facilitate pressure loss calculations
- Facilitate fan selection
- Generate final system representation

**Out-of-Scope:**

- Selection of system type and system configuration
- Actual sizing the duct and fittings
- Performing interference checks
- Performing pressure loss calculations
- Performing fan selection

**Definitions:**

- ASHRAE - American Society of Heating Refrigeration and Air Conditioning Engineers
- SMACNA - Sheet Metal and Air Conditioning Contractor's National Association
- BACnet – Building Automation and Control Network


**References:**

- ASHRAE Handbooks
- SMACNA HVAC Duct Construction Standards
- BACnet Specifications (ANSI/ASHRAE 135-1995)
- IFC R2.0 BS-3 Project: Pathway Design and Coordination

**Contributors:**

- James Forester, North American Chapter: Technical Coordinator
- North American Chapter -- Building Services Committee
- United Kingdom Chapter -- Building Services Committee
- German Chapter -- HVAC Committee
- Nordic Chapter -- HVAC Committee
- French Chapter -- HVAC Committee

### 4.3.1.2. Process Diagram: HVAC Duct System Design



### 4.3.1.3. Process Definition: HVAC Duct System Design

#### 4.3.1.3.1. Overview

Once an appropriate system type has been determined (outside of scope), the HVAC Duct System Design process begins by selecting and locating air terminal devices, air terminal boxes and fans that will be part of the system. Reflected ceiling plans may be available showing light fixtures, sprinklers and the ceiling grid to aid in the location of air terminal devices. If these are not available the engineer selects locations for the air terminal devices and submits the locations to other members of the design team for coordination. To appropriately locate the air terminal boxes and devices, structural information is required so that initial interferences may be avoided.

The next step is to connect the air terminals, terminal boxes and fans together with ducts and fittings. A network representation of this system layout is typically generated for use in calculating duct sizes and a graphical representation is generated for coordination with other disciplines.

The room air flow rates are then assigned to the air terminals. These air flow rates are determined by the building cooling and heating load calculations; these processes are defined in the IFC 1.0 Specifications.

The duct and fitting sizes are then calculated based upon these air flow rates and the duct system design criteria. The duct and fitting sizes are then updated in the graphical representation of the system.

Other required system components (i.e., dampers, sensors, etc.) are then located on the graphical representation. This process requires various architectural information such as the locations of fire rated walls, exit corridors, etc., which are available from the architectural plans. Any components that require other disciplines to respond are identified, such as electrical power required to fan powered terminal boxes.

Once these components are located, an interference check is performed. This requires the coordination with the other building disciplines and may require resizing or relocating ducts, fittings, etc.

A final duct system pressure loss calculation may be required beyond that made during the duct sizing based on changes from estimated values to actual values that can only be determined after the duct sizes are finalized. With the final pressure loss, the total air flow and the engineering design criteria, a fan can be selected.

Primary difficulties in the duct system design process are coordination with other disciplines to prevent conflicts for space and to predict sound levels that result from air flow in the ducts and air terminals.

#### 4.3.1.3.2. Task A - Select and Locate System Components

##### Task Description:


Before the engineer can select and locate system components, the following information is required from other members of the design team:

- Ceiling grid plans (architect)
- Reflected ceiling plans (architect)
- Lighting plans (architect or lighting designer)
- Structural plans (structural engineer)
- Plumbing plans (plumbing engineer)
- Piping plans (HVAC engineer)
- Sprinkler plans (fire protection engineer)
- Smoke detector plans (fire protection engineer)
- Speaker plans (architect or electrical engineer)

With the above information, the engineer can perform the tasks required for this process. If some of the above information is unavailable, the engineer must either generate it manually or make assumptions based on the function and usage of the spaces involved in the design.

Generally there are three types of system components to be selected and located for this process:

- **Fan(s):** The location of the fan(s) used for moving the air in the duct system. The fan(s) may be for supplying, returning or exhausting air from the building or space. The fan(s) may be stand alone or part of a manufactured assembly, which may include coils, filters, mixing boxes, etc. Combination fans, coils etc. may be factory assembled or assembled at the project site. The exact size and capacity of the fan(s) are not required at this stage, though an approximate fan size is necessary to ensure the space selected for the fan is adequate. Though not essential, having the size of the fan outlet is useful in sizing the transition between the fan outlet and the duct.
- **Air Terminal Boxes:** Depending on the type of HVAC system, the system may or may not have air terminal boxes. Terminal boxes are typically located in a branch duct downstream from the main supply duct. There are several different types of terminal boxes. They are used in various ways to control the amount and or temperature of the air being supplied to one or more spaces with similar heating and cooling load characteristics. It is desirable but not necessary to know the exact terminal boxes being used in order to size the associated ducts. If the exact terminal box being used is known, the exact duct connection size and pressure loss through the terminal boxes are known. Also terminal boxes from different manufactures have different dimensions and knowing the exact dimensions and clearances required for maintenance can prevent future conflicts for space.



Terminal boxes are typically located after the air terminal devices used for distributing the air in the spaces are located. This allows the terminal boxes to be positioned to permit the shortest duct runs between the terminal box and the air terminal devices it supplies.

- **Air Terminal Devices:** Air terminal devices are used to distribute the air from the duct system to the spaces or to remove air from the spaces. The air terminal device can be connected to the supply, return or exhaust air ducts in different ways:

Directly into the side of a main or branch duct or on a short duct section that allows for a volume damper and/or a lower resistant transition from the duct to the air terminal device. This type of connection is used where the duct is exposed in the space.

Directly on the outlet of a terminal box.

On the end of a branch duct from the main duct or from a duct on a terminal box. The air terminal device may terminate in an opening in a ceiling or wall, or be exposed entirely in the space.

An air terminal device can simply be located within an opening through a wall that forms a chase that is part of the general building construction or to an above ceiling plenum used for transferring return air. Locating an air terminal devices used in this way are not required for sizing the duct system, although they are usually located at the same time other air terminal devices are located.

Selecting the exact air terminal devices and their accessories at this stage is not required to size the duct system but is desirable to keep from revisiting each of the air terminal devices a second time. Making a selection also supplies the exact duct connection required and the exact pressure loss through the air terminal device which is necessary in the final design of the duct system for the fan selection.

#### **Example Usage Scenario:**

None provided


### **4.3.1.3.3. Task B - Connect Components with Ducts and Fittings**

#### **Task Description:**

Before the engineer can connect air terminals, boxes and fans with ducts and fittings, the following information is required from other members of the design team:

- Floor plans (architect)
- Structural plans (structural engineer)
- Coordination requirements from any other disciplines

This step involves preparing drawings that schematically represent the system under design. The duct is typically drawn from the fan to the air terminal boxes, if any, and then to the air terminal devices. Various types of elbows, tees and other fittings are utilized so each fitting must be designated as to what type is being used. These schematics are then used to begin coordination with other disciplines which are impacted by the duct system. The information derived from the air flow associated with each air terminal device together with the schematic drawing is used by a duct sizing program to determine actual duct sizes. Often the duct connections to different types of equipment are standardized.



#### **Example Usage Scenario:**

None provided

### **4.3.1.3.4. Task C - Sizing the Duct and Fittings**

#### **Task Description:**

The ducts are sized using the information derived from the schematic drawings and the design criteria established by the engineer. Design criteria include such information as type of design (constant pressure, static regain, etc.), maximum velocity, maximum height of duct, material to be used, etc. The actual

methodologies and algorithms used for sizing of the duct and fittings is out of scope, as this is application specific.

**Example Usage Scenario:**

None provided

#### **4.3.1.3.5. Task D - Locate Other System Components**

**Task Description:**

The location of other duct system components is determined from information in the schematic drawings and the design criteria established by the engineer. Other components, such as fire dampers, volume control dampers, louvers, filters, etc., are then located on the drawing. These components have pressure losses that may only be precisely determined after the actual duct sizes are known. After these pressure losses are determined, the total pressure loss is calculated. In many cases the pressure loss for these components are known before the ducts are sized or can be closely estimated so they can be entered before sizing the ducts and fittings.

Control elements, such as sensors, actuators and controllers, can also be specified at this point. The design engineer typically defines the general parameters of a control device. However, a control system vendor may utilize many different mechanisms to achieve the desired effect intended by the design engineer. For this reason, only a subset of control element information is necessary.

**Example Usage Scenario:**

None provided

#### **4.3.1.3.6. Task E - Interference Check**

**Task Description:**

Before the engineer can perform an interference check, the following information is required from other members of the design team:

- Floor plans (architect)
- Ceiling grid plans (architect)
- Reflected ceiling and/or lighting plans (architect or lighting designer)
- Power plans (electrical engineer)
- Piping plans (HVAC engineer)
- Plumbing and sprinkler plans (plumbing or fire protection engineer)
- Structural plans (structural engineer)
- Coordination requirements from any other disciplines

Interference checking identifies where changes are required in the location or size of specific ducts in order to eliminate physical conflicts with other building components or systems. An example scenario could be that the height of a duct is too great, thus requiring a transition fitting to clear a beam or a pipe. After any interferences are corrected, the total pressure loss for the system can be calculated. Performing the actual interference check is out of scope, as this is application specific.

Refer also to the IFC R2.0 BS-3 Project: Pathway Design and Coordination.

**Example Usage Scenario:**

None provided



**Example Usage Scenario:**

None provided

## **4.3.2. Process: HVAC Piping System Design**

### **4.3.2.1. Introduction**

**Overview:**

See project summary.

**Process Scope:**

- Select and locate components to be connected in the piping system
- Connect components with pipe and fittings
- Locate other components: strainers, valves, etc.
- Facilitate sizing pipes and fittings
- Facilitate interference checking
- Facilitate pressure drop calculations
- Facilitate pump selection
- Facilitate flow analysis
- Generate final system representation

**Out-of-Scope:**

- Selection of system type
- Actual sizing the pipe and fittings
- Performing interference checks
- Performing pressure drop calculations
- Performing pump selection
- Performing flow analysis

**Definitions:**

- ASHRAE - American Society of Heating Refrigeration and Air Conditioning Engineers
- BACnet – Building Automation and Control Network


**References:**

- ASHRAE Handbooks
- BACnet Specifications (ANSI/ASHRAE 135-1995)
- IFC R2.0 BS-3 Project: Pathway Design and Coordination

**Contributors:**

- James Forester, North American Chapter: Technical Coordinator
- North American Chapter -- Building Services Committee
- United Kingdom Chapter -- Building Services Committee
- German Chapter -- HVAC Committee
- Nordic Chapter -- HVAC Committee
- French Chapter -- HVAC Committee

### 4.3.2.2. Process Diagram: HVAC Piping System Design



### 4.3.2.3. Process Definition: HVAC Piping System Design

#### 4.3.2.3.1. Overview

Once an appropriate system type (chilled water, hot water, condenser water, etc.) has been determined (outside of scope), the Piping System Design process begins by selecting and locating pumps, coils, chillers, boilers, heat exchangers, cooling towers, etc., that will be part of the system. To appropriately locate the equipment, architectural and structural information is required so that initial interferences may be avoided.

The next step is to connect the various pieces of equipment together with pipes and fittings, including specifying the types of fittings (i.e., 90 degree elbow, 90 degree long-radius elbow, 45 degree elbow, thru tee, etc.). A graphical representation of this system layout is generated for use in calculating pipe sizes and coordination with other disciplines.

The fluid flow rates, fluid temperature changes, and pressure drops are assigned to the coils, heat exchangers, or other pieces of equipment that remove or add heat or power from the system. The fluid flow rates are determined from the building cooling and heating load calculations (defined in the IFC 1.0 Specifications), the engineer's design criteria, or from specific equipment requirements.

The pipe and fitting sizes will then be calculated based upon these fluid flow rates and the pipe system design criteria. The pipe and fitting sizes are then reflected in the graphical representation of the system.

Other required system components, such as valves, strainers, etc., are then located on the graphical representation. Any components that require other disciplines to respond are identified, such as electrical or pneumatic power required to operate control valves.

Once these components are located, an interference check is performed. This requires spatial coordination with other building disciplines and may require some pipes to be relocated.



A pressure drop calculation is then performed to determine the system pressure drop. With this information as well as the total fluid flow rate and the engineering design criteria, a pump can be selected.

Primary difficulties in the pipe system design process are coordination with other disciplines to prevent conflicts for space job and to predict sound levels which result from rotating equipment and fluid flow in pipes.

#### **4.3.2.3.2. Task A - Select and Locate System Components**

##### **Task Description:**

Before the engineer can select and locate system components, the following information is required from other members of the design team:

- Floor plans (architect)
- Reflected ceiling plans (architect)
- Structural plans (structural engineer)
- Duct plans (HVAC engineer)
- Plumbing plans (Plumbing engineer)
- Pipe system design criteria (HVAC engineer)

The selection of equipment (coils, evaporators, condensers, unit heater, radiation, etc.) the piping system will serve is made by the designer, using information from the heating and cooling load calculations in conjunction with manufacturers' equipment information and engineering judgment. The selection of equipment should include the type and size of pipe connections to the equipment. The physical location of the equipment is then determined, giving consideration to space requirements for maintenance and removal of coils and tube bundles.

##### **Example Usage Scenario:**

None provided

#### **4.3.2.3.3. Task B - Connect the Components with Pipe and Fittings**

##### **Task Description:**

Before the engineer can connect equipment with pipes and fittings, the following information is required from other members of the design team:

- Floor plans (architect)
- Structural plans (structural engineer)
- Coordination requirements from any other disciplines

This step involves preparing a schematic representation of the system under design. The various types of elbows, tees and other fittings that are utilized must be designated as to what type is being used and its pressure drop characteristics. These schematic representations are then used to begin coordination with other disciplines that are impacted by the piping system. Interferences must include pipe hangers and supports, and insulation when applicable. Often the piping connections to a given type of coil, unit heater or other piece of equipment are standardized. These assemblies of pipe, valves, fittings, etc., can be treated as standardized piping templates for the given piece of equipment.

##### **Example Usage Scenario:**

None provided

#### **4.3.2.3.4. Task C - Locate Other System Components**

##### **Task Description:**

The locations of other piping system components (i.e., valves, strainers, etc.) are determined from information in the schematic drawings and the design criteria established by the engineer. These components

have pressure drops, and connections that may be different from the pipe size. The requirement for some or all of these components may come from equipment selection programs, from standard lists or libraries, or be determined manually by the engineer.

Control elements, such as sensors, actuators and controllers, can also be specified at this point. The design engineer typically defines the general parameters of a control device. However, a control system vendor may utilize many different mechanisms to achieve the desired effect intended by the design engineer. For this reason, only a subset of control element information is necessary.

**Example Usage Scenario:**

None provided

#### **4.3.2.3.5. Task D - Sizing the Pipe and Fittings**

**Task Description:**

The pipe and fittings are sized using the information derived from the schematic drawing and the design criteria established by the engineer. Design criteria include such things as maximum velocity, pipe material to be used, etc. The actual sizing of the pipe and fittings is out of scope, as this is application specific.

**Example Usage Scenario:**

None provided

#### **4.3.2.3.6. Task E - Interference Check**

**Task Description:**

Before the engineer can perform an interference check, the following information is required from other members of the design team:

- Floor plans (architect)
- Ceiling grid plans (architect)
- Reflected ceiling and/or lighting plans (architect or lighting designer)
- Power plans (electrical engineer)
- Duct plans (HVAC engineer)
- Plumbing and sprinkler plans (plumbing or fire protection engineer)
- Structural plans (structural engineer)
- Coordination requirements from any other disciplines

Interference checking identifies locations where changes are required in the location of pipes in order to eliminate physical conflicts with other building components or systems. Interference checking must account for insulation, pipe supports and operating and servicing of valves, strainers, etc. For example, placing valves with stems down is not good engineering practice, while a horizontal stem requires more space for the stem, and a vertical stem may require more space at the side for service access. Performing the actual interference check is out of scope, as this is application specific.

Refer also to the IFC R2.0 BS-3 Project: Pathway Design and Coordination.

**Example Usage Scenario:**

None provided

#### **4.3.2.3.7. Task F - Identify alternatives to design problems**

**Task Description:**

This step requires the designer to go back and redesign certain portions of the system. This may involve regenerating the schematic design documents and recalculating system component sizes. Note that this step may occur at any point in the process.

**Example Usage Scenario:**

None provided

#### **4.3.2.3.8. Task G - Pressure Drop Calculations**

**Task Description:**

After interference conflicts are corrected the total pressure drop for the system can be calculated. This information is essential to properly select a pump that will serve the piping system. Performing the actual pressure drop calculation is out of scope, as this is application specific.

**Example Usage Scenario:**

None provided

#### **4.3.2.3.9. Task H - Pump Selection**

**Task Description:**

With the total fluid flow rates and pressure requirements (as determined in the preceding steps) in combination with the engineering design criteria for the pump (i.e., type of pump, pump materials, etc.), the pump selection can be made using a pump manufacturer's pump selection program. With the selection of the pump, consideration must be given to isolating the pump from the influence of expansion and contraction of the piping system due to temperature changes, and to the transfer of noise and vibration from the pump to the building. Performing the actual pump selection is out of scope, as this is application specific.

**Example Usage Scenario:**

None provided

#### **4.3.2.3.10. Task I - Flow Analysis**

**Task Description:**

For piping systems with diversified loads (so that all coils do not need maximum flow at the same time, or where there are multiple pumps in the system) the flow rates, pressure drops and temperatures may change randomly. Under these conditions good engineering practice requires further analysis of the flow. The results obtained from the pipe sizing program are necessary to the use of a flow analysis program. Performing the flow analysis is out of scope, as this is application specific.

**Example Usage Scenario:**

None provided

#### **4.3.2.3.11. Task J - Generate Final System Representation**

**Task Description:**

After the components are selected and the pipe and fittings sized, the results are used to generate graphical representations showing the actual size and location of the pipes, fittings and all of the components.

**Example Usage Scenario:**

None provided

## 4.4. [BS-3] Pathway Design and Coordination

### Processes Defined in this project:

1. Coordination of mechanical systems
2. Coordination of mechanical systems within the building model

### 4.4.1. Process: Pathway Design and Coordination

#### 4.4.1.1. Introduction

##### Overview:

The design of pathways contains the draft layout, the coordination and the representation of mechanical and electrical system-pathways to be installed.

This design process is carried out after the first coordination with the architect and structural engineers, and includes load estimates, energy and systems definitions required for a building.

The process ends with drawings containing the coordinated pathways for the mechanical and electrical installations (i.e. heating, cooling, air-conditioning, plumbing, fire-protection and electrical power) within a building.

The chapter on hand defines the prerequisites for the design of pathway based on generalized design of mechanical facilities.

##### Process Scope:

- Select and locate plant and other equipment to be connected to the system
- define pathway for different media (duct- and pipe work)
- coordinate pipe- and duct work within the pathway
- coordinate pathways within architectural and structural restraints

##### Out-of-Scope:

- None provided

##### Definitions:

- ISO
- DIN
- VDI
- SIA
- ASHRAE
- CIBSE


##### References:

- None provided

##### Contributors:

- Project Team (see project summary)

#### 4.4.1.2. Process Diagram: Pathway Design and Coordination



#### 4.4.1.3. Process Definition: Pathway Design and Coordination

##### 4.4.1.3.1. Overview

Based on the building model and the conditions (program) defined by the customer, an initial estimate of required energy, technical equipment and systems is defined. The process of designing the pathway starts by defining the required spatial extents for technical equipment, piping, ducting and electrical routes.

A rough building layout by the architect will frequently be available showing the suggested locations for plant rooms and risers.

Considering these parameters, the engineer defines the necessary locations for plant areas and suggests the routing of the main pathways.

The required plant area and main pathways are represented in the M & E drawings.

This draft is presented to the architect/customer with details on space requirements (sections). Thereafter, a review of the suggested design solution will take place, taking into account the structure, the initial and future investment, user requirements, operating expenses and the flexibility achieved.

Parameters from the building model, the definition of systems and the routes of each media type can be combined to define the pathway. Air ducts, including equipment (fire dampers, VAV-boxes, etc.) are combined to form a ventilation pathway. Pipes for heating, cooling or plumbing are combined to form a media pathway. Electrical trays are combined to form an electrical pathway. Each pathway should allow variables for necessary insulation or fire proofing, as well as variables for necessary access for installation and maintenance. The optimization of the pathway itself can be done by varying the distance and position of ducts, pipes or trays. Every pathway must be coordinated within the architectural and structural restraints, as well as with each other.

A final definition of the spatial requirements for technical equipment and media distribution, defines the location of the pathway. The translation of the pathway into geometrical forms is carried out. These drawings serve as a guideline for the ongoing building services design.

The definitions of the structural systems (flat slab, concrete or steel construction, beams, etc.) reflect the location of the plant areas, risers and pathways. Collision detection with walls, slabs, binding beams etc. should be made and openings have to be defined.

#### **4.4.1.3.2. Task A - Defining required space for stations**

##### **Task Description:**

This step contains the dimensioning of main components for different systems, inquiry of the approximate space requirements and corresponding placing of the technical areas in the building model.

##### **Example Usage Scenario:**

None provided



#### **4.4.1.3.3. Task B - Defining the required space for pathways**

##### **Task Description:**

This step contains the dimensioning of the energy and media supply as well as the specification of the pathway.

##### **Example Usage Scenario:**

None provided



#### **4.4.1.3.4. Task C - Geometrical representation of stations and pathways**

##### **Task Description:**

This step contains the geometrical representation of the defined centralized media supply and pathway.

##### **Example Usage Scenario:**

None provided



#### 4.4.1.3.5. Task D - Interference check

**Task Description:**

Collision detection within building services and building model.

**Example Usage Scenario:**

None provided



#### 4.4.1.3.6. Task E - Identify alternatives to resolve the collisions

**Task Description:**

This step requires the designer amend and redesign certain portions of the system to resolve possible collisions. This may involve regenerating schematic design documents and recalculating system component and sizes. Note that this step may occur at any point in the process.

**Example Usage Scenario:**

None provided



#### 4.4.1.3.7. Task F - Itemization of Pathway

**Task Description:**

This step contains the detailed output of a pathway. Consideration of connection points and branches as well as placement and distance of each pipe or duct, the cross-sectional dimension of the pathway is brought into line with the respective conditions and will be optimized.

**Example Usage Scenario:**

None provided



#### 4.4.1.3.8. Task G - Coordination of branches

##### Task Description:

This step contains the coordination of different trades within the design of pathway at branches as well as the coordination with structural conditions like binding beams etc.

##### Example Usage Scenario:

None provided



#### 4.4.1.3.9. Task H - Interference check

##### Task Description:

Final collision detection within building services and building model.

##### Example Usage Scenario:

None provided

#### 4.4.1.3.10. Task I - Determination of openings

##### Task Description:

This step contains the specification of openings defined by the itemized pathway or single pipes or ducts.

##### Example Usage Scenario:

None provided

#### 4.4.1.3.11. Task J - Generate final system representation

##### Task Description:

This step takes us back to HVAC System Design.

##### Example Usage Scenario:

None provided





## 4.5. [BS-4] HVAC Loads Calculation

### Processes Defined in this project:

1. Building Heating and Cooling Load Calculation

### 4.5.1. Process: Building Heating and Cooling Load Calculation

#### 4.5.1.1. Introduction

##### Overview:

Load calculations serve as the basis for all design stages of the building services design. The results of the load calculations enable the designer to dimension the plant equipment and to determine the required space for plant room.

Load calculations are an official proofing method (in Germany for example the proof for heat loss protection must be given in the course of a project), a mode for calculating the heating/cooling load or for the yearly dynamic load simulation:

The process terminates in the complete calculations and the data exchange into the IFC model.

The chapter on hand defines the prerequisites for the computer-aided load calculation .

##### Process Scope:

- Calculating heating/cooling load

##### Out-of-Scope:

- bounding conditions like adjacent buildings,

##### Definitions:

- DIN
- ISO
- VDI
- ASHRAE


##### References:

- DIN 4701, 4108
- VDI 6021
- VDI 2078

##### Contributors:

- |                      |                       |
|----------------------|-----------------------|
| ▪ Felix Brückner     | vögtlin engineering   |
| ▪ Rainer Hirschberg  | GTS                   |
| ▪ Doris Huber        | 'ESS                  |
| ▪ Eberhard Michaelis | Softtech              |
| ▪ Ulrich Paar        | Ziegler Informatics   |
| ▪ Robert Rottermann  | RoCAD Informatik      |
| ▪ Willi Spiegel      | Triplan GmbH          |
| ▪ Rolf Tonke         | Planungsgruppe M+M AG |
| ▪ Kurt Weber         | Pit-cup GMBH          |
| ▪ Michael Kuehn jr.  | Kuehn Bauer Partner   |

### 4.5.1.2. Process Diagram: Building Heating and Cooling Load Calculation



### 4.5.1.3. Process Definition: Building Heating and Cooling Load Calculation

#### 4.5.1.3.1. Overview

After the completion of the building model with its geometric and physical building specifications by the architect, the data is to be extracted using the IFC-Model. The IFC-Model includes all architectural building components of a defined room, the attributes and the relationships of the components to each other. The IFC-Model does not include any the description of the adjacent buildings (e.g. input for external shading).

The parameters like the room temperatures, required air changes, people or machine loads or other necessary data is submitted if known to the design team. If certain data is not know to the design team plausible data is assumed to provide preliminary answers.

National boundary conditions has to be transmitted alternatively or in respectively conformist form.

The data exchange to the Calculation-Software does not require any exchange of graphical data. The exchange should be independent from the calculation method applied because it describes only the physical data.

After the exchange of data, the engineer checks data transmitted for completeness and possibly amend the data. The engineer has to input the boundary conditions as well as the meteorological data for the load calculation method.

The definition of zones, as a result of the assigned plant equipment, can be carried out by simply numbering them. All rooms of one level having common boundaries can be defined as one zone. Another form of zoning can be made by direct plant assignment. This method ensures, that considerations of energy as well as the simultaneity of use conditions within plants are considered.

As a results of load calculations, the physical qualities of building components may be changed and submitted to an optimization process. This is requested to the IFC-building model. After changing the corresponding data a further exchange of basic data is carried out and the process starts once more.

A revision phase is necessary if there is change to the plant assignment or there are variations to the boundary conditions within the process.

At the end of the process the results of the load calculations are provided for the IFC model for further processing. The definition of technical stations, pathway and their space requirements as well as the dimensioning of system components for building services design are based on these results.


#### 4.5.1.3.2. Task A - IFC-Model take-over

##### Task Description:

This step contains the import of extracted data from the building model like component geometry and component qualities. The construction of this physical data exchange format corresponds in the construction to a Physical-STEP file.

##### Example Usage Scenario:

None provided




#### 4.5.1.3.3. Task B - Specification of zones

##### Task Description:

Considering the building geometry, zones are defined for the execution of the load calculations.

##### Example Usage Scenario:

None provided




#### 4.5.1.3.4. Task C - Load calculations

##### Task Description:

This step contains the execution of the load calculations.

##### Example Usage Scenario:

None provided



#### 4.5.1.3.5. Task D - Results into IFC-Model

##### Task Description:

Exchanging the results of the load calculations to the IFC model.

##### Example Usage Scenario:

None provided


#### 4.5.1.3.6. Task E - Design modifications

##### Task Description:

This step contains the iterative event for the execution of all calculations by variation or change of the zones, usage requirements etc., according to optimization by changing parameters .

##### Example Usage Scenario:

None provided



## 4.6. [CS-1] Code Checking - Energy Codes

### Processes Defined in this project:

#### 1. Commercial and Residential Energy Code Compliance Checking

Code compliance is performed by building designers, systems designers, and code enforcement officials. Compliance with codes begins during programming when designers determine which codes apply to the building project. Preliminary code reviews are frequently performed during schematic design and more thorough reviews are performed by members of the design team late in the design process before construction documents are complete. Building code officials perform plan reviews as part of the building permitting process. Designers and code officials perform drawing takeoffs as necessary to ensure compliance. Information about building systems, assemblies, layout, etc. is gathered during this process and compared to the requirements for each applicable code. Virtually all systems within a building are constrained in some way by codes (or voluntary design standards), hence codes are relevant to most other design processes. Energy codes, the subject of this Release 2.0 proposal, are strongly related to architectural, HVAC, and electrical design processes.

Code compliance checking is the process of assessing whether a building complies with codes enforced by local jurisdictions or with voluntary design standards promulgating by various standard-writing entities.

### 4.6.1. Process: Commercial and Residential Energy Code Compliance Checking

#### 4.6.1.1. Introduction

##### Overview:

This process will support applications that determine whether buildings conform with energy-efficiency codes for new construction. The CS-1 project will focus on two model codes that are widely used in the United States. The project will primarily address requirements pertinent to building envelope and lighting.

##### Process Scope:

- Commercial energy code compliance (e.g., ASHRAE/IES 90.1-1989 [Code])
- Residential energy code compliance (e.g., MEC)
- Prescriptive code requirements
- Performance code requirements

**Out-of-Scope:**

- Determination of which codes apply
- Modeling of code requirements (i.e., the object model will not include the code requirements)
- Modeling of energy code provisions not normally addressed on the building plans; e.g. compliance procedures, detailed product and construction specifications, and other information normally relegated to project specifications.

**Definitions:**

- MEC: Model Energy Code
- HVAC: heating, ventilating, and air-conditioning

**References:**

- Model Energy Code, The Council of American Building Officials; Falls Church, VA; 1993.
- ASHRAE/IES Standard 90.1-1989, Energy Efficient Design of New Buildings Except Low-Rise Residential Buildings; ASHRAE, Atlanta, GA; 1989.
- Energy Code for Commercial and High-Rise Residential Buildings, Codification of ASHRAE/IES 90.1-1989 Energy Efficient Design of New Buildings Except Low-Rise Residential Buildings; ASHRAE, Atlanta, GA; 1993.


**Contributors:**

- Rob Briggs, PNNL (NA)
- Tan You Tong, ITI (S)
- Tan Kee Wee, NCB (S)
- Philippe Debras, CSTB (F)
- Robert Amor, BRE (UK)
- Dave Chassin, PNNL (NA)
- Filiz Ozel, ASU (NA)
- Han Kiliccote, CMU (NA)


#### ***4.6.1.2. Process Diagram: Commercial and Residential Energy Code Compliance Checking***

Note: Building codes typically employ two different regulatory approaches: prescriptive requirements and performance requirements. The two-part diagram below illustrates the two different processes corresponding with these two different approaches. Most codes are neither purely prescriptive nor purely performance-based, but rather, contain elements of both types of requirements either in combination or as alternative paths for demonstrating compliance. In its simplest form, a prescriptive requirement says that object or attribute A must have value B. In contrast a performance requirement says object A must perform as well as C, where C can range from a model whose performance must be analyzed to a static value for a performance metric.

## Part A - Process for Prescriptive Code Requirements



## Part B - Process for Performance Code Requirements



### 4.6.1.3. Process Definition: Commercial and Residential Energy Code Compliance Checking

#### 4.6.1.3.1. Overview

Applicable energy codes are normally identified at the programming stage of the project. At the beginning of schematic design, the architect, HVAC engineer, energy consultant, or other designated design team member with responsibility for energy code compliance identifies those code requirements likely to constrain the building design. Depending on the severity of the code constraints, compliance with these requirements

may be spot checked as the design process progresses, or the energy requirements may be largely ignored until a final compliance check is done, usually at the end of the design development phase of the project.

Most energy code requirements are not strictly prescriptive, but rather constrain the performance of an assembly, subsystem, or major building system. Determining compliance with these requirements frequently requires multiple inputs and some computation. Enabling the necessary data to be managed and manipulated using IFC's will eliminate manual tasks and enable energy code compliance to be checked more easily and frequently during the design process, resulting in compliance at lower cost and with less disruption to the design process. The capability to associate code constraints with objects in the building model will enable design applications to monitor conformance with codes without concurrent operation of code-checking applications. Designers can then focus on the design with confidence that they will be notified if proposed design changes violate code requirements.

#### 4.6.1.3.2. Task A - Identify Applicable Code Requirements

##### Task Description:

This process begins with the intent to demonstrate that a given proposed building design complies with a given energy code.

Some requirements in the code (or even major sections of the code) may not apply due to particular characteristics of the project, such as its location, intended use, or number of stories. Some specific energy code-related examples of requirements that are conditionally applicable based on project characteristics are listed below.


- Certain buildings may be exempted from all envelope insulation requirements based on very low connected loads or the absence of space-conditioning equipment.
- Insulation of the exposed perimeter edges of slab-on-grade construction is required in climates with greater than 3,000 heating degree days base 65°F but is not required in climates with 3,000 or fewer heating degree days.

The applicability of other code requirements may depend on specific conditions or exceptions in the code or on definitions of the objects addressed in the requirements. These conditions must be evaluated before the relationship between a building object and an applicable code constraint can be established. Some examples of these conditions are listed below.

- Exterior above-grade walls are subject to insulation requirements, but parapet walls and wing walls are exempt from these requirements.
- Insulation requirements apply to interior walls separating conditioned from unconditioned spaces but otherwise do not apply to interior walls.
- Basement wall insulation is required in many locations, but it is not required when walls are more than one story below grade.
- Either wall or roof insulation requirements may apply to steeply sloping roofs depending on the slope of the assembly.
- Lighting efficiency requirements apply for most building use types, but they do not apply to hotel guest rooms.


##### Example Usage Scenario:

Figure 1 shows an insulated slab edge. The applicability of code requirements governing the R-value and depth of this insulation is dependent on the climate in which the building is built and whether or not the slab edge occurs at the boundary between conditioned and unconditioned space. If the location has 3,000 or fewer heating degree days base 65°F or if the space circumscribed by the slab perimeter is unconditioned, no slab edge insulation is required.



**Figure 1 - Insulated Slab-on-Grade Perimeter**

Figure 2 shows a parapet wall. Although on the building elevation the parapet wall may be indistinguishable from the exterior wall, the insulation requirement that applies to the exterior wall does not apply to the parapet wall.



**Figure 2 - Parapet Wall**

#### 4.6.1.3.3. Task B - Record Code Constraints

##### Task Description:

Where code requirements constrain the building design, it may be useful to record the code constraint for future use by other applications. The value of storing code constraint information in the building model (as opposed to simply reporting a compliance result) is that it can provide persistent guidance to the user and enable user notification when design modifications are made that will affect compliance. Prescriptive code constraints can be represented as discrete limiting values, which can be associated with a building object and stored in the building model for other applications to utilize and to document the basis for design decisions.

In order for this constraint object to be fully useful, it needs to carry the following information:

- The object to which the constraint is connected
- The numeric and logical content of the constraint
- Identification of the code to which the constraint belongs
- Identification of the application that established the constraint
- A description of the constraint
- Text to be used in notifying the user about the constraint
- Other objects and attributes on which the value or application of the constraint depends.

Unlike with prescriptive requirements, a performance-based requirement cannot be expressed as a discrete constraint on an individual object. Rather, the constraint is typically imposed on a system consisting of multiple objects that interact within the code-constrained system. To accommodate performance-based code constraints, it is necessary to attach the constraints to aggregate objects. In addition, many, though not all, performance codes employ requirements that are not fixed values but rather are themselves the results of calculations. These requirements tend to have a larger number of dependencies on other objects in the model, and hence are more likely to be affected by other design changes.


##### Example Usage Scenario:

Figure 3 shows a window assembly consisting of a window and a window frame. The U-factor of the window assembly--not the glass or the frame but the combined assembly--is constrained by a code requirement. For purposes of this example, the code constraint (from ASHRAE/IES Standard 90.1-1989) is that the U-factor of the window assembly may not exceed  $0.72 \text{ Btu}/(\text{h}\cdot\text{ft}^2\cdot^\circ\text{F})$ . Listed below is the information that would be recorded with the code constraint and that would be available to other applications.



Code constraint attached to aggregate object *Window Assembly*.

- Numeric and Logical Content: Window assembly U-factor must be less than or equal to  $0.72 \text{ Btu}/(\text{h}\cdot\text{ft}^2\cdot^\circ\text{F})$ .
- Identification of Code and Section Number: ASHRAE/IES Standard 90.1-1989, Section 8.6.10.2(b).
- Constraint Established By: COMcheck-EZ, Version 2.0.
- Description of Constraint: The code requires that locations with greater than 3,000 heating degree days base  $65^\circ\text{F}$  have an overall U-factor (i.e., including both glass and frame) that does not exceed  $0.72 \text{ Btu}/(\text{h}\cdot\text{ft}^2\cdot^\circ\text{F})$ .
- Text for User Notification: "The overall U-factor (i.e., including both glass and frame) exceeds  $0.72 \text{ Btu}/(\text{h}\cdot\text{ft}^2\cdot^\circ\text{F})$  and therefore violates ASHRAE/IES Standard 90.1-1989, Section 8.6.10.2(b)."



**Figure 3 - Window and Frame**

This Constraint Depends On: 1) site heating degree days base  $65^\circ\text{F}$ , 2) space conditioning of parent space, 3) glass U-factor, 4) glass area, 5) frame U-factor, and 6) frame

#### **4.6.1.3.4. Task C - Check for Compliance with Prescriptive Requirements**

##### **Task Description:**

This second step for compliance checking with prescriptive code requirements involves a logical comparison of the applicable prescriptive requirements in the code with the corresponding objects and attributes in the building model. This checking process yields both a status result and a code constraint on each of the corresponding building attributes. Commercial energy codes usually contain requirements that pertain to the architectural envelope, lighting systems, and HVAC and service water heating systems. Residential energy codes usually address only building envelope, HVAC, and water heating.

##### **Example Usage Scenario:**

Figure 1 shows the perimeter of a concrete slab on grade that has been insulated using vertically placed insulation that extends downward 24" from the top of the slab. In Minneapolis, this insulation must have an R-value of 8 or greater. The compliance checking process for prescriptive requirements simply involves executing logical comparisons between the applicable code requirements and the corresponding attribute(s) of code-constrained objects.

#### **4.6.1.3.5. Task D - Define Budget Model**

##### **Task Description:**

Compliance checking with performance-based requirements frequently requires that three steps be taken that are not required with prescriptive requirements: defining a budget building model, defining a proposed building model, and analyzing the performance of each. Defining the budget model (i.e., the model or building configuration that defines code-minimum performance) is typically performed by implementing prescriptive code requirements into a copy of the description of the proposed design. For example, the code checking procedure may substitute the prescriptive wall and roof insulation requirements for those used in the proposed design. Other assumptions may be imposed to ensure a fair basis for comparison with the performance results from the proposed model; for example, by specifying consistent operating assumptions and energy prices. In addition to implementing these modifications, this step involves translating the representation in the building model to the appropriate representation and format required by the simulation model used to analyze performance.

However, as indicated in the process diagram, a common variation for performance code requirements is to have the budget value be a static metric of performance. In this case, the process simplifies to a logical comparison of performance values similar to the prescriptive compliance check.

### Example Usage Scenario:

Figure 4 shows a building floor plan with three different space usage (or task area) designations. The lighting sections of commercial building energy codes set lighting power budgets for various types of spaces based on their usage. The lighting power budget is generated by multiplying the area of each space type by its permitted lighting power density. This approach is performance-based because the resulting budget is applied at the whole-building level, and users are free to use any combination of lighting fixture types and quantities provided the aggregate input wattage does not exceed the budget.




Figure 4 - Floor Plan

The actual values that make up the lighting budget model are shown in Table 1.

Table 1 - Example Budget Model for Performance-Based Lighting Compliance

Space Type Designation	Floor Area (ft <sup>2</sup> )	Lighting Power Density (W/ft <sup>2</sup> )	Lighting Power Budget (W)
Cafeteria	4,400	2.5	11,000
Restrooms	300	0.8	240
Vestibule	800	1.0	800
Corridor/Stairs	1,000	0.8	800
Total	6,500	---	12,840


#### 4.6.1.3.6. Task E - Define Proposed Model

##### Task Description:

A similar process is used to define the proposed model as was used to define the budget model. Most objects in this model are defined directly from the building model entered by the user, however some assumptions may be imposed to ensure a fair comparisons between budget and proposed models. A similar translation is made to the required format for the simulation model.

##### Example Usage Scenario:

Figure 5 shows the reflected ceiling plan for the same areas shown in Figure 4. For lighting compliance, the fixture descriptions, quantities, and input wattages that are specified for the building are used to define the proposed model. Table 2 lists the parameter values for the system shown on the reflected ceiling plan (Figure 5).



**Figure 5** - Reflected Ceiling Plan

Table 2 - Proposed Design Model for Performance-Based Lighting Compliance

Fixture Description	Quantity	Input Wattage (W)	Design Lighting Power
Total			

#### 4.6.1.3.7. Task F - Analyze Performance

##### Task Description:

The third step with performance code requirements is to calculate the performance of the two models, one representing the design proposed by the user and the other establishing code-minimum performance. While this process description implies that a the analysis involves a complex process, the basic sequence is applicable to a wide range of analysis procedures. The required calculation may be as simple as a parallel path calculation that combines the rated thermal conductances of two components to determine an overall assembly conductance (as in Figure 3 for the window assembly), or it may be as complex as an annual computer simulation of building energy use for a multi-zone building.

##### Example Usage Scenario:

Table 1 and Table 2 show the calculation of lighting power budget and the connected load for the proposed design. In this lighting compliance example, the performance analysis involves multiplying values in each of the rows and summing the products in the right-most columns.

#### 4.6.1.3.8. Task G - Compliance Determination and Reporting

##### Task Description:

Depending on the compliance outcome from the code checking sequence, the user is either notified of the code violation or notified that the design complies and given the opportunity to generate a compliance report for submission as part of the building permit application. When a prescriptive code requirement is violated, the specific features that violate the requirement are listed for the user along with the corresponding code constraints. Such notification normally prompts the user to modify the design and rerun the compliance check to document compliance. The user may also leave the design unchanged and demonstrate compliance using an alternative, performance-based compliance method.

Unlike with prescriptive requirements, a failure to comply with a performance-based requirement cannot be attributed to the violation of a specific requirement but may depend on a large number of building objects. Results from a performance code evaluation are reported in the form of performance relative to a performance budget. This fact often leads the user to an iterative process to resolve the code violation. The user evaluates various ways of achieving compliance, and often a variety of design and cost issues are considered before a design change is accepted.

##### Example Usage Scenario:

Figure 6 shows a portion of a compliance report from an energy code application that has both prescriptive and performance-based requirements. Note that at the bottom of the page, the report indicates that the building complies by a certain percentage with the performance requirements of the code but that it also notes the violation of a specific prescriptive requirement. In this case, the example building will not comply until the violation of the prescriptive requirement is corrected.

ENVELOPE COMPLIANCE CERTIFICATE COMcheck-EZ Software Version 2.0		Permit # _____			
Section 1: PROJECT INFORMATION		Chkd by/Date _____			
Project Information: ABC Stores Inc. 1234 5th Ave. George, Washington 98765					
Designer/Contractor Information: ENR Design and Construction Inc. 567 George Washington Way Martha, Washington 98766					
CLIMATE-SPECIFIC REQUIREMENTS					
Component Name/Description	Area	Cavity R-Value	Cont. R-Value	Assembly U-Factor	Budget U-Factor
ROOF: Nonwood Joist/Truss	4500	0.0	16.0	0.060	0.057
WALL: Metal Frame, 16" o.c.	600	13.0	0.0	0.132	0.086
WALL: CMU >8"/Int. Ins/Mtl	1200	13.0	0.0	0.112	0.086
WALL: CMU >8"/Int. Ins	680	--	0.0	0.273	0.086
WIN: Low-E/Clr/Tbrk/SHGC=0.71/PF	500	--	--	0.570	--
<b>WARNING: The following window violates a mandatory U-factor requirement</b>					
WIN: Single/Clr/Mtl/SHGC=0.87/PF	100	--	--	1.170	--
DOOR: Opaque	35	--	0.700	--	--
DOOR: Glass	40	--	0.920	--	--
SLAB: Unheated w/36" Vertical	280	--	6.0	--	--
Envelope PASSES Performance Requirements: Design 2% better than code.					

Figure 6 - Example Energy Code Compliance Report

## 4.7. [CS-2] Code Checking Extensions

### Processes Defined in this project:

1. Code Compliance Checking for Disable Access and Escape Route of Commercial, Residential and Institutional Buildings

### 4.7.1. Commercial, Residential and Institutional Code Compliance Checking for Disable Access and Escape Route

#### 4.7.1.1. Introduction

##### Overview:

This process will support applications that determine whether building design compile with building codes related to disable access and escape route. CS-2 project will based on codes used in Singapore. The project will address requirements related to usage, dimension, material and relationship of building spaces.

Disable access code compliance process check whether the access provisions and facilities of a building complies with one or more codes or standards that serve the needs of the wheelchair user enforced by various codes and standards promulgation entities. The provisions also apply to ambulant disabled.

Escape route code compliance process check whether the exit provisions and facilities of a building complies with one or more codes or standards that provide safe means of escape for occupants enforced by various codes and standards promulgation entities.

##### Process Scope:

- Check code compliance for commercial buildings of public resort and concourse (e.g. banks, concert halls, cinemas, hotels, religious buildings, theatres and stadiums).
- Check only the interior of building.
- Check prescriptive based code requirements.
- Check disabled access
  - Check clearance (*width, area for wheelchair movement*) of space and access
  - Check surface requirement (*materials*) of space and access
  - Check floor level changes (*gradient*) of space and access
  - Check obstacles on space and access
  - Check access aids provision (*symbol, handrails*)
- Check escape route
  - Check occupancy capacity requirements
  - Check exit requirements (*number, location, capacity and minimum width of exits*)
  - Check approach to exit (*smoke free, fire resistance, sprinkler protected*)
  - Check area of refuge (*smoke free, fire resistance, sprinkler protected*)
  - Check means of escape (*staircase and passageway*)
  - Check escape aids provision (*symbol*)

Note: The above checks are based on the usage and floor area of a space, story, zone or building

##### Out-of-Scope:

- Check performance based code requirements
- Exterior space
- Check disabled access
  - Check sanitary provisions (*washroom, water closet, basin, urinals, bath*)
  - Check circulation provisions (*lift, conveyance*)
  - Check transport provisions (*car park*)
- Check escape route
  - Check travel distance
  - Check escape requirements for specific type of building (*e.g. hotels, hospitals*)

##### Definitions:

For disabled access:

- Accessible Route: a continuous unobstructed path connecting all accessible elements and spaces in a building that can be maneuvered by people with physical disabilities.
- Disable Person: A person who is wheelchair bound which affects his mobility (only in CS-2 context).

**References:**


- Code of Practice on Barrier-free Accessibility in Building 1995, Building Control Division, Public Work Department, Ministry of national Development, Singapore.
- Code of Practice for Fire Precaution in Building 1991, Fire Safety Bureau, Singapore Civil Defence Force.

**Contributors:**

- Wong Wai Ching (S)
- Zhong Qi (S)
- Tan Kee Wee (S)

### 4.7.1.2. Process Diagram

Note: The process diagram found below is adopted from that of CS-1. This is to ensure consistency between CS-1 and CS-2. As the scope of this project only cover the prescriptive approach to building codes compliance hence only the process for prescriptive code requirements is given below.



### 4.7.1.3. Process Definition

#### 4.7.1.3.1. Overview

The process is used by building designers and code enforcement officers to ensure code compliance during design and submission stage, respectively. With the process, designers can detect code violations in their design as early as possible while design changes are still relatively cheap to make. Similarly, code enforcement officers can verify the plans submitted by the designers for building approvals faster and more objectively. As both the professionals are using the same checking system, consistency in code interpretation is automatically ensured.

A plan checking system must be able to retrieve information from the design and to be checked against the building code. It may perform more computations to derive additional information from the retrieved before checking is possible. This is because the derivable information is not usually found in the building model in order to keep the size of the exchange model small.

#### 4.7.1.3.2. Task A - Identify Applicable Code Requirements

**Task Description:**

This process involves identifying code requirements to be checked from a code requirement knowledge base. It should allow user to invoke either all or certain part of the requirements captured in the knowledge base.

Specific code requirements to be complied with will be generated from this task which in turn loads the import routines to retrieve specific building information from the building model to be checked.

#### **Example Usage Scenario:**

From an end-user perspective, the task involves mainly deciding which code requirements to be complied with based on the type, usage and occupancy of the building or specific part of the building (either in terms of zone, storey or space). The code requirements can be grouped into the following topics:

- Space clearance and allowance (width, area for wheelchair movement) of space and access
- Floor surface requirement (materials) of space and access
- Floor level changes (gradient) of space and access
- Obstacles on space and access
- Access aids provision (symbol, handrails)
- Occupancy capacity requirements
- Exit requirements (number, location, capacity and minimum width of exits)
- Approach to exit (smoke free, fire resistance, sprinkler protected)
- Area of refuge (smoke free, fire resistance, sprinkler protected)
- Means of escape (staircase and passageway)
- Escape aids provision (symbol)

From a system point of view, a user interface (e.g. in a form of check boxes) should be provided to facilitate the selection of the above requirements. Once the selection is completed, the specific modules of checking routines are then loaded. Next, the user will then be prompted to provide the source of building model. The system can provide an interactive means, e.g. a “rubber bend” polygon, for user to define the extent of the floor plan to be checked or an import facility to read the predefined building model from a physical file or a server. Once the building model is read into the system, instances of building object will be instantiated. From the building objects’ interface, specific attributes of the object can then be retrieved by the system to checking purpose.

#### **4.7.1.3.3. Task B - Check for Compliance**

##### **Task Description:**

In CS-2, only prescriptive checking is covered. It involves a logical comparison of the applicable prescriptive requirements in the code with the corresponding objects and attributes in the building model. The result of this step is a set of design violations. A series of computation, derivation and code cross-referencing are expected before the comparison can be carried out.

##### **Example Usage Scenario:**

From end user perspective, the building will be processed portion by portion until all the requirements are met. A few examples are given below:

- Space clearance and allowance requirements
  - *The minimum clear floor space required to accommodate a single, stationary wheelchair shall be 900 by 1200mm as illustrated in figure 1.*





Figure 1 Minimum Clear Floor Space


- The minimum clear floor space for wheelchair to turn shall be 1800 by 1800mm as illustrated in figure 2.

Figure 2 Minimum Clear Turning Space



- The minimum clear width of an accessible route shall be 1200mm to allow both wheelchair and a walking person to pass as illustrated in figure 3.





Width of Accessible Routes

Figure 3 Width of Accessible Routes

- Floor surface (slip resistance) requirements
  - *The slip resistance of a few typical flooring surface*

Material	Slip resistance		Remarks
	Dry & Unpolished	Wet	
Clay Tiles	Very good	Very good	Carborundum finish
Carpet	Very good	good	Must be securely fixed
Rubber (sheet/tiles)	Very good	Very poor	Not suitable for toilet
...	...	...	...

- Floor level changes requirements
  - *Any changes in level, except for lifts, shall conform to the following table*

Changes in vertical rise (mm)	Gradient not steeper than
0 to 15	1:2
15.1 to 50	1:5
50.1 to 200	1:10
Exceeding 200	1:12

- Obstacles on space and access
  - *Any building element (e.g. column or cabinet) that post as obstacle (leaving insufficient clear width or turning space for the wheelchair) on a disabled accessible route or space shall be avoided.*
  - *Wheelchair manoeuvring at the doorway shall be free of obstruction and be provided with clear space (as illustrated in figure 4) on either side of the door in the following manner:*
    - *For one-way swing door, minimum space of 300mm and 600mm, on the push and pull sides of the door, respectively.*
    - *For two-way swing door, a minimum space of 300 mm.*




Figure 4 Minimum Doorway manoeuvring Space

- Access aids provision (handrail, ramp, symbol)
  - Handrail shall be slip resistant, have circular section of 30-45 mm in diameter, continuous gripping surface, without interruptions that can break hand hold and have a clear space of not less than 40 between the handrail and the wall as illustrated in figure 5.




Figure 5 Handrail

- Ramp (an inclined way connecting one level to another) shall have a level landing at the top and bottom of each run and also where the run changes in direction as illustrated in figure 6. (The minimum space for landing found in between runs shall be at least 1500x1500mm and that found at the top and bottom run shall be at least 1200x1500mm)




Figure 6 Level Landing

- Ramp with horizontal run exceeds 9000mm shall have a level landing as illustrated in figure 7.




Figure 7 Ramps and Landing

- Occupancy capacity requirements

Type of Occupancy	Capacity (number of persons per unit width of exit)			
	Exit to external space	Exit to Internal space	Staircase	Corridors, Exit passageway
Commercial (shop, office)	100	80	60	100
Hotel	50	40	30	50
...	...	...	...	...

- Exit requirements (number, location, capacity and minimum width of exits)

- Number of exit

Type of Occupancy	Maximum Occupant with one Exit
Commercial (shop, office)	50
Hospital Ward	15
...	...

- Number of exit staircase: at least two independent exit staircases per storey.
- Minimum width

Type of Occupancy	Minimum Width (m)	
	Door	Stairs
Commercial (shop, office)	1	1
Hotel	1	1
...	...	...

- When more than one exit is required from any space, the exits shall be placed as remote as possible from the others.

- Approach to exit (smoke free, fire resistance, sprinkler protected, ventilated and pressurized)
  - All internal exit passageway shall be naturally ventilated by fixed ventilation openings in external wall, such ventilation openings shall not be less than 15 percent of the floor area of the passageway.
  - In any building of which the habitable height exceeds 24 m, any internal staircases without provision of natural ventilation shall be pressurized to comply with the pressurization regulations.
  - The floor area of a smoke-stop lobby shall be not less than 3m<sup>2</sup> ...
  - Walls shall have a fire resistance of at least 1 hr.
- Area of refuge (smoke free, fire resistance, sprinkler protected, ventilated and pressurized)
  - Exit doors between Area of refuge and external space shall have fire resistance of at least half an hour and fitted with automatic self-closing device to comply with requirement found in....

- Means of escape (staircase and passageway)
- Escape aids provision (symbol)

#### **4.7.1.3.4. Task C - Report Code Violations**

##### **Task Description:**

After the compliance checking, the violations will be recorded in the building model for user to take necessary action to correct the design. This information can be presented graphically or in textual report.

##### **Example Usage Scenario:**

After the compliance checking, the violations will be recorded in the building model. The information can then be used subsequently by users to do the necessary corrections. Specific violation can be presented on screen as highlighted bounding box of the non-compliant building element with attached electronic "post-it-notes" to give detailed violation description. A summary report can also be generated in a written format to report all the violations found. The violation description will spell out the requirement to be met and what was actually found in the building model to the user. Prompt will also be given to the user to modify the design and rerun the compliance check.

## **4.8. ES-1 Cost Estimating**

### **Processes Defined in this project:**

1. Cost Estimating

### **Sub-Processes Defined in this project:**

2. Scope Analysis
3. Identify Objects
4. Identify Tasks Needed to Install Objects
5. Identify Resources Needed to Perform Tasks
6. Quantify
7. Costing and Cost Summarization

## **4.8.1. Cost Estimating**

### **4.8.1.1. Introduction**

#### **Overview:**

These cost estimating usage scenarios describe the processes involved in determining costs based on information provided by objects in the Integrated Model. It includes:

- analysis of information in the model,
- adding information to help classify objects,
- adding objects to model tasks and resource usage,
- determining quantities,
- determining costs,
- and propagating costs and cost summaries back into the model.

#### **Process Scope:**

- The Cost Estimating section describes the major processes involved in producing an estimate. These include, Scope Analysis, Object Identification, Identification of needed Tasks and Resources, Quantification, Costing, and Summarizing Costs.

#### **Out-of-Scope:**

- The processes described here do not include cost attribute maintenance for actual costs incurred to a project.


**Definitions:**

- None provided

**Contributors:**

- Mike Cole - NA
- Ray Brungard - NA
- Jeffrey Wix - UK
- Peggy Woodall - NA
- Annette Stumph - NA
- Roger Grant - NA

**4.8.1.2. Process Diagram – Cost Estimating**



### **4.8.1.3. Process Definition – Cost Estimating**

#### **4.8.1.3.1. Overview**

##### **Scope Analysis**

This process looks at the level of detail that will be used in determining the objects that will be used in making the estimate. It provides information pertaining to the overall job, what state the design is in, and possibly for what the estimate is to be used for. This would indicate, for example, whether the estimate was to be detailed or conceptual.

Furthermore, it would indicate whether the entire project is being estimated, or just a portion of the project. It may be to estimate the cost impact of alternate designs, or a required change to the design.

##### **Identify Objects**

This process identifies the project objects to be costed. Such project objects may be an entire building, a section of a building, a space, individual elements (such as door), repeating types of elements (type of door), a process, or a resource.

Once the objects to be costed are selected, they must then be mapped to objects in the costing database. The mapping process may involve grouping model objects together (such as collecting connected wall segments to be estimated as a group). For construction planning purposes, construction zones are needed to define areas where similar objects need to be grouped for scheduling purposes. At this point you may need to replace a single object with an aggregation of its sub-elements (such as defining the separate concrete pours, and expansion joints of a foundation slab).

##### **Identify Tasks Needed to Install Object**

This process examines how the object (which was selected and identified in the previous step) is to be built in the field and comes up with a set of tasks that are needed to install the object. For instance, a wall may require 'framing', 'sheetrocking', and 'finishing'. These tasks can be modeled to come up with more accurate cost estimates. Information about the tasks may be used later in project scheduling.

##### **Identify Resources Needed to Perform Task**

Each task will require one or more resources. Resources may include labor (carpenters, electricians, ...), equipment (crane, scaffolding, ...), and materials (lumber, carpeting, ...). Resource objects can be used along with task objects to model the costs of installing an object. Information about the resources may be used later in project scheduling.

##### **Quantify**

First, identify the way in which an object is to be 'counted', such as by piece, linear foot, etc. Next establish the amount of item to be measured. This includes the counting of discrete objects as well as calculation of quantities from the object's dimensional information.

As with the object, its required resources also need to be quantified. Again one must establish the unit of measure for resources needed to install the and then establish the amounts of each resource that will be needed to install the object. This will be calculated using the object's dimensions and estimated resource usage based on those dimensions. Labor and material production rates will be used to establish the usage quantities.

##### **Cost**

This process evaluates the price impact of the objects. Using the quantities developed in the previous process, and applying unit costs for the overall object and/or its required resources, the cost impact of the object is calculated.

An object may have costs in addition to its cost per unit that has been calculated, such as tax, bond, insurance, and fees. Where appropriate, these costs should be added onto the cost of an object.

## Summarize Costs

Report the estimated costs in a way that is easy for the intended customer to understand. This may include a schedule or report that organizes and summarize all of the cost information in the model, or possibly a browser that would allow a user to look at the cost information for any object in the model.

### 4.8.1.3.2. Task A - Scope Analysis

#### Task Description:

This process looks at the level of detail that will be used in determining the objects that will be used in making the estimate. It provides information pertaining to the overall job, what state the design is in, and possibly for what the estimate is to be used for. This would indicate, for example, whether the estimate was to be detailed or conceptual.

Once 'detail available' and 'estimate use' is analyzed, the types of objects to be estimated will be determined. For example, a 'conceptual estimate' may only look at project spaces and zones to come up with a rough initial estimate based on average cost per square meter. At a later stage of the design, more detailed estimating will be possible. The costs of individual walls, doors, windows, etc. can be modeled.

Some estimates are designed to determine the overall cost of a project. Others are used to do a value analysis among alternate designs or building methods. Late in the design process (and into the building process), estimates are needed to determine the cost impact of required design changes (change orders).

The classifications, attributes, dimensions, and context of model objects may be used to identify them and in turn map them to 'cost objects' in an estimating system. If the identification and classification system is to be highly automated, it should be configured at this point to define how information about the objects will be used to map them to 'cost objects'.


#### Example Usage Scenario:

##### Conceptual Estimate - Scope Analysis

At the beginning of the design process, an architect may only know the space and usage requirements of a building. In that case, a *conceptual estimate* would be done based on only this information.

If the model contains only space program information, it is determined that only the IfcSpaceProgramme objects will be used in this estimate.

In the diagram at the right you see some the objects that have been created to do a space planning analysis for the building.




#### Example Usage Scenario:

##### Detail Estimate - Scope Analysis

As the design process progresses, actual construction objects (e.g. walls, doors, windows,...) are added to the model. We can use these objects to more accurately estimate the cost of constructing the spaces.

In the diagram at the right you see some the walls and doors that are now available for estimating. In a detail estimate these objects are targeted to be within the scope of the estimate.

At this time we determine whether the targeted



objects will be estimated on a per unit basis, or if the tasks and resources to install an object will be modeled.

#### Example Usage Scenario:

##### Value Analysis - Scope Analysis

During the design process, the cost of alternate building designs must be evaluated. In this case, the objects that are removed, changed, or added, from one design to another must be targeted. If these objects are part of a grouping of construction objects that are installed as a unit, the entire grouping may be targeted.

This frame will show a layout similar to the one use above, but with significant design changes to some part of it.

#### 4.8.1.3.3. Task B - Identify Object

##### Task Description:

This process identifies the project objects to be. Such project objects may be an entire building, a section of a building, a space, individual elements (such as door), repeating types of elements (type of door), a process, or a resource. The types of objects to be identified were determined in the 'Scope Analysis'.

Once the objects to be costed are selected, they must then be mapped to objects in the costing database. The mapping process may involve grouping model objects together (such as collecting connected wall segments to be estimated as a group). Conversely, it may involve delineating separate construction zones of a single object (such as defining the separate concrete pours of a foundation slab).

Using the object's type, attributes, dimensions, etc., determine what 'cost object' best models the costing of that object. The most flexible way to perform this task is to use an object browser and classify the objects manually. The quickest way is to define classification rules to automatically classify the objects. Each has advantages and disadvantages. The 'best' way may be some combination of these two.

Once the model object has been mapped to a 'cost object' classification, the classification should be recorded in the model object. This allows the identification process to be separated from the quantification and costing processes.

#### Example Usage Scenario:

##### Conceptual Estimate - Identify Objects

Continuing from the previous example, the object identification process would examine the information in the `IfcSpaceProgramme` objects. Based on that information, it would select an estimating system object that would best model the cost of the space. The process stores the type of the estimating system object in the `IfcSpaceProgramme` object. Thus, later process do not need classify the object, they need only look up the estimating system classification stored on the `IfcSpaceProgramme` object.

Model Object	Estimating Object ID
Equipment Yard	SP_EnclosedYard
Truck Dock	SP_Dock
Switch Gear	SP_Equip Room
Receiving	SP_Utility

#### Example Usage Scenario:

##### Detail Estimate - Identify Objects

This step is the same for detail estimates. The model objects that have been targeted for estimating should be mapped to estimating system objects that are designed to represent them.

Model Object	Estimating ID
Double Exterior Doors	DR_Ext
Double Interior Doors	DR_Int
Exterior Wall	WL_Ext
Interior Wall	WL_Int
Yard Wall	WL_Block

#### 4.8.1.3.4. Task C - Identify Tasks Needed to Install the Object

##### Task Description:

Tasks are activities or operations required to place or install any object (permanent or temporary) in the project. To identify the tasks needed, the estimator selects a construction method for the object. The



construction method will require one or more tasks to be performed. Task objects will be created and will be referenced the object to be constructed.

#### **Example Usage Scenario:**

##### Conceptual Estimate - Identify Tasks

This is beyond the scope of Conceptual Estimating, which generally relies on a cost per unit to estimate costs.

#### **Example Usage Scenario:**

##### Detail Estimate - Identify Tasks

Detail Estimates often model the tasks needed to install an object in order to estimate the cost of the object. If we are processing a wall object, several tasks may be identified and added to the model. These tasks may be; framing the wall, putting up sheetrock, finishing the sheetrock, and painting the wall. By modeling each of these tasks, we can later determine the cost of the wall. Modeling the tasks may be done outside the model, but by adding it to the model, we may be able to share this information with the scheduling process, which also models tasks.

Object	Required Tasks
Interior Wall	Framing
	Apply sheetrock
	Finishing
	Painting

#### **4.8.1.3.5. Task D - Identify Resources Needed to Perform a Task**

##### **Task Description:**

Each task will require one or more resources to be completed. Some resource types include Labor, Material, Subcontractors/Vendors, Equipment, etc. The quantity of the resource that is required and the unit cost of the resource, will contribute to the cost of the task.

The application will either create a resource objects, and/or select ones that already exist in the model. These resources will be referenced by the task to be performed. There may be multiple uses of a resource within the same task.

#### **Example Usage Scenario:**

##### Detail Estimate - Identify Resources

Continuing with the previous example, we now want to determine the resources required to complete each of the tasks. In the case of "framing the wall", we may need various types of lumber, nails, and carpenters.

Task	Resources
Framing	Lumber
	Nails
	Carpenter

#### **4.8.1.3.6. Task E - Quantify**

##### **Task Description:**

The input to this process is the object that is to be quantified. Depending on the type of object, various dimension attributes will be used to calculate the overall quantity of the object and the quantities of resources required.

The 'overall' quantity of an object is measured in the dimension in which an estimator thinks of it in a 'unit cost' sense. For instance, the overall quantity of a wall might be in linear feet. The overall quantity of a concrete slab might be square feet or cubic yards, depending on how it is being estimated. The overall quantity should be calculated directly from the object's dimension attributes.

The resource quantities are the amounts of the various resources needed to install the object. These quantities are based on the dimension and specification attributes of the object. For instance, a wall's stud count will be based on the length of the wall and the stud spacing and possibly a waste factor stored in the estimating system. The duration quantities for the labor resources will be based on the object's dimension

Model Object	Area
Equipment Yard	50 M2
Receiving	12 M2

Model Object	Length
Interior Wall	100 M
Yard Wall	30 M

Model Object	Resource	Quantity
Interior Wall	Framing Lumber	700 M
	Nails	1.5 Kilos
	Carpenter	20 Hours

When all of a task's resources are costed, the resource use costs should be accumulated and the task's overall cost should be updated.

The last cost to be calculated is the primary object's total cost. If no tasks or resources have been attached to the object to model its installation cost, and the object does not have 'parts' which have been costed, the object's cost will be based on its 'overall' dimension, various specifications, and a unit cost originating in the estimating system. The object's 'ProductCost' attribute should be updated with the calculated cost.

If the primary object's cost has been modeled using tasks, resources, or component 'parts' which contain costs, the object's 'ProductCost' should be updated to reflect these factors.

#### **Example Usage Scenario:**

##### Conceptual Estimate - Cost

In a conceptual estimate, you may compute cost directly from the quantity of an object. For example, if equipment yard space has a historical cost of \$40 per M<sup>2</sup>, you could estimate the cost based on the area, and that cost factor.

Model Object	Cost
Equipment Yard	\$2,000
Receiving	\$2,400

### Example Usage Scenario:

#### Detail Estimate - Cost

If you are doing a more detailed estimate, in which you have done task and resource modeling, you would use the quantities of the various materials and resources and their unit costs to determine their costs. You would then total the costs of the materials and resources to determine the cost of the object.

Model Object	Resource	Cost
Interior Wall	Framing Lumber	
	Nails	
	Carpenter	

### 4.8.1.3.8. Task G - Cost Summarization

#### Task Description:

When the process of determining costs is complete, we need to place the costs back into the model in a way that is understandable to people who need to review cost information. One place to put the cost is on the object whose cost was estimated. But this does not show the purpose or scope of the estimate, which is needed to understand the “meaning” of the cost. Placing estimated costs together in a “cost schedule” helps to give context and meaning to costs.

Once the costs are gathered together in a cost schedule, there should be a convenient way to reference the cost schedule elements from the object whose cost is being represented. Conversely, you should also be able to reference the object from the cost schedule element.

### Example Usage Scenario:

#### Conceptual Estimate - Cost Summarization

In this example, the quantities and costs of the spaces programs that were targeted in the conceptual estimate are grouped and reported in a cost schedule. In this simple schedule, the cost of the spaces are listed at the detail level, and added together to show the cost of their grouping (Equipment/Receiving Area).

The model user should be able easily determine what objects the schedule refers to, for instance, an application may provide a utility to “jump to” a graphic representation of an object, from a display of the cost schedule. Conversely, from the graphic representation of an object, the user may wish to see a list of all cost schedules that contain information about the object’s cost.

Estimate from Initial Space Plan			
Area	Model Object	Object Quantity	Cost
Equipment/Receiving Area			\$10,900
	Equipment Yard	50 M2	\$2,000
	Truck Dock	12 M2	\$2,000
	Switch Gear	25 M2	\$4,500
	Receiving	14 M2	\$2,400

### Example Usage Scenario:

#### Detail Estimate - Cost Summarization

In this example, the costs of the building elements that make up the spaces are targeted and reported together. The costs individual objects, of groupings (Equipment/Receiving Area) and sub-groupings (Walls and Doors) can all be reported in a single cost schedule.

The example shows one way that costs may be grouped but is in not intended as a suggestion for a specific hierarchy.

Again, it is important that a user be able to “flip” between a model object and the places where its cost is reported.

#### Estimate from Wall Layout Design

Area	Type	Model Object	Object Quantity	Cost
Equipment/Receiving Area				
	Walls			
		Yard Wall		
		Exterior Walls		
		Interior Walls		
	Doors			
		Exterior Double Doors		
		Exterior Single Doors		
		Loading Bay Overhead Doors		
		Interior Single Doors		
		Interior Double Doors		
...	...	...		

## 4.9. [FM-3] Property Management (Building Owner's viewpoint)

### Processes Defined in this project:


1. Enabling the use of IFC objects in property management
2. Grouping IFC objects
3. Linking the maintenance objects to the IFC objects

### 4.9.1. Property Management

#### 4.9.1.1. Introduction

##### Overview:

Property management is a process starting from requirement programming and continuing through the building's life cycle. The tools should facilitate the evaluation and comparison of properties and all costs during the construction and the life cycle. For these purposes the design and product data should be in such a format that it could be combined to the owner's and other external data bases for evaluation and management purposes.



**Process Scope:**

In this phase the FM-3 project covers just a subset of this process focusing on grouping of spaces and other possible objects for different purposes, like maintenance, administration, public registers, mapping etc. This process is based on objects provided by the design and construction process and uses mainly the attributes in the current model. The main user is the building owner and the benefits is more efficient use of the building data and through this cost savings in the administrative work. This process starts after the building is completed and is carried out through the whole life cycle of the building.

- Grouping IFC objects
- Linking the maintenance objects to the IFC objects

**Out-of-Scope:**

- Instructions for the maintenance
- Evaluation methods

**Definitions:**

- Group: a set of selected objects and / or groups
- Maintenance object: an object containing description, classification and maintenance history of linked IFC building elements

**References:**


- Version 1.0 IFC Model
- CB-1 Client Briefing
- ES-1 Cost Estimating
- (FM-1 and FM-2 Maintenance, in version 3.0)
- FM-4 Occupancy Planning

**Contributors:**


- Poul Sorgenfri Ottosen (AAU, Danish Department of Education) (Nordic)
- Jan Karlshøj (Carl Bro A/S) (Nordic)
- Arto Kiviniemi (VTT Building Technology) (Nordic)

### 4.9.1.2. Process Diagram – Property Management

#### Object grouping



#### Maintenance linking



### 4.9.1.3. Process Definition – Property Management

#### 4.9.1.3.1. Overview

The need for grouping can be caused by any management purpose, like a new department, workgroup, cleaning area, renovation, fire zone etc. In this process the property manager can create new groups from selected objects. These groups can be used for any administrative or management purposes. All material or quantitative information is calculated from the IFC model. The model information can be used together with the owner's own or other external database information to evaluate operational costs or other needed values.

#### 4.9.1.3.2. Grouping IFC objects

##### Task Description:

The first task is to define the grouping purpose, which defines the classification of this group. Then the objects for new groups can be selected through various methods:

- *any objects selected by the user*
- *filtered objects (type, properties or other selection key) selected by the user*
- *filtered objects in the whole model*

After the selection is completed the user can give a description to the group.

If the selected objects already belong to some group with the same classification, the application should warn the user about it and ask for instructions for further operations.

When the groups are formed the user can use those as the selection criteria for different operations and reports. All IFC object data should be available through these selections.

*If the Grouping is added in IFC Release 1.5 this part may not be needed..*

### Example Usage Scenario:

The grouping mechanism enables many different functions in FM and also in other activities. With this mechanism the building owner can form for example rental, cleaning and other area combinations from spaces: The cleaning areas in the building needs to be defined. Different materials need different operations. The materials on surfaces can be recognized from the IFC model and picked automatically. After this the selected objects can be divided to proper sizes for operations and grouped to one unit. The classification and description of the unit enables easy administration, visualization and reporting of these units.


The building administrator is continually facing the problems of matching room size and facilities with user requirements. While the building will contain several types of rooms, each sized and equipped for a specific usage, each user will have individual requirements regarding for floorage and facilities.

The layout and facilities of a building are basically static. The building is the result of user or owner requirements at the time of erection. User requirements were analyzed and the building program, the design and construction of the building were based on the results. User requirements, however, do not remain static. They develop continuously according to the development of the individual user's business, which is independent of the physical setting provided by the building. The user can consequently be expected currently to increase or reduce his floorage requirements and/or require other facilities

Ideally, the building administrator should have a tool that can provide precise information about room types, users and historical development, including a facility for grouping together rooms used by the same institution or department. This information can be utilized by the building administrator for current inquiries and in creating a strategy for the further development of the building.

### Floorage control tool - examples of usage

The administrator will continually evaluate the degree to which the building is utilized, for example by dividing the rooms into categories, which would enable him to calculate the net/gross area ratio. This can be used both in the operation of the existing building, as a guide for refurbishment and as an element of the planning of new buildings.



The possibility of carrying out area analyses helps to improve the planning of extensions to buildings, the purchase of additional buildings and the erection of new buildings. The area analyses are also useful for the building administrator in deciding whether a change in the distribution of existing rooms among users would benefit

University Group	Member
Department 1	Room 1
	Room 2
	Room 4
Department 2	Room 3
	Room 5
	Room 6
Department 3	Room 7
	Room 8
Institute 1	Department 1
	Department 2
	Department 3

himself and/or the users or increase the possible uses of the building. See also the process diagram below.

Besides a room index based on size and type, the building administrator will want to make indexes grouping room types by functions. If the group is recorded in the database or in a model instead of just being stored as an inquiry, it is possible for independent systems to use the information

A size index can be used directly as a basis for planning a cleaning schedule, including outsourcing/overall planning/management and the practical aspects of daily cleaning.

Residence Group	Member
Apartment 1	Room 101 Room 102 Room 103
Apartment 2	Room 201 Room 202 Room 203
Apartment 3	Room 301 Room 302 Room 303
Section A	Apartment 1 Apartment 2 Apartment 3 Room 001 (Corridor)

University Group	Member
Laboratory	Room 801 (Electrical) Room 802 (Structural) Room 903 (Chemistry)
Dark-room	Room 201 Room 202 Room 203
Special rooms	Laboratory Dark-room

#### 4.9.1.3.3. Linking the maintenance objects to the IFC objects

##### Task Description:

First task is to define the selection criteria for a maintenance group. Then the objects for a new group can be selected through various methods:

- *any objects selected by the user*
- *filtered objects (type, properties or other selection key) selected by the user*
- *filtered objects in the whole model*


After the selection is completed the user can give a description to the new maintenance group.

If the selected objects already belong to some maintenance group, the application should warn the user about it and ask for instructions for further operations.

When the maintenance groups are formed the user can use those as the selection criteria for different maintenance operations and reports. All maintenance data is stored in the maintenance object and the IFC object data should be available from the actual objects.



### Example Usage Scenario:



The different window and door types as well as other objects in the building can be linked to a maintenance object. The grouping mechanism is identical to the grouping activities.

With the description and classification attributes the different maintenance groups, purposes and needs can be identified. With delivery date and guarantee ending date the status of the guarantee can be stated. The guarantee terms can define the maintenance period and the maintenance instructions. With last maintenance date, maintenance handling and maintenance history the operations can be verified. The inspection intervals, last inspection date, inspection handling and inspection history helps the property manager to plan and define priorities for maintenance operations in connection with the information in cost object.

The guarantee terms, maintenance instructions, maintenance history and inspection history are pointers which refer to external databases or paper documents.

The dates of delivery, guarantee ending, last maintenance and last inspection as well as maintenance and inspection handling enable the search, selection of objects and operation to them on these criterion.

To plan and carry out facility maintenance a knowledge of the condition of the building and the funds available for the purpose is necessary. The Building administrator will base his decisions regarding building maintenance on inspections, which together with the funds/appropriations available form the basis of the budget and, consequently, the maintenance schedule for the budget period.

A typical maintenance sequence is shown below. The buildings are inspected periodically to record its condition and maintenance requirements, including whether the maintenance measures in question are preventive, remedial or reconstruct. The inspection results in a condition report, which the building administrator can use for a total price calculation. The calculation is compared with the funds available, which will enable the building administrator to prioritize maintenance jobs if necessary, in order not to exceed the total budget. The building administrator will have to evaluate the costs that will result from omitting a job, such as increased future maintenance costs and the possible expire of periods of guarantee. The result of this process is a budget which will also be a maintenance schedule. The physical maintenance can be implemented according to instructions provided either by the producer of the component in question or the instruction of the building administrator.

Condition report					
<i>SfB-Classification group</i>	<i>Material</i>	<i>Component</i>	<i>Supplementary description</i>	<i>State</i>	<i>What to do</i>
21(Facade)	Brick			OK	
22(Internal wall)	Brick		Crack above tile	Need repair	putty and painting
31(Window)	Steel		Rust in the bottom of the window frame	Need repair	cleaning, painting

## 4.10. [FM-4] Occupancy Planning

### Processes Defined in this project:

1. Occupancy Planning
2. Design of Workstations
3. Floor Layout of Workstations for an Open Office

### 4.10.1. Occupancy Planning

#### 4.10.1.1. Introduction

##### Overview:

The occupancy planner (includes interior designers, facilities managers, architects, furniture dealers' designers, etc.) applies standards during the assignment of people and organizations to interior spaces. It also involves the planning and moving of building assets such as equipment and furniture. This process occurs during the initial planning of space occupancy, and whenever that occupancy needs to change (company reorganization, company growth, or new hires, etc.). The layout and design of typical workstations can be sub-processes of the occupancy planning when it involves systems furniture planning for open offices. These processes require information about the building floor spaces. They also generate space occupancy data for future use of office planning.

Automatic input and utilization of the IFC supported object data, such as building elements and spaces as well as FF&E and occupants, may improve the efficiency of the processes. New objects generated will also be IFC compliant so that they can be used by various FM processes during the operation of the facility.

##### Process Scope:

- Evaluation of open spaces
- Move of people and FF&E

##### Out-of-Scope:

- Design of workstations
- Floor layout of workstations
- Stacking and blocking
- Work and purchase order tracking process

##### Definitions:

- FF&E: furniture, fixture, and equipment that is movable.
- Schematic Design: the conceptual allocation of space to define adjacencies and required functions defined by area and circulation paths.
- Move Plan: a plan that is used in Facilities Management for occupancy planning, moving people and FF&E around.


- Candidate Solution: existing or new spaces, as well as all the changes, work required, FF&E to be moved or purchased, occupants to be moved, that meet the requirements defined in the space programme.

#### References:

#### Contributors:

- Sandy Anderson (IBM) (NA) (temporary)
- Rick Bartling (Herman Miller) (NA)
- Vicky Borchers (MKS) (NA)
- Francois Grobler (USA-CERL) (NA)
- Jeff Laba (IBM) (NA) (temporary)
- Paul Lewis (Visio) (NA) (temporary)
- Elizabeth Menard (Naoki Systems) (NA)
- Richard See (Autodesk) (NA) (part-time)
- Rob Wakeling (Visio) (NA)
- Kevin Yu (Naoki Systems) (NA)

### 4.10.1.2. Process Diagram



### 4.10.1.3. Process Definition

#### 4.10.1.3.1. Overview

The occupancy planner (includes interior designers, facilities managers, architects, furniture dealers, etc.) applies standards during the assignment of people and organizations to interior spaces. This process occurs during the initial planning of space occupancy, and whenever that occupancy needs to change (company reorganization, company growth, etc.).

#### 4.10.1.3.2. Task A - Assess Move Request

##### Task Definition:

Assess request with respect to occupant information, company policies, and regulatory requirements. Identify FF&E required for the occupant, and generate space programme.

##### Example Usage Scenario:

The first step is to assess the move request. In this step, the occupancy planner evaluates the request with respect to occupant information, input for impact assessment for future move consolidation, company policies, and regulatory requirements. This step may identify the FF&E required, and finally generate the space program for the request.

#### 4.10.1.3.3. Task B - Evaluate Candidate Solutions

##### Task Definition:

Compare space programme to available (incl. existing or added) spaces to find candidate solutions including the changes of spaces and FF&E, required work, occupants to be moved, etc..

**Example Usage Scenario:**

The second step is to evaluate candidate solutions based on criteria such as optimal space use, adjacency and proximity, and future BPR (Business Process for Re-engineering) changes. The space program from the last step is used to block plan available spaces, and find candidate solutions that include the changes of spaces and FF&E. This process will also result in schematic designs.

**4.10.1.3.4. Task C - Develop Proposed Move Plan**

**Task Definition:**

During the design and generation of drawings, we allow for client review and approval. Define temporary staging areas, generate schedules, identify sources of all FF&E required and generate a cost estimate.

**Example Usage Scenario:**

An occupancy move plan should be developed in this step to allow for client review and approval. A list of all FF&E required is created. A preliminary work schedule and a cost estimate will be included in the plan. The schematic design used in the last step will also be included in the plan package.

**4.10.1.3.5. Task D - Approval Process**

**Task Definition:**

Occupant and management review proposed move plan and either approve (possibly with constraints) or rejects --> revert to previous steps.

**Example Usage Scenario:**

The approval process involves the review of proposed plan. This process could either approve (possibly with constraints) or rejects. In the case of rejection, it is possible that the move request is re-analyzed or the candidate solutions are re-evaluated.

**4.10.1.3.6. Task E - Complete Move Plan**

**Task Definition:**

Modify proposed plan to comply with constraints. Generate work orders and purchase orders.

**Example Usage Scenario:**

If the plan has been approved, there is a need to modify the proposal as with the constraints suggested. The work orders and purchase orders will be generated, and a new plan will be developed. Based on the new plan, bills-of-materials for the purchase of new FF&E will be produced.

**4.10.1.3.7. Task F - Implement Move Plan**

**Task Definition:**

Purchase FF&E. Perform work orders. Deal with change orders. Complete staging space. Move the occupant.

**Example Usage Scenario:**

The space occupants including the existing FF&E will be moved. During the implementation, as-built changes will be summarized and possibly updated into the original move plan. The implementation will eventually result in new or revised space and FF&E inventories.

**4.10.1.3.8. Task G - Updates**

**Task Definition:**

Revised documentation and databases to reflect new and revised spaces and assets.

### **Example Usage Scenario:**

Finally, documents and databases of space and asset (i.e. FF&E) inventory will be updated to reflect the changes.

## **4.10.2. Design of Workstations**

### **4.10.2.1. Introduction**

#### **Overview:**

The facility manager (also interior designers, architects, furniture manufactures and designers, contract furnishing dealer, etc.) designs typical workstations to be used by office staff. The workstations designed could be used as company standards and be selected in the layout of the systems furniture. This process could also occur in the entire process of occupancy planning in an organization.

#### **Process Scope:**

- Approval of design
- Systems furniture design

#### **Out-of-Scope:**

- Design of workstation groups
- Layout of workstations
- Stacking and blocking
- Standardizing workstations
- Technology configuration


#### **Definitions:**

- FF&E: furniture, fixture, and equipment that is movable.
- Systems furniture: is meant to represent furniture systems that integrate both modular and free-standing furniture with independent panels hanging furniture components such as work surfaces, storage, and so on.
- Workstation: a bound space assembled by systems furniture or floor to ceiling wall systems with necessary office equipment to house one or a few people to perform tasks.

#### **References:**

#### **Contributors:**

- Sandy Anderson (IBM) (NA) (temporary)
- Rick Bartling (Herman Miller) (NA)
- Vicky Borchers (MKS) (NA)
- Francois Grobler (USA-CERL) (NA)
- Rob Wakeling (Visio) (NA)
- Kevin Yu (Naoki Systems) (NA)



will also be created. For example, a programmer will need a computer; and based on the work types, the computer may need a modem.

The workstation requirements will be summarized that include security requirements (e.g. files must be locked), electrical and telecommunication requirements (e.g. 3-circuit, dedicated, network type, etc.), privacy requirements (e.g. visual privacy), and any types of special requirements such as aesthetic requirements. Table 2 shows a sample list of workstation component and equipment types for a computer programmer.

#### 4.10.2.3.3. Task B - Determine Basic Workstation Spaces

##### Task Definition:

Define spaces of the workstation (including circulation space inside of the workstation) according to the basic requirement of human dimension standards, and company policies.

##### Example Usage Scenario:

The basic spaces according to the human dimension standards requirements will be determined in this step. This step can be performed in parallel with the first one. Table 3 shows some examples of human dimension requirements for a basic workstation. One may also want to apply some company policies to this step.

#### 4.10.2.3.4. Task C - Define Workstation Configurations

##### Task Definition:

Finalize all workstation components with all detailed dimensions and material information, and spaces.

##### Example Usage Scenario:

After the above two steps have been finished, detailed workstation configurations will be designed, which include all the information about the components (see Table 4), equipment, and spaces (i.e. their dimensions, materials, space footage, and even brands, suppliers, models, colors, etc.), as well as acoustical and electrical properties.

**Table 2: List of Component and Equipment Types**

Furniture Component:	
worksurface	writing & reading PC computer file references accessories
Storage	filing storage reference storage
Seating	main chair (1)
Panel type	moderate privacy enclosure
Lighting	ceiling lighting
Equipment:	
PC Computer	1 (with modem)
Special Requirements:	
Worksurface	Worksurface height is 38 inches as requested by Jack

**Table 3: Human Dimension for Basic Workstation**

Zone/Height	Dimension (inch)
Worktask Zone	66 - 70
Chair Clearance Zone	66 - 70
Circulation Zone	24
Worksurface Height	29 - 35
Shelf Height	?

**Table 4: Sample Component Configuration of Workstation (unit: inch)**

Item Description	Dimension			Hanging/Mounting Height	Finish/ Color	Quantity	Remark
	Height	Width	Depth				
Overhead storage with task light	18	42	15	55	walnut	2	
Worksurface rectangle	N/A	42	42	38 (on request)	walnut	2	Special request
Worksurface square corner	N/A	42	48	38 (on request)	walnut	1	Special request
Chair	adjustable	22	22	N/A	blue foam		
Panel	76	42	2.5	N/A	grey		

#### 4.10.2.3.5. Task D - Design Workstation


##### Task

##### Description:

Produce the workstation drawings and define the specifications according to the configurations.

##### Example Usage Scenario:

Based on the configurations defined in the last step, design drawings and specifications will be produced in this step. See Figure 1 for an example of a workstation drawing.



**Figure 4: Sample Workstation**

#### 4.10.2.3.6. Task E - Approve Design

##### Task Description:

Corporation and also the user approve the design.

##### Example Usage Scenario:

This process examines the design produced in the last step and attempts to approve it or reject it based on criteria.

#### 4.10.2.3.7. Task F - Implement

##### Task Description:

Implement the design.

##### Example Usage Scenario:

After the design has been approved, the implementation will be executed.

### 4.10.3. Floor Layout of Workstations for an Open Office

#### 4.10.3.1. Introduction

##### Overview:

The facility manager (also interior designers, architects, or furniture dealers, etc.) designs the layout of the workstations for an open office. The purpose of the design is to organize the individual workstations into workstation groups with each usually representing a departmental unit and performing a certain type of function as a whole such as marketing. The workstation groups are assembled workstations connected by shared vertical panels. In order to group the workstations, employee work interaction patterns must be captured and block plan mechanism may be used. The process is part of the entire floor furniture and



equipment planning for the department(s), and occurs after typical individual workstations have been designed.

**Process Scope:**

- Floor blocking

**Out-of-Scope:**

- Bubble diagram design
- Design of workstations
- Standardizing of workstations
- Stacking
- Approval process of the design

**Definitions:**


- FF&E: furniture, fixture, and equipment that is movable.
- Workstation: is a bound space assembled by systems furniture or floor to ceiling wall systems with necessary office equipment to house one or a few people to perform tasks.
- Systems furniture: is meant to represent furniture systems that integrate both modular and free-standing furniture with modular contiguously grouped panels hanging furniture components such as work surfaces, storage, and etc..
- Workstation group: physically adjacent workstations that together perform a certain function, such as marketing, or computer programming.
- Floor blocking: the process of designing block plans that are two-dimension horizontal layout in a floor plan. Each block is a large bound zone that contains one or more work groups that represent a functional unit such as a department, etc..
- Bubble Diagram: a graphical diagram that depicts the adjacency relationships of work groups (e.g. departments) using circles and lines without floor space restrictions. The circles (i.e. bubbles) are used to represent the work groups by their size, color, or shading meaning the size and name of the group. The lines are used to represent the closeness of the adjacency usually by their thickness.

**References:**

- Julie K. Rayfield, "The Office Interior Design Guide – An Introduction For Facilities Management &

**Contributors:**

- Sandy Anderson (IBM) (NA) (temporary)
- Rick Bartling (Herman Miller) (NA)
- Vicky Borchers (MKS) (NA)
- Francois Grobler (USA-CERL) (NA)
- Rob Wakeling (Visio) (NA)
- Kevin Yu (Naoki Systems) (NA)




### Example Usage Scenario:

**Table 5: Sample Worksheet of Employee Interaction**

Employee Information			Interaction Description	With whom		Where	Importance Rating	Average Dur.	Daily Freq.
Name	Dept.	Position		Name	Dept.				
Jack	Dev.	System Designer	Program Corporation	Tony	Development	either office	3	30 min.	0.5
			Consulting	Kevin	Research	Kevin	2	30 min.	0.25
			Customer Requirement	Linda	Marketing	either	1	5 min.	1
			Approval	Jeff	Project Manager	Jeff	4	20 min.	0.25
...	...	...	...	...	...	...	...	...	...

An employee working interaction pattern summary is produced in this step. This summary includes information such as department name of the employees, with whom one has interaction with the other, how many times of such interaction, and average duration of each meeting. A worksheet (see Table 5) can be used for collecting information and interaction analysis.

From this information, an adjacency diagram may be used to clarify relationships and provide a basic schematic for further development of a floor plan (see Figure 2).



**Figure 5: Adjacency Diagram**


#### 4.10.3.3.3. Task B - Define Physically Adjacent Workstation Groups

##### Task Definition:

Define the functional workstation groups according to the individual employees working relationships summarized in the last step. A group consists of one or a few different types of typical workstations that have close working relationships, frequent or infrequent but critical interactions, and perform the same kind of functions. In the case that the interaction frequency and importance rating are conflict, a decision has to be made based on human judgement.

##### Example Usage Scenario:

Once the employee working interactions have been determined, the physically adjacent workstation groups can be defined with each providing a certain working function (e.g. development group). Each workstation group consists of one or a few different types of typical workstations that have close working relationships, frequent interactions, and perform the same kind of function as a whole. Adjacent workstation groups are typically connected by shared vertical panels and necessary connecting accessories. See Figure 3 for an example (*Note: this diagram doesn't show the actual results of the interaction relationships from the last step. Real world project examples may be provided later.*)



**Figure 6: Sample Workstation Group**

#### 4.10.3.3.4. Task C - Define Departmental Common Areas

##### Task Definition:

Define the areas that are shared by all employees in the department, such as common circulation and conference rooms, etc.

##### Example Usage Scenario:

The departmental common area such as the common circulation areas, conference rooms, printing service center, etc. is defined. This step can be performed independently with the first one. The common area requirements will be used for floor layout design in later steps.

**Table 6: Sample Adjacency Matrix**

<b>Accounting</b>	3	2	2	1	1
<b>Marketing</b>		3	2	2	1
<b>Executive</b>			3	2	2
<b>Operation</b>				2	2
<b>Research</b>					3
<b>Development</b>					

**Adjacency Rating Code:**  
1. Undesirable  
2. Desirable  
3. Essential


#### 4.10.3.3.5. Task D - Produce, Evaluate and Optimize Candidate Block Plans

##### Task Definition:

Segment large spaces for workstation groups according to the relationships between the workstation groups, and the relationships between departments in case of multiple departments. Floor geometry constraints such as column grids, ceiling grids, window grids, the space footage must be taken into consideration. A floor block can contain one or more workstation groups, or one or more workstations. This step also evaluates different candidate block plans and attempts to optimize the space or FF&E usage.

##### Example Usage Scenario:

After the above three steps, a floor block plan can be designed according to the relationships between the workstation groups, and the relationships between departments in case of multiple departments. The relationships between the workstations can be determined through the 'Adjacency Matrix' mechanism (see Table 6). Different adjacency rating scheme can be used. Building shell information such as column grids, ceiling grids, window grids, the space footage should be essential as input information for this design. Different candidate plans will be evaluated according to criteria of optimum use of space or FF&E. Eventually, each block could contain one or more workstation groups as well as individual workstations that do not belong to any defined group. Figure 4 is a sample that shows a portion of a floor block diagram.



**Figure 7: Sample Floor Block Diagram**

#### 4.10.3.3.6. Task E - Define Floor Layout Configurations

##### Task Definition:

Define all the detailed footage of all the workstations, workstation groups and departmental boundaries.

##### Example Usage Scenario:

In order to do the layout design, detailed floor layout configurations must be defined, which includes all the detailed footage of all the workstations, workstation groups, and departmental boundaries on the floor. The furniture system chosen during the floor layout configuration will affect the workstation boundaries.


#### 4.10.3.3.7. Task F - Design Floor Layout

##### Task Definition:

Produce the workstation layout drawings and define the specifications.

##### Example Usage Scenario:

Based on the configuration, the final step is to perform the design of floor workstation layout. From this step, drawings and specifications will be produced. Figure 5 shows a portion of a floor layout of workstations as an example.



**Figure 8: Sample Floor Layout of Workstations**

#### 4.10.3.3.8. Task G - Implement

##### Task Definition:

Implement the design of workstation layout.

##### Example Usage Scenario:

Once the design is approved, it is implemented based on the design drawings and specifications. During the implementation, existing inventories should be considered. Drawings are changed and as-built drawings are produced throughout the implementation.

#### 4.10.3.3.9. Task H - Update

##### Task Definition:

This is an on-going process that occurs during the course of design and implementation. Inventories are updated.

##### Example Usage Scenario:

As-built drawings are updated; any existing inventories are updated with left over furniture from the job.

## 4.11. *[SI-1] Photo Accurate Visualization*

### **Project process list:**

- Photo Accurate Visualization

### **4.11.1. Photo Accurate Visualization**

#### **4.11.1.1. Introduction**

**Overview:** In the design of a building or other structure, the architect or designer may want to see what the building or the structure will look like, or may want to render images for the client's benefit. Such visualization may be desired at any time from the earliest architectural design or retrofitting to the final interior design. Visualization is the key to solving lighting and daylighting design problems, and is also important in assessing building performance and human comfort issues.

#### **Process Scope:**

- Selection of surface materials
- Selection of lighting
- Rendering

#### **Out-of-Scope:**

- Process of acquisition of space/building geometry
- Photometric information that may be generated by the application used in the simulation

#### **Definitions:**

- None provided

#### **References:**


- None provided

#### **Contributors:**

- Vladimir Bazjanac (LBNL) (NA)
- Greg Ward (LBNL) (NA)

Note: Contributors listed here are people who have contributed to the definition of this process to-date; more names may be added later.

### 4.11.1.2. Process Diagram



### 4.11.1.3. Process Definition

#### Overview

The input information for the selection of materials consist of the three-dimensional representation of space or building geometry. Each of the surfaces that affect the rendering is associated with a particular material, for which reflectance, transmittance, color, pattern and texture are defined.

To perform a visual simulation, the user selects and places light sources (luminaires) in three-dimensional space, and specifies daylight conditions. Light source configuration and light distribution data are selected from manufacturers' catalogs. The sun and sky conditions (sky distribution and solar position specific to time in the simulation) are taken from a set of quantitative models (including daylight models) appropriate to the building site.

To define the rendering, the user also specifies a point in three-dimensional space from which the space or the building are viewed. The user may also specify the animation path, should he wish to create an animation. The output from the simulation are two-dimensional (floating point) color images, luminance and isolux contour plots, and/or animations.

The input of three-dimensional geometry description of the space or the building, if done manually, is very time-consuming an error prone. So is, to a lesser extent, the manual input of material and surface properties. If these data are originally input into IFC-compliant CAD software and data bases, the automatic acquisition of the data will reduce input preparation time by orders of magnitude and virtually eliminate input data error. This will substantially reduce the cost of use of visualization tools and make the daily application of such tools in building design and construction attainable.

#### Task Description

The user loads the space or building description (in form of 3-D building geometry), selects the materials for each surface that affects the rendering, defines the source(s) of light and the associated attributes, selects a view-point, defines the parameters of rendering and executes the simulation.

#### Example Usage Scenario

The architect has redesigned the space to serve as a computer classroom and has, together with the interior designer, planned the layout of computers and monitors in the space. Since three of the four walls that define this space have large windows, reflection and glare from monitor screens may render this layout unusable. To

find the extent of possible reflection and glare, the architect uses a high-end visualization tool to generate a photo-accurate image of the space and all furnishings. The resulting image clearly conveys that reflection from computer monitors will be unacceptable in the current layout. The architect and the interior designer will have to change the orientation (position) of monitors, introduce effective blinds or drapes, or change the layout of the space.



## 4.12. [XM-2] Project Document Management

### Domain process list:

- Project Document Management

### 4.12.1. Project Document Management

#### 4.12.1.1. Introduction

##### Overview:

Project Document Management refers to all information pertaining to the documents used to estimate, bid, purchase, and manage the building process as well as for use within the Facilities Management domain. This data identifies the document, the author of the document, changes to the document since the last change, and relationships to other documents.

It has been suggested to the group that the first concentration of our should be on the Contract Drawings represented in the model. It is acknowledged that this is only a small subset of the related documents of the model.

##### Process Scope:

- Create Drawing View:
- Retrieve Drawing View:

##### Out-of-Scope:

- All NonCAD Document Views (such as Specifications, Change Orders, etc.)

##### Definitions:

- **Bulletin** - a collection of Drawings, Specifications, Sketches, and instructions transmitted to the Project Team from the Architect in order to convey a clarification or change to the original drawings issued.
- **Addenda** - Similar to the Bulletin but released by the Architect prior to the signing of a contract between the Owner/Architect and the Construction Team.



- **Drawing** - A 2D representation of a collection of objects that are contained within the model. This may be seen as a view of the model in 2D for a select number of objects within a View Type (such as plan or section).
- **Specification** - A written representation of the objects within the model with instructions on how they are to be constructed (such as materials to be used, techniques in construction, show drawings to be submitted, etc.)

**References:** Any pertinent references or background materials used

- None at this writing.


**Contributors:** The names and chapters of the domain participants

- Raymond H. Brungard      NA
- Graham Storer              UK
- Arto Kiminieri              Nordic
- Richard See                  NA
- Ken Herold (part time)      NA
- Mike Cole (part time)       NA

#### 4.12.1.2. Process Diagram – Document Management

The diagram should illustrate how the tasks use the model to get data that was created by previous processes and to store data that may be used by later processes.

See Process Diagrams METAD1.vsd and METAD2.vsd under separate cover.



#### 4.12.1.3. Process Definition – Document Management

##### 4.12.1.3.1. Overview

This section should include overview information about subject process. This overview provides a sentence or two about each bubble in the Process Diagram. The overview should conclude with what bottlenecks or

areas of difficulty are frequently encountered in this process, and the benefits of enabling this process through IFC's.

The basic requirement of this process is to be able to create and retrieve views of the model which relate to the objects as 2D drawings used to. This means that a selection of objects may be chosen with a view type (the way in which the objects are to be viewed in 2D, such as plan or section view) to represent a discrete area or areas within the project. These areas can be interpreted as drawings in the sense that they may be printed out or viewed in the same manner as drawings are used today.

## **Process Task Descriptions**

### **4.12.1.3.2. Create Drawing View**

Identify Objects within the model to include in the Drawing View. These objects should be a complete representation of the work for its' view.

Identify the view type used to represent the objects within the drawing. This view type represents the way in which the objects are viewed, usually representing a direction of view, such as plan (viewing from the top).

Provide and apply a reference number, name, revision number, and general information regarding the intended drawing.

Provide for drawing "types", such as plumbing, electrical, concrete, etc.

Provide for additional references for aggregation of information such as Bulletin, Addenda, etc.

### **4.12.1.3.3. Retrieve Drawing View**

Receive the Bulletin, Addenda, or drawing set and their references.

Identify the Drawings within the set.

Identify Drawing type.

Identify the Objects within the drawings

Identify the View of the Objects.

Retrieve additional references.

## 5. Information Requirements Analysis

### 5.1. [AR-1] Architectural Model Extensions

#### 5.1.1. Process: Building Shell Design

##### 5.1.1.1. Information Analysis by Task

Please see the process overview description, process diagram and detailed process definition for this process in the "AEC+FM Industry Process Definitions" section of this document.

##### 5.1.1.1.1. Task 1 - Preliminary Building Massing (option 1)

See task description and usage scenario in the Process Definitions section above.

**Input Information:**

- . *A bubble diagram laid out floor by floor (Architecture block & stack)*
- . *Structural depths (Structural)*
- . *Codes*
- . *Core/Circulation*
- . *Roof Design*
- . *Floor to Ceiling heights*
- . *Preliminary BS depths*

**Output Information:**

- . *Refined floor plate shapes (Structural, Architecture)*
- . *Refined floor to floor heights (Structural, Architecture)*
- . *Volume and massing of the building (Architecture, HVAC, Simulation, Analysis)*
- . *Preliminary elevation shape (Architecture)*
- . *Exterior Circulation (ramps, balconies, docks, stairs, elevators)*

##### 5.1.1.1.2. Task 2 - Determine Relationship between Shell and Structure

See task description and usage scenario in the Process Definitions section above.

**Input Information:**

- . *Preliminary Massing Studies*
- . *Climate*
- . *Context*
- . *Architectural Styles*
- . *Preliminary Design Grid (Architecture)*
- . *Preliminary Structural Grid/System (Structural)*

**Output Information:**

- . *Floor plates and design grid (Structural, Architecture)*
- . *Refined elevation and model (Architecture)*

##### 5.1.1.1.3. Task 3 - Determine Fenestration (aesthetic criteria)

See task description and usage scenario in the Process Definitions section above.

**Input Information:**

- . *Refined floor plate shapes (Structural, Architecture, Construction)*
- . *Refined floor to floor heights (Structural, Architecture)*
- . *Preliminary Structural Depths (Structural)*

- . *Architectural Styles*
- . *Manufactured Systems*
- . *Volume and massing of the building (Architecture, HVAC, Simulation, Analysis)*
- . *Code requirements (fire access, sill heights, energy)*
- . *Preliminary elevation shape (Architecture, Structural)*
- . *Building Orientation (Architecture)*

**Output Information:**

- . *Window/Door dimensions (Architecture, HVAC, Simulation, Construction, Analysis)*
- . *Window/Door locations (Architecture, HVAC, Simulation, Construction, Analysis)*
- . *Glass Area (Architecture, HVAC, Simulation, Construction, Analysis)*
- . *Window/Door Type (Architecture ( HVAC, Simulation, Construction, Analysis)*
- . *Window/Door Framing (Architecture, HVAC, Simulation, Construction, Analysis)*
- . *Shading elements (overhang, brise desoleil, landscape elements, Analysis)*

#### **5.1.1.1.4. Task 4 - Define Shell Materials**

See task description and usage scenario in the Process Definitions section above.

**Input Information:**

- . *Project Material List (Architecture, Client)*
- . *Architectural Context*
- . *Lifecycle concerns*
- . *Construction Methods (Construction)*
- . *Code Considerations*

**Output Information:**

- . *Exterior wall type (HVAC, Simulation, Structural, Construction, Analysis)*
  - . *Composition*
  - . *Materials*
  - . *Connections*
- . *Window/Door Type*
  - . *Composition*
  - . *Materials*
- . *Project documents (information to others)*

#### **5.1.1.1.5. Task 5 - Costs**

See task description and usage scenario in the Process Definitions section above.

**Input Information:**

- . *Fenestration (Architecture)*
- . *Wall type (Architecture)*
- . *Window/Door type (Architecture)*
- . *Exterior Circulation (ramps, balconies, docks, stairs, elevators)*
- . *Preliminary Building Services*
- . *Occupancy*
- . *Loads (lighting, ventilation)*
- . *Waste Stream (greening)*

**Output Information:**

- . *Heat gain numbers*
- . *Heat Loss numbers*
- . *Preliminary energy analysis*
- . *Material*
- . *Equipment*
- . *Life Cycle Costs/Trade-Offs*
- . *Waste Stream/Trade-Offs (greening)*
- . *Construction Time*

#### 5.1.1.1.6. Task 6 - Visual Design Refinements

See task description and usage scenario in the Process Definitions section above.

**Input Information:**

- *Wall Type (Architecture)*
- *Cost*
- *Scale*
- *Building Services*
- *Relationship of Materials*
- *Architectural Style (Architecture)*

**Output Information:**

- *Details on adornment (Structural, Construction)*

#### 5.1.1.2. IFC Model Impact

This section summarizes the model requirements from all the process tasks analyzed above into two groups  
Extensions to R1.5.1 model object types and proposed new object types for R2.0.

##### **Extensions to IFC R1.5 object types**

- **IfcWindow**

**Data**

- {{ Data description      type }}
- {{ notes }}

- **IfcDoor**

**Data**

- {{ Data description      type }}
- {{ notes }}

##### **New object types required in IFC R2.0**

- **Parapet      IfcWall::Type = parapet**

**Data**

- {{ Data description      type }}
- {{ notes }}

- **Snow Build UP**

**Data**

- {{ Data description      type }}
- {{ notes }}

- **Wind**

**Data**

- {{ Data description      type }}
- {{ notes }}

- **Height**

**Data**

- {{ Data description      type }}
- {{ notes }}

- **Function (Handrail/Safety, Screening)**

**Data**

- {{ Data description      type }}
- {{ notes }}

- **Louver**

**Data**

- Geometry type
- Details type
- Material type
- Finish type
- Free Area (ventilation) type
- Screen/mesh size type
  - Structural framing for hole (detailed enough???)

- **Stair (See Stair Process)**

- Data**

- {{ Data description type }}
  - {{ notes }}

- **Ramp**

- Data**

- Geometry type
  - Material type
  - Finish type
  - Handrail (link) type
    - see Handrail
  - Guardrail (link) type
    - see Guardrail
  - Building code (link) type

- **Projections (ornamentation) NOTE: better word???**

- Data**

- Type (Canopy, Flag Pole, gargoyle, prefabricated balcony) type
  - Geometry type
  - Material type
  - Weight type
  - Manufacturer type
  - Orientation type
  - Connections to façade (e.g. bolt, steel clip, etc.) type

- **Curtain wall (window wall) (Look at CSI code Uniformat)**

- Data**

- Assembly type
  - Surface (link) type
  - Manufacturer type
  - Detail type
  - Building code (link) type
  - Specification (link) type

- **Foundation (elements, connections) see foundation design**

**\*\* Note: need to know: floor to floor; floor plate; topography(grade)\*\***

### **5.1.1.3. RoadMap Issues**

#### **Interoperability Value**

##### **Disciplines/Applications from which information is needed:**

- Structural
- HVAC
- Energy
- Codes

***Disciplines/Applications to which information will be supplied:***

- HVAC
- Simulation
- Construction
- Facility Management
- Specifications

***Value of software supporting this process***

In this section, other domain teams will rank the value of software which supports this process, based on IFC.

- {{ discipline 1 }} - {{value from 1-10, 1 being the lowest value, 10 being the highest value}}
- {{ discipline 2 }} - {{value from 1-10}}

***Sponsor Software Companies***

The following organizations that develop software used by AEC end users have shown interest in developing applications which implement the process:

- {{ company 1 }}
- {{ company 2 }}

***5.1.1.4. Issues identified in reviews***

***No reviews recorded***

**Issues**

**Proposed resolution**

- No issues recorded
  - No resolutions recorded

**5.1.2. Process: Building Core Design**

See Process Definitions section above.

***5.1.2.1. Information Analysis by Task***

Please see the process overview description, process diagram and detailed process definition for this process in the "AEC+FM Industry Process Definitions" section of this document.

***5.1.2.1.1. Task 1 - Determine Core Spaces Needed***

See task description and usage scenario in the Process Definitions section above.

***Input Information:***

- Space program (owner requirements)
- Occupancy (Floor by Floor)
- Occupancy Type (Assembly, etc in code)
- Codes/Egress (Distances) (Look to AR-2)
- Building Services (# and type of service)
- Vertical Circulation (#, type)

***Output Information:***

- Spaces (#, type)

#### 5.1.2.1.2. Task 2 - Determine Core Space Sizes

See task description and usage scenario in the Process Definitions section above.

**Input Information:**

- Calculate elevators (Number and sizes length, width, and type (freight vs. passenger )( Freight lobbies)
- Calculate Stairs (process ##### Length, width)
- Floor to Floor Heights
- Number of Floors
- Calculate Escalator (width, length)
- Alarm Stations (width, length)
- Restroom Design (process ##### length, width, area)
- Required spaces (length/width or area) Electrical, Communications, Waste Disposal, Janitorial, Mechanical

**Output Information:**

- Required spaces (length/width or area) (Collection of spaces ie (Core, parking)

#### 5.1.2.1.3. Task 3 - Layout Core Spaces

See task description and usage scenario in the Process Definitions section above.

**Input Information:**

- Structural Grid (grid of object, including shear walls etc.
- Max. Distance between exit stairs.
- Space efficiency (% usable goal)
- Parking Plan
- Required spaces (length/width or area) Electrical, Communications, Waste Disposal, Janitorial, Mechanical, Stair, Elevator, Escalator

**Output Information:**

- Core layout (collection of spaces)

#### 5.1.2.1.4. Task 4 - Detailed Design of Stairs

Covered elsewhere - in Restroom design Process

#### 5.1.2.1.5. Task 5 - Detailed Design of Restrooms

Covered elsewhere - in Restroom design Process

### 5.1.2.2. IFC Model Impact

This section summarizes the model requirements from all the process tasks analyzed above into two groups  
Extensions to R1.5.1 model object types and proposed new object types for R2.0.

#### **Extensions to IFC R1.5 object types**

- **None specified**

#### **New object types required in IFC R2.0**

- **Stairs (Actual object)**

**Data**

- {{ Data description      type }}
- {{ notes }}

- **Stairs Well**

**Data**

- {{ Data description      type }}



- {{ notes }}

- **Elevator Shaft**

- Data**

- {{ Data description      type }}
    - {{ notes }}

- **Elevator**

- Data**

- {{ Data description      type }}
    - {{ notes }}

- **Emergency services**

- Data**

- Fire Standpipe      type
    - Hose      type

### **5.1.2.3. RoadMap Issues**

#### **Interoperability Value**

##### ***Disciplines/Applications from which information is needed:***

- Structural
- HVAC
- Telecommunications
- Plumbing
- Electrical

##### ***Disciplines/Applications to which information will be supplied:***

- Structural
- HVAC
- Telecommunications
- Plumbing
- Electrical
- Specifications

#### **Value of software supporting this process**

In this section, other domain teams will rank the value of software which supports this process, based on IFC.

- {{ discipline 1 }} - {{value from 1-10, 1 being the lowest value, 10 being the highest value}}
- {{ discipline 2 }} - {{value from 1-10}}

#### **Sponsor Software Companies**

The following organizations that develop software used by AEC end users have shown interest in developing applications which implement the process:

- {{ company 1 }}
- {{ company 2 }}

### **5.1.2.4. Issues identified in reviews**

#### **No reviews recorded**

##### **Issues**

### **Proposed resolution**

- No issues recorded
- No resolutions recorded

## **5.1.3. Process: Stair Design**

See Process Definitions section above.

### **5.1.3.1. Information Analysis by Task**

Please see the process overview description, process diagram and detailed process definition for this process in the "AEC+FM Industry Process Definitions" section of this document.

#### **5.1.3.1.1. Task 1 - Locate Stairs**

See task description and usage scenario in the Process Definitions section above.

##### **Input Information:**

- *Configuration (type straight, Scissors)*
- *Owner Requirements*
- *Codes*
- *Occupancy*
- *Circulation*
- *Core Inputs (location exit, etc.)*

##### **Output Information:**

- *Location and Type*

#### **5.1.3.1.2. Task 2 - Determine Width**

See task description and usage scenario in the Process Definitions section above.

##### **Input Information:**

- *Configuration (type straight, Scissors, spiral)*
- *Handrail projection (Depth)*
- *Clear Area (distance) between handrail*
- *Stair use (Fire stair, Ornamental)*
- *Codes (Tread Width(distance))*
- *Egress (# of occupants by building type)*
- *Owner Requirements (Grander defined width)*

##### **Output Information:**

- *Width of treads*

#### **5.1.3.1.3. Task 3 - Determine Tread depth and Risers height**

See task description and usage scenario in the Process Definitions section above.

##### **Input Information:**

- *Floor to Floor Heights*
- *Acoustic rating (stc, impact rating)*
- *Codes (Max and min, ratio, nosing depth)*
- *Owner requirements (Depth, Rise) consistent fall within the ratio*

##### **Output Information:**

- *Tread depth*
- *Riser height*
- *Nosing Depth*
- *Landing Locations*

- *Material Type*
- *Finish*

#### 5.1.3.1.4. Task 4 - Determine Landing

See task description and usage scenario in the Process Definitions section above.

**Input Information:**

- *Stair Width*
- *Acoustic rating (stc, impact rating)*
- *Door, standpipe, handrail, clearance*
- *Special Criteria (depth, width)*

**Output Information:**

- *geometry of Landings*
- *Material Type*
- *Finish*

#### 5.1.3.1.5. Task 5 - Guardrail Design

See task description and usage scenario in the Process Definitions section above.

**Input Information:**

- *Code (min. /max height, balustrade spacing, Minimum penetration size)*
- *Special Criteria (min. /max height, balustrade spacing, Minimum penetration size)*

**Output Information:**

- *Guardrail geometry*
- *Material Type*
- *Finish*
- *Guardrail specifications (min. /max height, balustrade spacing, Minimum penetration size))*

#### 5.1.3.1.6. Task 6 - Handrail Design

See task description and usage scenario in the Process Definitions section above.

**Input Information:**

- *Code (Minimum projections, min. /max height, diameter, extension from base, extension from top, continuation)*
- *Stair configuration (egress, ornamental)*
- *Special Criteria (Minimum projections, min. /max height, diameter, extension from base, extension from top, continuation)*

**Output Information:**

- *Handrail geometry*
- *Material Type*
- *Finish*
- *Handrail specifications (Minimum projections, min. /max height, diameter, extension from base, extension from top, continuation)*

#### 5.1.3.1.7. Task 7 - Construction and Materials

See task description and usage scenario in the Process Definitions section above.

**Input Information:**

- *none identified*

**Output Information:**

- *none identified*

### 5.1.3.1.8. Task 8 - Finalize Design

See task description and usage scenario in the Process Definitions section above.

**Input Information:**

- *Life Safety Requirements*
- *Exits*

**Output Information:**

- *Lighting needs*
- *Ventilation needs*
- *Pressurization*
- *Signage*
- *Stair Design*

### 5.1.3.2. IFC Model Impact

This section summarizes the model requirements from all the process tasks analyzed above into two groups  
Extensions to R1.5.1 model object types and proposed new object types for R2.0.

#### **Extensions to IFC R1.5 object types**

- **None specified**

#### **New object types required in IFC R2.0**

- **Treads**

**Data**

- *RiserHeight* type
- *TreadDepth* type
- *TreadMaterial*
- *NosingMaterial*
- *TreadType*

- **Handrails**

**Data**

- *HandrailType* type
- *Material* type
- *DepthFromWall* type

- **Guardrails**

**Data**

- *GuardrailType* type
- *Material* type
- *DepthFromWall*

- **Landings**

**Data**

- *Depth* type
- *Width* type
- *Material* type

- **Stringer**

**Data**

- *Depth* type
- *Width* type
- *Material* type
- *Shape (surfaces)* type

### 5.1.3.3. RoadMap Issues

#### **Interoperability Value**

##### **Disciplines/Applications from which information is needed:**

- *Structural*
- *Codes*

##### **Disciplines/Applications to which information will be supplied:**

- *Plumbing*
- *Electrical*
- *Codes*
- *Construction*
- *Facility Management*
- *Structural*
- *Specifications*

#### **Value of software supporting this process**

In this section, other domain teams will rank the value of software which supports this process, based on IFC.

- {{ discipline 1 }} - {{value from 1-10, 1 being the lowest value, 10 being the highest value}}
- {{ discipline 2 }} - {{value from 1-10}}

#### **Sponsor Software Companies**

The following organizations that develop software used by AEC end users have shown interest in developing applications which implement the process:

- {{ company 1 }}
- {{ company 2 }}

### 5.1.3.4. Issues identified in reviews

#### **No reviews recorded**

##### **Issues**

##### **Proposed resolution**

- No issues recorded
  - No resolutions recorded

### 5.1.4. Process: Public Restroom Design

See Process Definitions section above.

#### 5.1.4.1. Information Analysis by Task

Please see the process overview description, process diagram and detailed process definition for this process in the "AEC+FM Industry Process Definitions" section of this document.

##### 5.1.4.1.1. Task 1 - Determine Requirements

See task description and usage scenario in the Process Definitions section above.

##### **Input Information:**

- . *Occupancy type*
- . *Program Occupancy (number)*
- . *Floor area*
- . *Municipal fixtures requirements*
- . *ADA (clearances)*
- . *Special Criteria (list of fixtures)*

**Output Information:**

- . *Fixtures number and types and spacing (clearance) (urinal, WC wall, WC floor etc.)*

#### **5.1.4.1.2. Task 2 - Layout**

See task description and usage scenario in the Process Definitions section above.

**Input Information:**

- . *Fixtures (mounting height, clearances)*
- . *Plumbing considerations (Renovation)*
- . *Codes (Entry, turnaround space)*
- . *accessories (grab bars, mirrors, paper towel, trash, partition etc.) mounting, clearances, width, length, height, depth.*
- . *Core constraints (width, length, area, polygonal area)*
- . *drainage*
- . *Structural Grid*

**Output Information:**

- . *Location, height of fixtures and accessories*
- . *Location of walls, doors*
- . *Space geometry*
- . *FloorDrain*
- . *Millwork (cabinets and counter tops)*

#### **5.1.4.1.3. Task 3 - Construction Detailing, Finishes and Lighting**

See task description and usage scenario in the Process Definitions section above.

**Input Information:**

- . *Space geometry*
- . *Fixtures types, locations*
- . *accessories (grab bars, mirrors, paper towel, trash, partition etc.) mounting, clearances, width, length, height, depth.*
- . *Client requirements (ie. stone)*

**Output Information:**

- . *Partition types*
- . *Fixture and accessories manufactures model etc.*
- . *\*\* Note: finish decisions \*\**

#### **5.1.4.2. IFC Model Impact**

This section summarizes the model requirements from all the process tasks analyzed above into two groups  
Extensions to R1.5.1 model object types and proposed new object types for R2.0.

##### ***Extensions to IFC R1.5 object types***

- ***None specified***

##### ***New object types required in IFC R2.0***

- ***Fixture (Anything coordinated with another discipline)***  
***Data***

- *MoutingHeight* type
- *DrainConnectionPoint* type
- *HwConnectionPoint* type
- *CwConnectionPoint* type
- *ElectricalConnectionPoint* type
- *RoughOpening* type
- *Detail (link)* type
- *BuildingCode (link)* type
- *OperatingControlLocation (dispenser conforms to range)* type
- *Material* type
- *Finish* type
- *AssociatedFitting* type
- *GraphicSymbol* type
- *Color* type
- *MountingType* type
- *Manufacturer* type

- **Accessories (Everything else)**

- Data**

- *MountinHeight* type
    - *BoundingBox* type
    - *RoughOpening* type
    - *Detail (link)* type
    - *BuildingCode (link)* type
    - *OperatingControlLocation (dispenser conforms to range)* type
    - *Material* type
    - *Finish* type
    - *Graphic Symbol* type
    - *Color* type
    - *MountingType* type
    - *Manufacturer* type

- **Manufactured Partitions**

- Data**

- *Height* type
    - *Width* type
    - *Thickness* type
    - *Door (link)* type
    - *Hardware (link)* type
    - *Material* type
    - *Detail (link)* type
    - *Specification (link)* type
    - *Finish* type
    - *Mounting* type
    - *Manufacturer* type

- **Millwork (Casework)**

- Data**

- *MountingHeight* type
    - *Geometry* type
    - *MountingHardware* type
    - *Detail (link* type)
    - *Manufacturer* type

### **5.1.4.3. RoadMap Issues**

#### ***Interoperability Value***

##### ***Disciplines/Applications from which information is needed:***

- *Structural*
- *Plumbing*
- *HVAC*
- *Electrical*

##### ***Disciplines/Applications to which information will be supplied:***

- *HVAC*
- *Plumbing*
- *Structural*
- *Electrical*
- *Construction*
- *Facility Management*
- *Specifications*

#### ***Value of software supporting this process***

In this section, other domain teams will rank the value of software which supports this process, based on IFC.

- {{ discipline 1 }} - {{value from 1-10, 1 being the lowest value, 10 being the highest value}}
- {{ discipline 2 }} - {{value from 1-10}}

#### ***Sponsor Software Companies***

The following organizations that develop software used by AEC end users have shown interest in developing applications which implement the process:

- {{ company 1 }}
- {{ company 2 }}

### **5.1.4.4. Issues identified in reviews**

#### ***No reviews recorded***

##### **Issues**

##### **Proposed resolution**

- No issues recorded
  - No resolutions recorded

### **5.1.5. Process: Roof Design**

See Process Definitions section above.

#### ***5.1.5.1. Information Analysis by Task***

Please see the process overview description, process diagram and detailed process definition for this process in the "AEC+FM Industry Process Definitions" section of this document.

##### **5.1.5.1.1. Task 1 - Design Roof**

See task description and usage scenario in the Process Definitions section above.



**Input Information:**

- . *Budget constraints*
- . *Community and regional standards*
- . *Environment such as snow or tepid regions*
- . *Screening building services*
- . *Image (height, patterns, fabric)*
- . *Client Requirements (material which would effect pitch)*
- . *Lifecycle Requirements*
- . *Fire Exiting (penthouse)*
- . *Alternative Energy (passive design, orientations, equipment)*
- . *Live load based on use*
- . *Codes (fire, class, slopes)*
- . *Functional requirement (structural loading, pool, )*
- . *Building massing*
- . *Building materials*
- . *Structural*
- . *Surrounding Building Scapes*

**Output Information:**

- . *Basic form of roof (i.e. Flat, pitched, shed, etc.)*
- . *Material requirements (i.e. clay tile roofing, slate)*
- . *Slope*
- . *Structural depths*
- . *Area of roof planes*
- . *Vert/horz projections*
- . *Lifecycle*

**5.1.5.1.2. Task 2 - Skylight/Clear Story**

See task description and usage scenario in the Process Definitions section above.

**Input Information:**

- . *Codes*
- . *Environmental*
- . *Structural*
- . *Client requirements*
- . *Day lighting*
- . *Ventilation*
- . *Lifecycle*
- . *Design Intent*
- . *Energy requirements*
- . *Manufacturer input*

**Output Information:**

- . *Geometry*
- . *Glazing properties*
- . *Materials (performance properties)*
- . *Manufacture information*

**5.1.5.1.3. Task 3 - Layout of Services**

See task description and usage scenario in the Process Definitions section above.

**Input Information:**

- . *HVAC equipment and piping locations*
- . *Telecommunications needs in respect to roof dishes etc.*
- . *Plumbing venting stacks*
- . *Circulation (stairwell)*
- . *Roof Circulation*
- . *Amenities (pool, heliport)*

- *Fire Protection*
- *Maintenance requirements*

**Output Information:**

- *Location and geometry of penetration*
- *Location geometry of loading*
- *Location of amenities and equipment*
- *Equipment access*

#### **5.1.5.1.4. Task 4 - Design Rain/Snow Drainage**

See task description and usage scenario in the Process Definitions section above.

**Input Information:**

- *Structure*
- *Roof geometry*
- *Contributing sources (adjacent surfaces walls etc.)*
- *Geographic location and weather information.*
- *Lifecycle (materials copper vs steel)*
- *Code requirements*
- *Site considerations (drainage)*

**Output Information:**

- *Water/Snow drainage plan*
- *Rough drain/downspouts location and sizes (interior drainage)*
- *Maintenance requirements*

#### **5.1.5.2. IFC Model Impact**

This section summarizes the model requirements from all the process tasks analyzed above into two groups  
Extensions to R1.5.1 model object types and proposed new object types for R2.0.

##### **Extensions to IFC R1.5 object types**

- **None specified**

##### **New object types required in IFC R2.0**

- **Stairs Well**

**Data**

- {{ Data description    type }}
- {{ notes }}

- **Roof**

**Data**

- *Style (flat, sloped, etc.)    type*
- *Fire Classification (A,B, ...)    type*
- *Space (link)    type*
  - *size and volume for ventilation*

- **Climate (Check spec and BS)**

**Data**

- {{ Data description    type }}
- {{ notes }}

- **RoofSurface**

**Data**

- *Geometry    type*
- *Assembly (material - membrane assembly    type*
- *Lifecycle (link) )    type*

- Surface (link) ) type
- Specification (link) ) type
- FireClassification) type
- **Surface (Apply to all object)**
  - Data**
  - Reflectivity type
  - RenderingAttribute (link to material) type
  - Color type
  - Roughness (list) friction coefficient) type
  - Transparency ) type
- **Specification (property set) (Apply to all object)**
  - Data**
  - Section (pointer to file or contained text block) type
- **Assembly (property set) (Apply to all object)**
  - Data**
  - Factors (list for assembly) type
  - Material (link) (factors/attributes) type
- **Lifecycle (property set) (Apply to all object)**
  - Data**
  - ServiceLife type
  - Maintenance interval type
  - Warranty type
  - Salvage Value type
  - Recyclability (property sets?) type
  - Disposal (test field) type
  - Cost (link) type
- **Skylights (could be domed, barrel vault)**
  - Data**
  - Geometry type
  - Location type
  - Manufacture type
  - Glazing type type
    - (Ufactor, solar head gain coefficient, vis light transmittance, layers, air space, shading coefficient) (Have someone look at galzing type code/BS)
  - GlazingArea) type
  - FrameType) type
  - Operable (same windows?) ) type
  - VentilationArea) type
  - RoughOpening) type
  - FinishedOpening) type
  - EdgeType (assembly/detail) ) type
  - LifeCycle ) type
    - pulled out to Property set applied to all objects
- **Joint (Expansion, Edge condition, Control Joint)**
  - Data**
  - Assembly (fill the gap) type
  - Type (Expansion, Edge, Control, Score, Reveal) type
  - Pointer to objects type
  - Details type
  - FireRating type
  - Waterproof type
  - Ventilation type

- *Manufacturer* type
- *RangeOfMovement* type
- *DirectionOfMovement* type
- *Lifecycle* type

- **Scupper (General opening/edge and object inserted to take)**

**Data**

- *Geometry* type
- *Material* type
- *Detail* type
- *Manufacturer* type

- **RoofDrain/DownSpout**

**Data**

- *Detail* type
- *Location* type
- *Manufacturer* type (text string?)
- *Specification (link)* type
- *Material* type

- **Gutters**

**Data**

- *Geometry* type
- *Slope* type
- *Capacity* type
- *Detail* type
- *Interface - Drainage*
- *FlowVolume* type
- *TributaryArea (Roof planes, Adjacent Surfaces)* type
- *PrimaryDrainage* type
- *Secondard* type
- *Size* type
- *Interface - Snow*
- *SnowZone* type
- *Load* type

- **Mech screen**

**Data**

- *Length* type
- *Width* type
- *Height* type
- *Type (assembly)* type

- **Window cleaning**

*(rigging, tracks, rails, carriage, apparatus, maybe this should be pulled out as a process)*  
*(Separate object type?)*

**Data**

- *Location* type
- *Type* type
- *Connection* type

- **Projections (mechanical screens)**

**Data**

- *ProjectionType* type
- *Length* type
- *Material* type
- *Weight* type
- *Orientation* type

- vertical, horizontal, etc
- Connection type
  - connection to facade ie. bolt, steel
- **Stairs (See Stair Process)**
- **Access (walkways, etc)**
  - Data**
  - Path type
  - Composition (assembly) type
  - Width type

### 5.1.5.3. RoadMap Issues

#### **Interoperability Value**

##### ***Disciplines/Applications from which information is needed:***

- Structural
- HVAC
- Plumbing
- Telecommunications
- Electrical
- Municipal codes

##### ***Disciplines/Applications to which information will be supplied:***

- Structural
- Plumbing
- Telecommunications
- HVAC (heat gain/heat loss analysis)
- Electrical
- Municipal Codes
- Specifications

#### **Value of software supporting this process**

In this section, other domain teams will rank the value of software which supports this process, based on IFC.

- {{ discipline 1 }} - {{value from 1-10, 1 being the lowest value, 10 being the highest value}}
- {{ discipline 2 }} - {{value from 1-10}}

#### **Sponsor Software Companies**

The following organizations that develop software used by AEC end users have shown interest in developing applications which implement the process:

- {{ company 1 }}
- {{ company 2 }}

### 5.1.5.4. Issues identified in reviews

#### **No reviews recorded**

##### **Issues**

##### **Proposed resolution**

- No issues recorded

- No resolutions recorded

## 5.2. [AR-2] Compartmentation of Buildings

### 5.2.1. Process: Compartmentation of buildings

#### 5.2.1.1. Information Analysis by Task

Please see the process overview description, process diagram and detailed process definition for this process in the "AEC+FM Industry Process Definitions" section of this document.

##### 5.2.1.1.1. Task A - Identify Main/Ancillary Use Spaces

See description in the Process definition section above.

**Input Information:**

- . Project Information
- . Project Geometry
- . Building Use Type
- . Building Geometry
- . Use Classification
- . Occupancy

**Output Information:**

- . Main Use Spaces
- . Ancillary Use Spaces

##### 5.2.1.1.2. Task B - Adjust Main/Ancillary according to Code

See description in the Process definition section above.

**Input Information:**

- . Project Information
- . Project Geometry
- . Building Use Type
- . Building Geometry

**Output Information:**

- . Additional Main Use Spaces if any.

##### 5.2.1.1.3. Task C - Identify Single Occupancy Spaces

See description in the Process definition section above.

**Input Information:**

- . Project Information
- . Project Geometry
- . Building Use Type
- . Building Geometry
- . Use Classification
- . Occupancy

**Output Information:**

- . Single Occupancy Spaces

#### 5.2.1.1.4. Task D - Check Areas/Volumes to Design Fire Compartments

See description in the Process definition section above.

**Input Information:**

- Main Use Spaces
- Single Occupancy Spaces.

**Output Information:**

- Fire Compartments.

#### 5.2.1.2. IFC Model Impact

This section summarizes the model requirements from all the process tasks analyzed above into two groups  
Extensions to R1.5.1 model object types and proposed new object types for R2.0.

##### **Extensions to existing R1.5.1 Object Types**

- IfcProject
- IfcSite
- IfcBuilding
- IfcSpace

##### **New object types required in IFC R2.0**

- **IfcMainUseSpace**

**Data**

- FireUseClassification IfcClassification
- (A MainUseSpace will have one Fire Use which is assigned from the FireUseClassification)

- **IfcAncillaryUseSpace**

**Data**

- FireUseClassification IfcClassification
- (An AncillaryUseSpace will have one Fire Use which is assigned from the FireUseClassification. An AncillaryUseSpace is contained by one MainUseSpace)

- **IfcSingleOccupancySpace**

**Data**

- SingleOccupancyPossessor STRING
- (Defines who possesses and uses a space for fire compartmentation purposes)

- **IfcFireCompartment**

**Data**

- UseType STRING
- (no description)

#### 5.2.1.3. RoadMap Issues

##### **Interoperability Value**

**Disciplines/Applications from which information is needed:**

- Client Brief
- Architecture Building Model)
- Services Engineers)

**Disciplines/Applications to which information will be supplied:**

- Architecture

### **Target Software Companies/Application Type**

- *Architects and Fire Officers*
- *CAD systems providers (Autodesk)/Autocad*
- *CAD-support FM applications /space planning, occupancy planning, and asset management databases*

### **Value of software supporting this process**

In this section, other domain teams will rank the value of software which supports this process, based on IFC.

- *Architecture: High (in the top 5)*
- *FM: Very High (in the top 3)*
- *CM/Cost: Very High (in the top 3)*
- *Building Service:*
- *HVAC:*

### **Sponsor Software Companies**

The following organizations that develop software used by AEC end users have shown interest in developing applications which implement the process:

- *Autodesk - UK*
- *SSi*

#### **5.2.1.4. Issues identified in reviews**

##### **No reviews recorded**

##### **Issues**

##### **Proposed resolution**

- No issues recorded
  - No resolutions recorded

### **5.3. [BS-1] HVAC System Design**

#### **5.3.1. Process: HVAC Duct System Design**

HVAC Duct System Design supports the design and representation of air distribution ductwork systems. Engineers typically perform these processes during the design phase of a building or project, prior to construction. The process culminates with a set of drawings, schedules, and specifications (construction documents) that can be bid upon and constructed.

##### **5.3.1.1.1. Select and Locate System Components**

This step involves selecting and locating the air terminals, boxes (if included in the design), and fans that compose the HVAC duct system.

##### **Input Information:**

- *Floor plans*
- *Ceiling grid plans*
- *Reflected ceiling plans*
- *Lighting plans*
- *Structural plans*



- *Sprinkler plans*
- *Piping plans*
- *Smoke detector plans*
- *Speaker plans*

**Output Information:**

- *Pset\_AirTerminal*
- *Pset\_CoordinationRequirement*
- *Pset\_TerminalBox*
- *IfcPathwayElement*
- *IfcEquipment*

**Project Model Usage Requirements:**

**Object types existing in R1.5.1:**

- **IfcWall**

*Data*

- *All available data*
  - *Location and type information (i.e., fire ratings, special construction types, etc.). This allows the designer to identify the potential locations for air terminals, boxes and fans*

- **IfcSpace**

*Data*

- *Programme information*
  - *Information specific to the intended function of the space, which is used to determine the number and type of air terminals to be installed.*

- **IfcCeiling**

*Data*

- *Ceiling Type information*
  - *Information needed to determine the type and location of air terminals to be installed.*
  - *Information needed to determine clearances in interstitial spaces.*

- **IfcBeam**

*Data*

- *Type, size and location of beams*
  - *This information is needed to prevent conflicts with air terminals and terminal boxes.*

- **IfcFluidMover**

*Data*

- *All available data.*
  - *This information coupled with the Pset\_Fan or Pset\_AirHandlingUnit property sets are used to locate and initially specify the fan.*

**Object types to add in R2.0:**

*See the IFC Model Impact section for class details.*

### 5.3.1.1.2. Connect Components with Ducts and Fittings

This step involves using engineering judgment to connect the air terminals, boxes, and fans with ducts and fittings. This information is then used for preparing drawings or specifications which will schematically represent the system under design. These schematics are then used to begin coordination with other disciplines which are impacted by the system.

**Input Information:**

- *Floor plans*
- *Structural plans*
- *Pset\_CoordinationRequirement*

**Output Information:**

- *Pset\_DuctFitting*
- *Pset\_DuctSegment*
- *IfcPathwayElement*

**Project Model Usage Requirements:**

**Object types existing in R1.5.1:**

- ***IfcWall***

*Data*

- All available data
  - Location and type information (i.e., fire ratings, special construction types, etc.). This allows the designer to locate ducts and fittings appropriately.

- ***IfcCeiling***

*Data*

- Ceiling Type information
  - Information needed to determine where duct and fittings can be located.

- ***IfcBeam***

*Data*

- Type, size and location of beams
  - This information is needed to prevent conflicts between beams and ducts and fittings.

**Object types to add in R2.0:**

*See the IFC Model Impact section for class details.*

### 5.3.1.1.3. Sizing the Duct and Fittings

The sizes of the duct and fittings are calculated.

**Input Information:**

- *Pset\_HVACSpaceElementInformation*
- *Pset\_DuctSystemDesignCriteria*
- *Pset\_DuctDesignCriteria*

**Output Information:**

- *Pset\_CoordinationRequirement*
- *Pset\_RectangularDuctConnection*
- *Pset\_RoundDuctConnection*
- *Pset\_OvalDuctConnection*

**Project Model Usage Requirements:**

**Object types existing in R1.5.1:**

- ***Pset\_HVACSpaceElementInformation***

*Data*

- MaximumAirflow and MinimumAirflow values calculated from the room or space load calculations.

**Object types to add in R2.0:**

*See the IFC Model Impact section for class details.*

### 5.3.1.1.4. Locate Other System Components

Identify and locate other system components required for the duct system.

**Input Information:**

- . *Pset\_DuctSystemDesignCriteria*
- . *Pset\_DuctDesignCriteria*
- . *IfcWall*

**Output Information:**

- . *Pset\_CoordinationRequirement*
- . *IfcDamper*
- . *IfcPathwayElement*
- . *IfcControlElement*
- . *IfcActuator*

**Project Model Usage Requirements:**

**Object types existing in R1.5.1:**

- ***IfcWall***  
Data
  - All available data
    - Location and type information (i.e., fire ratings, special construction types, etc.). This allows the designer to identify locations for system components such as fire dampers.

**Object types to add in R2.0:**

*See the IFC Model Impact section for class details.*

### 5.3.1.1.5. Interference Check

Identify any interferences with other trades.

**Input Information:**

- . *Plumbing/Sprinkler plans*
- . *Piping plans*
- . *Floor plans*
- . *Ceiling grid plans*
- . *Reflected ceiling plans*
- . *Lighting plans*
- . *Power plans*
- . *Structural plans*
- . *Pset\_CoordinationRequirement*

**Output Information:**

- . *Pset\_CoordinationRequirement*

**Project Model Usage Requirements:**

**Object types existing in R1.5.1:**

- ***IfcWall***  
Data
  - All available data
    - Location and type information (i.e., fire ratings, special construction types, etc.). This allows the designer to identify conflicts between walls and the duct system.
- ***IfcBeam***  
Data
  - Type, size and location of beams
    - This information is needed to prevent conflicts with air terminals, terminal boxes, duct, fittings, and equipment.

**Object types to add in R2.0:**

*See the IFC Model Impact section for class details.*

#### **5.3.1.1.6. Identify alternatives to design problems**

This step requires the designer to go back and redesign certain portions of the system. This may involve regenerating the schematic design documents and recalculating system component sizes. Note that this step may occur at any point in the process.

**Input Information:**

- *Pset\_CoordinationRequirement*

**Output Information:**

- *Pset\_CoordinationRequirement*

**Project Model Usage Requirements:**

**Object types existing in R1.5.1:**

- *None.*

**Object types to add in R2.0:**

*See the IFC Model Impact section for class details.*

#### **5.3.1.1.7. Pressure Loss Calculations**

Determine the system pressure losses based on the duct system that has been designed.

**Input Information:**

- *Pset\_DuctSystemDesignCriteria*
- *Pset\_DuctDesignCriteria*

**Output Information:**

- *Pset\_Fan, Pset\_PackagedACUnit*

**Project Model Usage Requirements:**

**Object types existing in R1.5.1:**

- *Pset\_Fan, Pset\_PackagedACUnit*  
Data
  - *All available data*
  - *Pressure loss performance requirements for the fan or packaged AC unit*

**Object types to add in R2.0:**

*See the IFC Model Impact section for class details.*

#### **5.3.1.1.8. Fan Selection**

Identify a fan that will appropriately meet the requirements of the duct system.

**Input Information:**

- *Pset\_DuctSystemDesignCriteria*
- *Pset\_HVACAirSideSystemDesignCriteria*

**Output Information:**

- *Pset\_CoordinationRequirement*
- *IfcEquipment*
- *Pset\_Fan, Pset\_PackagedACUnit*
- *Pset\_ElectricalCharacteristics*

### **Project Model Usage Requirements:**

#### **Object types existing in R1.5.1:**

- **Pset\_HVACAirSideSystemDesignCriteria**

*Data*

- All available data.
- This information is updated appropriately as the fan system is sized.

- **IfcEquipment**

*Data*

- All available data.
- The information related to the weight and maintenance requirements is updated based on the fan selection.

- **Pset\_Fan, Pset\_PackagedACUnit**

*Data*

- All available data.
- The information related to the fan or packaged unit is updated with the new performance data from the fan selection.

- **Pset\_ElectricalCharacteristics**

*Data*

- All available data.
- The electrical requirements for the selected fan or packaged AC unit.

#### **Object types to add in R2.0:**

*See the IFC Model Impact section for class details.*

### **5.3.1.1.9. Generate Final System Representation**

This step involves preparing drawings and specifications which will be used as contract documents for bid and construction. These documents complete the design phase of the system.

#### **Input Information:**

- *Pset\_CoordinationRequirement*

#### **Output Information:**

- *Pset\_AirTerminal*
- *Pset\_TerminalBox*
- *Pset\_DuctFitting*
- *Pset\_DuctSegment*
- *IfcDamper*
- *IfcPathwayElement*
- *IfcControlElement*
- *IfcActuator*

### **Project Model Usage Requirements:**

#### **Object types existing in R1.5.1:**

- None.

#### **Object types to add in R2.0:**

*See the IFC Model Impact section for class details.*

### 5.3.1.2. IFC Model Impact

#### Usage/Extensions to R1.5.1 object types and property sets

- **Pset\_AirHandlingUnit**  
Data
  - To be determined
- **Pset\_HVACAirSideSystemInformation**  
Data
  - Need to coordinate with duct system design
- **Pset\_Fan**  
Data
  - To be determined
- **Pset\_Insulation**  
Data
  - Need to coordinate with duct and pipe insulation
- **IfcEquipment**  
Data
  - Need to reconcile relationship with *IfcPathwayElement* to allow for connectivity

#### New object types and property sets required in R2.0

- **IfcPathwayElement**

*IfcPathwayElement* generically connects together parts of a networked system. A networked system can be used to represent a system used to transport fluids, such as a duct or piping system. It can also be used for many other system representations, such as electrical distribution systems, computer networks, etc. Note that some types of pathway elements are part of more than one networked system. For example, a fan powered terminal box participates as part of a duct system as well as an electrical system.

*IfcPathwayElement* is a subtype of *IfcBuildingElement*. This class provides a reference to a *PathwayElementType* type definition which contains the attributes required for the system being designed. In this manner, a pathway element can have properties of a channel (one input and one output), a junction (many inputs and one output) or a splitter (one input and many outputs).

NOTE to Modeling Team: The following paragraph is reflective of IFC 1.0 constructs and does not incorporate the *IfcNetwork* constructs planned for the IFC Release 2.0 Core Model.

The *I\_PhysicalConnections* interface on *IfcElement* (from which *IfcBuildingElement* derives) contains the *ConnectionPoints* and *PointConnections* attributes which can be used for collecting physical or logical connections for both nodes and edges. *ConnectionPoints* can be used to collect pure logical connection points. *PointConnections*, combined with the information in a connection type property set (i.e., *Pset\_RectangularDuctConnection*, *Pset\_RoundDuctConnection*, *Pset\_OvalDuctConnection*) attached to the referenced *IfcPointConnector*, provide the required information for the type, size and location of physical connections.

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_RectangularDuctConnection**

This property set provides size information about a rectangular duct connection.

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_RoundDuctConnection**

*This property set provides size information about a round duct connection.*

**Data**

- See Object Type Definition Tables for details

- **Pset\_OvalDuctConnection**

*This property set provides size information about an oval duct connection.*

**Data**

- See Object Type Definition Tables for details

- **Pset\_CoordinationRequirement**

*This property set provides a placeholder for interoperable coordination requirements between different disciplines.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_AirTerminal**

*This property set will be used by an IfcPathwayElement object for defining Air Terminals.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_TerminalBox**

*This property set will be used by an IfcPathwayElement object to define Terminal Boxes.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_DuctFitting**

*This property set will be used by an IfcPathwayElement object to define duct fittings.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_DuctSegment**

*This property set will be used by an IfcPathwayElement object to define duct segments.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_DuctDesignCriteria:**

*This property set will typically be used in conjunction with Pset\_Fluid and Pset\_Insulation.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_DuctSystemDesignCriteria:**

*This property set will typically be used in conjunction with Pset\_Fluid and Pset\_Insulation.*

**Data**

- See the Object Type Definition Tables section for details.

- **IfcDamper:**

*This object class is a subtype of IfcPathwayElement and is used to define dampers.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_FireDamper:**

*This property set adds information to an IfcDamper object that is specific to fire dampers.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_SmokeDamper:**

*This property set adds information to an IfcDamper object that is specific to smoke dampers.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_FireSmokeDamper:**

*This property set adds information to an IfcDamper object that is specific to combination fire and smoke dampers.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_BackdraftDamper:**

*This property set adds information to an IfcDamper object that is specific to backdraft dampers.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_ControlDamper:**

*This property set adds information to an IfcDamper object that is specific to control dampers.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_Louver:**

*This property set adds information to an IfcDamper object that is specific to louvers.*

**Data**

- See the Object Type Definition Tables section for details.

- **IfcControlElement**

*This class is used to identify control components that are typically a part of any HVAC duct or piping system. The information contained within this class and its related property sets attempt to remain consistent with the BACnet Standard. This allows implementation of the IFC control elements to be compatible with the BACnet Standard as desired.*

*BACnet is a very extensive, but not exhaustive specification aimed at providing an interoperable method of generalized Building Control Systems from different vendors. It does provide an object specification, some of which has been integrated into IFC.*

*To determine the suitability of the BACnet object attributes required for inclusion in IFC, the BACnet object attributes were categorized into three major groups by the IAI Building Systems domain committee:*

- *External -- Provided by the consultant, design engineer or owner. These are the attributes to be included in the IFC specifications.*
- *Vendor -- Specifics that depend upon the product offering of the control vendor and the vendor's engineering efforts*
- *Run-Time -- The actual values of the building and systems when under control (values altered by operating staff are considered run-time, not externally specified)*

*The reader is reminded that BACnet is a communication protocol. It is not a database for a building control system, but rather formalized method of communication.*

*In order to provide IFC interoperability, the externally specified attributes of the BACnet Objects should be standardized so that design engineers can communicate their requirements to control vendors. All other uses and definitions of the BACnet attributes are defined in the BACnet Specification (ANSI/ASHRAE 135-95).*

**Data**

- See the Object Type Definition Tables section for details.

- **IfcActuator**

*This object class subtypes from IfcControlElement to define the various types of actuators.*

**Data**

- See the Object Type Definition Tables section for details.



- **Pset\_LinearActuator**

*This property set adds information to an IfcActuator object that is specific to linear actuators.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_RotationalActuator**

*This property set adds information to an IfcActuator object that is specific to linear actuators.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_ElectricActuator**

*This property set adds information to an IfcActuator object that is specific to electric actuators.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_PneumaticActuator**

*This property set adds information to an IfcActuator object that is specific to pneumatic actuators.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_HydraulicActuator**

*This property set adds information to an IfcActuator object that is specific to hydraulic actuators.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_HandOperatedActuator**

*This property set adds information to an IfcActuator object that is specific to hand operated actuators.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_Sensor**

*This property set adds information to an IfcControlElement object that is specific to sensors.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_Controller**

*This property set adds information to an IfcControlElement object that is specific to sensors.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_ControlElementAnalogInput**

*This property set adds information to an IfcControlElement object that has an analog input.  
This is a BACnet compatible property set.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_ControlElementAnalogOutput**

*This property set adds information to an IfcControlElement object that has an analog output.  
This is a BACnet compatible property set.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_ControlElementBinaryInput**

*This property set adds information to an IfcControlElement object that has a binary input. This is a BACnet compatible property set.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_ControlElementBinaryOutput**

*This property set adds information to an IfcControlElement object that has a binary output. This is a BACnet compatible property set.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_ControlElementMultiStateInput**

*This property set adds information to an IfcControlElement object that has a multi-state input. This is a BACnet compatible property set.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_ControlElementMultiStateOutput**

*This property set adds information to an IfcControlElement object that has a multi-state output. This is a BACnet compatible property set.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_ControlElementEventEnrollment**

*This property set adds information to an IfcControlElement object regarding the events that the object participates with. This is a BACnet compatible property set.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_ControlElementLoop**

*This property set adds information to an IfcControlElement object about the control loop that the object participates with. This is a BACnet compatible property set.*

**Data**

- See the Object Type Definition Tables section for details.

### 5.3.1.3. RoadMap Issues

#### Interoperability Value

**Disciplines/Applications from which information is needed:**

- Architectural
- Structural
- HVAC (Piping plans, thermal loads)
- Plumbing/Fire Protection
- Electrical
- Lighting

**Disciplines/Applications to which information will be supplied:**

- Electrical
- HVAC
- Plumbing/Fire Protection
- Structural

### ***Value of software supporting this process***

In this section, other domain teams will rank the value of software which supports this process, based on IFC.

- *Architecture (7)*
- *Building Services (8)*
- *HVAC (9)*
- *FM (6)*
- *CM/Cost (8)*

### ***Sponsor Software Companies***

The following organizations that develop software used by AEC end users have shown interest in developing applications which implement the process:

- *APEC*
- *Carrier*
- *Greenheck*
- *Honeywell*
- *Landis-Staefa*

#### ***5.3.1.4. Issues identified in reviews***

##### ***No reviews recorded***

###### **Issues**

###### **Proposed resolution**

- No issues recorded
  - No resolutions recorded

#### **5.3.2. Process: HVAC Piping System Design**

HVAC Piping System Design supports the design and representation of piping systems. These processes are typically performed by engineers and design-build contractors during the design phase of a building or project, prior to construction. The process culminates with a set of drawings which can be bid upon and constructed.

This section defines the specific requirements for HVAC Piping System Design based on the generalized Building Services System Design described above.

##### ***5.3.2.1. Information Analysis by Task***

Please see the process overview description, process diagram and detailed process definition for this process in the "AEC+FM Industry Process Definitions" section of this document.

###### **5.3.2.1.1. Select and Locate System Components**

This step involves selecting and locating the air terminals, boxes (if included in the design), and fans that compose the HVAC duct system.

###### ***Input Information:***

- *Floor plans*
- *Ceiling grid plans*
- *Reflected ceiling plans*
- *Lighting plans*
- *Structural plans*

- *Sprinkler plans*
- *Piping plans*
- *Smoke detector plans*
- *Speaker plans*

**Output Information:**

- *Pset\_AirTerminal*
- *Pset\_CoordinationRequirement*
- *Pset\_TerminalBox*
- *IfcPathwayElement*
- *IfcEquipment*

**Project Model Usage Requirements:**

**Object types existing in R1.5.1:**

- **IfcWall**

**Data**

- All available data
  - Location and type information (i.e., fire ratings, special construction types, etc.). This allows the designer to identify the potential locations for air terminals, boxes and fans

- **IfcSpace**

**Data**

- Programme information
  - Information specific to the intended function of the space, which is used to determine the number and type of air terminals to be installed.

- **IfcCeiling**

**Data**

- Ceiling Type information
  - Information needed to determine the type and location of air terminals to be installed.
  - Information needed to determine clearances in interstitial spaces.

- **IfcBeam**

**Data**

- Type, size and location of beams
  - This information is needed to prevent conflicts with air terminals and terminal boxes.

- **IfcFluidMover**

**Data**

- All available data.
  - This information coupled with the *Pset\_Fan* or *Pset\_AirHandlingUnit* property sets are used to locate and initially specify the fan.

**Object types to add in R2.0:**

*See the IFC Model Impact section for class details.*

### 5.3.2.1.2. Connect Components with Ducts and Fittings

This step involves using engineering judgment to connect the air terminals, boxes, and fans with ducts and fittings. This information is then used for preparing drawings or specifications which will schematically represent the system under design. These schematics are then used to begin coordination with other disciplines which are impacted by the system.

**Input Information:**

- *Floor plans*
- *Structural plans*
- *Pset\_CoordinationRequirement*

**Output Information:**

- *Pset\_DuctFitting*
- *Pset\_DuctSegment*
- *IfcPathwayElement*

**Project Model Usage Requirements:**

**Object types existing in R1.5.1:**

- **IfcWall**

**Data**

- All available data
  - Location and type information (i.e., fire ratings, special construction types, etc.). This allows the designer to locate ducts and fittings appropriately.

- **IfcCeiling**

**Data**

- Ceiling Type information
  - Information needed to determine where duct and fittings can be located.

- **IfcBeam**

**Data**

- Type, size and location of beams
  - This information is needed to prevent conflicts between beams and ducts and fittings.

**Object types to add in R2.0:**

*See the IFC Model Impact section for class details.*

### 5.3.2.1.3. Sizing the Duct and Fittings

The sizes of the duct and fittings are calculated.

**Input Information:**

- *Pset\_HVACSpaceElementInformation*
- *Pset\_DuctSystemDesignCriteria*
- *Pset\_DuctDesignCriteria*

**Output Information:**

- *Pset\_CoordinationRequirement*
- *Pset\_RectangularDuctConnection*
- *Pset\_RoundDuctConnection*
- *Pset\_OvalDuctConnection*

**Project Model Usage Requirements:**

**Object types existing in R1.5.1:**

- **Pset\_HVACSpaceElementInformation**

**Data**

- MaximumAirflow and MinimumAirflow values calculated from the room or space load calculations.

**Object types to add in R2.0:**

*See the IFC Model Impact section for class details.*

### 5.3.2.1.4. Locate Other System Components

Identify and locate other system components required for the duct system.

**Input Information:**

- . *Pset\_DuctSystemDesignCriteria*
- . *Pset\_DuctDesignCriteria*
- . *IfcWall*

**Output Information:**

- . *Pset\_CoordinationRequirement*
- . *IfcDamper*
- . *IfcPathwayElement*
- . *IfcControlElement*
- . *IfcActuator*

**Project Model Usage Requirements:**

**Object types existing in R1.5.1:**

- ***IfcWall***

**Data**

- All available data
- Location and type information (i.e., fire ratings, special construction types, etc.). This allows the designer to identify locations for system components such as fire dampers.

**Object types to add in R2.0:**

See the IFC Model Impact section for class details.

### 5.3.2.1.5. Interference Check

Identify any interferences with other trades.

**Input Information:**

- . *Plumbing/Sprinkler plans*
- . *Piping plans*
- . *Floor plans*
- . *Ceiling grid plans*
- . *Reflected ceiling plans*
- . *Lighting plans*
- . *Power plans*
- . *Structural plans*
- . *Pset\_CoordinationRequirement*

**Output Information:**

- . *Pset\_CoordinationRequirement*

**Project Model Usage Requirements:**

**Object types existing in R1.5.1:**

- ***IfcWall***

**Data**

- All available data
- Location and type information (i.e., fire ratings, special construction types, etc.). This allows the designer to identify conflicts between walls and the duct system.

- ***IfcBeam***

**Data**

- Type, size and location of beams
- This information is needed to prevent conflicts with air terminals, terminal boxes, duct, fittings, and equipment.

**Object types to add in R2.0:**

*See the IFC Model Impact section for class details.*

#### **5.3.2.1.6. Identify alternatives to design problems**

This step requires the designer to go back and redesign certain portions of the system. This may involve regenerating the schematic design documents and recalculating system component sizes. Note that this step may occur at any point in the process.

**Input Information:**

- *Pset\_CoordinationRequirement*

**Output Information:**

- *Pset\_CoordinationRequirement*

**Project Model Usage Requirements:**

**Object types existing in R1.5.1:**

- *None.*

**Object types to add in R2.0:**

*See the IFC Model Impact section for class details.*

#### **5.3.2.1.7. Pressure Loss Calculations**

Determine the system pressure losses based on the duct system that has been designed.

**Input Information:**

- *Pset\_DuctSystemDesignCriteria*
- *Pset\_DuctDesignCriteria*

**Output Information:**

- *Pset\_Fan, Pset\_PackagedACUnit*

**Project Model Usage Requirements:**

**Object types existing in R1.5.1:**

- *Pset\_Fan, Pset\_PackagedACUnit*  
**Data**
  - *All available data*
  - *Pressure loss performance requirements for the fan or packaged AC unit*

**Object types to add in R2.0:**

*See the IFC Model Impact section for class details.*

#### **5.3.2.1.8. Fan Selection**

Identify a fan that will appropriately meet the requirements of the duct system.

**Input Information:**

- *Pset\_DuctSystemDesignCriteria*
- *Pset\_HVACAirSideSystemDesignCriteria*

**Output Information:**

- *Pset\_CoordinationRequirement*
- *IfcEquipment*
- *Pset\_Fan, Pset\_PackagedACUnit*
- *Pset\_ElectricalCharacteristics*

### **Project Model Usage Requirements:**

#### **Object types existing in R1.5.1:**

- **Pset\_HVACAirSideSystemDesignCriteria**

**Data**

- All available data.
- This information is updated appropriately as the fan system is sized.

- **IfcEquipment**

**Data**

- All available data.
- The information related to the weight and maintenance requirements is updated based on the fan selection.

- **Pset\_Fan, Pset\_PackagedACUnit**

**Data**

- All available data.
- The information related to the fan or packaged unit is updated with the new performance data from the fan selection.

- **Pset\_ElectricalCharacteristics**

**Data**

- All available data.
- The electrical requirements for the selected fan or packaged AC unit.

#### **Object types to add in R2.0:**

*See the IFC Model Impact section for class details.*

### **5.3.2.1.9. Generate Final System Representation**

This step involves preparing drawings and specifications which will be used as contract documents for bid and construction. These documents complete the design phase of the system.

#### **Input Information:**

- **Pset\_CoordinationRequirement**

#### **Output Information:**

- **Pset\_AirTerminal**
- **Pset\_TerminalBox**
- **Pset\_DuctFitting**
- **Pset\_DuctSegment**
- **IfcDamper**
- **IfcPathwayElement**
- **IfcControlElement**
- **IfcActuator**

### **Project Model Usage Requirements:**

#### **Object types existing in R1.5.1:**

- None.

#### **Object types to add in R2.0:**

*See the IFC Model Impact section for class details.*



### 5.3.2.2. IFC Model Impact

#### Usage/Extensions to R1.5.1 object types and property sets

- **Pset\_AirHandlingUnit**  
*Data*
  - To be determined
- **Pset\_HVACAirSideSystemInformation**  
*Data*
  - Need to coordinate with duct system design
- **Pset\_Fan**  
*Data*
  - To be determined
- **Pset\_Insulation**  
*Data*
  - Need to coordinate with duct and pipe insulation
- **IfcEquipment**  
*Data*
  - Need to reconcile relationship with *IfcPathwayElement* to allow for connectivity

#### New object types and property sets required in IFC R2.0

- **IfcPathwayElement**

*IfcPathwayElement* generically connects together parts of a networked system. A networked system can be used to represent a system used to transport fluids, such as a duct or piping system. It can also be used for many other system representations, such as electrical distribution systems, computer networks, etc. Note that some types of pathway elements are part of more than one networked system. For example, a fan powered terminal box participates as part of a duct system as well as an electrical system.

*IfcPathwayElement* is a subtype of *IfcBuildingElement*. This class provides a reference to a *PathwayElementType* type definition which contains the attributes required for the system being designed. In this manner, a pathway element can have properties of a channel (one input and one output), a junction (many inputs and one output) or a splitter (one input and many outputs).

NOTE to Modeling Team: The following paragraph is reflective of IFC 1.0 constructs and does not incorporate the *IfcNetwork* constructs planned for the IFC Release 2.0 Core Model.

The *I\_PhysicalConnections* interface on *IfcElement* (from which *IfcBuildingElement* derives) contains the *ConnectionPoints* and *PointConnections* attributes which can be used for collecting physical or logical connections for both nodes and edges. *ConnectionPoints* can be used to collect pure logical connection points. *PointConnections*, combined with the information in a connection type property set (i.e., *Pset\_RectangularDuctConnection*, *Pset\_RoundDuctConnection*, *Pset\_OvalDuctConnection*) attached to the referenced *IfcPointConnector*, provide the required information for the type, size and location of physical connections.

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_RectangularDuctConnection**

This property set provides size information about a rectangular duct connection.

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_RoundDuctConnection**

*This property set provides size information about a round duct connection.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_OvalDuctConnection**

*This property set provides size information about an oval duct connection.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_CoordinationRequirement**

*This property set provides a placeholder for interoperable coordination requirements between different disciplines.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_AirTerminal**

*This property set will be used by an IfcPathwayElement object for defining Air Terminals.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_TerminalBox**

*This property set will be used by an IfcPathwayElement object to define Terminal Boxes.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_DuctFitting**

*This property set will be used by an IfcPathwayElement object to define duct fittings.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_DuctSegment**

*This property set will be used by an IfcPathwayElement object to define duct segments.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_DuctDesignCriteria:**

*This property set will typically be used in conjunction with Pset\_Fluid and Pset\_Insulation.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_DuctSystemDesignCriteria:**

*This property set will typically be used in conjunction with Pset\_Fluid and Pset\_Insulation.*

**Data**

- See the Object Type Definition Tables section for details.

- **IfcDamper:**

*This object class is a subtype of IfcPathwayElement and is used to define dampers.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_FireDamper:**

*This property set adds information to an IfcDamper object that is specific to fire dampers.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_SmokeDamper:**

*This property set adds information to an IfcDamper object that is specific to smoke dampers.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_FireSmokeDamper:**

*This property set adds information to an IfcDamper object that is specific to combination fire and smoke dampers.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_BackdraftDamper:**

*This property set adds information to an IfcDamper object that is specific to backdraft dampers.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_ControlDamper:**

*This property set adds information to an IfcDamper object that is specific to control dampers.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_Louver:**

*This property set adds information to an IfcDamper object that is specific to louvers.*

**Data**

- See the Object Type Definition Tables section for details.

- **IfcControlElement**

*This class is used to identify control components that are typically a part of any HVAC duct or piping system. The information contained within this class and its related property sets attempt to remain consistent with the BACnet Standard. This allows implementation of the IFC control elements to be compatible with the BACnet Standard as desired.*

*BACnet is a very extensive, but not exhaustive specification aimed at providing an interoperable method of generalized Building Control Systems from different vendors. It does provide an object specification, some of which has been integrated into IFC.*

*To determine the suitability of the BACnet object attributes required for inclusion in IFC, the BACnet object attributes were categorized into three major groups by the IAI Building Systems domain committee:*

*External -- Provided by the consultant, design engineer or owner. These are the attributes to be included in the IFC specifications.*

*Vendor -- Specifics that depend upon the product offering of the control vendor and the vendor's engineering efforts*

*Run-Time -- The actual values of the building and systems when under control (values altered by operating staff are considered run-time, not externally specified)*

*The reader is reminded that BACnet is a communication protocol. It is not a database for a building control system, but rather formalized method of communication.*

*In order to provide IFC interoperability, the externally specified attributes of the BACnet Objects should be standardized so that design engineers can communicate their requirements to control vendors. All other uses and definitions of the BACnet attributes are defined in the BACnet Specification (ANSI/ASHRAE 135-95).*

**Data**

- See the Object Type Definition Tables section for details.

- **IfcActuator**

*This object class subtypes from IfcControlElement to define the various types of actuators.*

**Data**

- See the *Object Type Definition Tables* section for details.

- **Pset\_LinearActuator**

*This property set adds information to an IfcActuator object that is specific to linear actuators.*

**Data**

- See the *Object Type Definition Tables* section for details.

- **Pset\_RotationalActuator**

*This property set adds information to an IfcActuator object that is specific to linear actuators.*

**Data**

- See the *Object Type Definition Tables* section for details.

- **Pset\_ElectricActuator**

*This property set adds information to an IfcActuator object that is specific to electric actuators.*

**Data**

- See the *Object Type Definition Tables* section for details.

- **Pset\_PneumaticActuator**

*This property set adds information to an IfcActuator object that is specific to pneumatic actuators.*

**Data**

- See the *Object Type Definition Tables* section for details.

- **Pset\_HydraulicActuator**

*This property set adds information to an IfcActuator object that is specific to hydraulic actuators.*

**Data**

- See the *Object Type Definition Tables* section for details.

- **Pset\_HandOperatedActuator**

*This property set adds information to an IfcActuator object that is specific to hand operated actuators.*

**Data**

- See the *Object Type Definition Tables* section for details.

- **Pset\_Sensor**

*This property set adds information to an IfcControlElement object that is specific to sensors.*

**Data**

- See the *Object Type Definition Tables* section for details.

- **Pset\_Controller**

*This property set adds information to an IfcControlElement object that is specific to sensors.*

**Data**

- See the *Object Type Definition Tables* section for details.

- **Pset\_ControlElementAnalogInput**

*This property set adds information to an IfcControlElement object that has an analog input.  
This is a BACnet compatible property set.*

**Data**

- See the *Object Type Definition Tables* section for details.

- **Pset\_ControlElementAnalogOutput**

*This property set adds information to an IfcControlElement object that has an analog output.  
This is a BACnet compatible property set.*

**Data**

- See the *Object Type Definition Tables* section for details.

- **Pset\_ControlElementBinaryInput**

*This property set adds information to an IfcControlElement object that has a binary input.  
This is a BACnet compatible property set.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_ControlElementBinaryOutput**

*This property set adds information to an IfcControlElement object that has a binary output.  
This is a BACnet compatible property set.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_ControlElementMultiStateInput**

*This property set adds information to an IfcControlElement object that has a multi-state input.  
This is a BACnet compatible property set.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_ControlElementMultiStateOutput**

*This property set adds information to an IfcControlElement object that has a multi-state output. This is a BACnet compatible property set.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_ControlElementEventEnrollment**

*This property set adds information to an IfcControlElement object regarding the events that the object participates with. This is a BACnet compatible property set.*

**Data**

- See the Object Type Definition Tables section for details.

- **Pset\_ControlElementLoop**

*This property set adds information to an IfcControlElement object about the control loop that the object participates with. This is a BACnet compatible property set.*

**Data**

- See the Object Type Definition Tables section for details.

### 5.3.2.3. RoadMap Issues

#### Interoperability Value

**Disciplines/Applications from which information is needed:**

- Architectural
- Structural
- HVAC
- Plumbing/Fire Protection
- Electrical

**Disciplines/Applications to which information will be supplied:**

- Electrical
- HVAC
- Plumbing/Fire Protection
- Structural

### ***Value of software supporting this process***

In this section, other domain teams will rank the value of software which supports this process, based on IFC.

- *Architecture (7)*
- *Building Services (8)*
- *HVAC (9)*
- *FM (6)*
- *CM/Cost (8)*

### ***Sponsor Software Companies***

The following organizations that develop software used by AEC end users have shown interest in developing applications which implement the process:

- *APEC*
- *Carrier*
- *Greenheck*
- *Honeywell*
- *Landis-Staefa*

#### ***5.3.2.4. Issues identified in reviews***

##### ***No reviews recorded***

###### **Issues**

###### **Proposed resolution**

- No issues recorded
  - No resolutions recorded

#### ***5.4. [BS-3] Pathway Design and Coordination***

##### **5.4.1. Process: Pathway Design and Coordination**

The design of pathways contains the draft layout, the coordination and the representation of mechanical and electrical system-pathways to be installed.

This design process is carried out after the first coordination with the architect and structural engineers, and includes load estimates, energy and systems definitions required for a building.

The process ends with drawings containing the coordinated pathways for the mechanical and electrical installations (i.e. heating, cooling, air-conditioning, plumbing, fire-protection and electrical power) within a building.

Based on the building model and the conditions (program) defined by the customer, an initial estimate of required energy, technical equipment and systems is defined. The process of designing the pathway starts by defining the required spatial extents for technical equipment, piping, ducting and electrical routes.

A rough building layout by the architect will frequently be available showing the suggested locations for plant rooms and risers.

Considering these parameters, the engineer defines the necessary locations for plant areas and suggests the routing of the main pathways.

The required plant area and main pathways are represented in the M & E drawings.

This draft is presented to the architect/customer with details on space requirements (sections). Thereafter, a review of the suggested design solution will take place, taking into account the structure, the initial and future investment, user requirements, operating expenses and the flexibility achieved.

Parameters from the building model, the definition of systems and the routes of each media type can be combined to define the pathway. Air ducts, including equipment (fire dampers, VAV-boxes, etc.) are combined to form a ventilation pathway. Pipes for heating, cooling or plumbing are combined to form a media pathway. Electrical trays are combined to form an electrical pathway. Each pathway should allow variables for necessary insulation or fire proofing, as well as variables for necessary access for installation and maintenance. The optimization of the pathway itself can be done by varying the distance and position of ducts, pipes or trays. Every pathway must be coordinated within the architectural and structural restraints, as well as with each other.

A final definition of the spatial requirements for technical equipment and media distribution, defines the location of the pathway. The translation of the pathway into geometrical forms is carried out. These drawings serve as a guideline for the ongoing building services design.

The definitions of the structural systems (flat slab, concrete or steel construction, beams, etc.) reflect the location of the plant areas, risers and pathways. Collision detection with walls, slabs, binding beams etc. should be made and openings have to be defined.

#### **5.4.1.1. Information Analysis by Task**

Please see the process overview description, process diagram and detailed process definition for this process in the "AEC+FM Industry Process Definitions" section of this document.

##### **5.4.1.1.1. Task A - Defining required space for stations**

This step contains the dimensioning of main components for different systems, inquiry of the approximate space requirement and corresponding placing of the technical areas in the building model. See also - description in the Process definition section above.

**Input Information:**

- . *system design criteria*
- . *building model from architect*
- . *load calculations and media/system type*
- . *preliminary systems definition*
- . *other requests like accessibility, flexibility, installation, maintenance*
- . *coordination with client*

**Output Information:**

- . *needed plant area and room for the central supply*
- . *placing of the central supply in the building*

##### **5.4.1.1.2. Task B - Defining the required space for pathways**

This step contains the dimensioning of the energy and media supply as well as the specification of *pathway*. See also - description in the Process definition section above.

**Input Information:**

- . *system design criteria*
- . *building model from architect*
- . *loads and required medium*
- . *appropriate system*
- . *other items like accessibility, insulation, fire proofing, installation*

**Output Information:**

- . *required area or volume of pathway*

#### **5.4.1.1.3. Task C - Geometrical representation of stations and pathways**

This step contains the geometrical representation of the defined centralized media supply and pathway. See also - description in the Process definition section above.

**Input Information:**

- *areas for technical plant equipment*
- *placement of plant equipment*
- *space requirement of pathway*

**Output Information:**

- *building model with geometrical representation of technical plant equipment and pathways.*

#### **5.4.1.1.4. Task D - Interference check**

Collision detection with other technical services and the building model . See also - description in the Process definition section above.

**Input Information:**

- *building model with geometrical representation of technical plant equipment and pathways*
- *coordination requirement*

**Output Information:**

- *coordination requirement*

#### **5.4.1.1.5. Task E - Identify alternatives to resolve the collisions**

This step requires the designer to go back and redesign certain portions of the system. This may involve regenerating the schematic design documents and recalculating system component. Note that this step may occur at any point in the process. See also - description in the Process definition section above.

**Input Information:**

- *coordination requirement*

**Output Information:**

- *geometrical representation of pathway*

#### **5.4.1.1.6. Task F - Itemization of Pathway**

This step contains the detailed output of a pathway. By consideration of departures and branching as well as the location and distance of each pipe or duct the cross-sectional dimension of the pathway is brought into line with the respective conditions and will be optimized. See also - description in the Process definition section above.

**Input Information:**

- *coordination requirement*
- *thermal load calculations*
- *building model from architect*

**Output Information:**

- *geometrical representation of pathway*
- *coordination requirement*

#### **5.4.1.1.7. Task G - Coordination of branches**

This step contains the coordination of different trades within the design of pathway at branchings as well as the coordination with structural conditions like binding beams etc. See also - description in the Process definition section above.

**Input Information:**

- *geometrical representation of pathway*
- *coordination requirement*



- *building model from architect*

**Output Information:**

- *coordinated allocation scheme of pathway*

#### **5.4.1.1.8. Task H - Interference check**

Collision detection with other disciplines and building model . See also - description in the Process definition section above.

**Input Information:**

- *building model geometrical representation of technical facilities and pathways*
- *cost estimating and operating expanses for HVAC-Systems*
- *building model*
- *coordination requirement*

**Output Information:**

- *coordination requirement*

#### **5.4.1.1.9. Task I - Determination of openings**

This step contains the specification of openings. See also - description in the Process definition section above.

**Input Information:**

- *coordination requirement*
- *geometrical representation of pathway*

**Output Information:**

- *coordination requirement*
- *size and placement*

#### **5.4.1.1.10. Task J - Generate final system**

This step contains the design of drawings or specifications which are used as a basis for further systems design. See also - description in the Process definition section above.

**Input Information:**

- *coordination required*

**Output Information:**

- *see definitions of objects and attributes of*
  - *AR-1 Completion of Architectural Model*
  - *BS-1 HVAC System Design*
  - *BS-2 Power and Lighting Systems Design*
  - *ST-1 Steel Frame Structures*
  - *ST-2 Reinforced Concrete Structures*

### **5.4.1.2. IFC Model Impact**

This section summarizes the model requirements from all the process tasks analyzed above into two groups  
Extensions to R1.5.1 model object types and proposed new object types for R2.0.

#### **Extensions to existing R1.5.1 Object Types**

*The coordination of the pathways deals with existing definitions of objects and attributes in the following projects :*

- *AR-1 Completion of Architectural Model*
- *BS-1 HVAC System Design*
- *BS-2 Power and Lighting Systems Design*
- *ST-1 Steel Frame Structures*

## *ST-2 Reinforced Concrete Structures*

*The basic information as well as the results of the coordination take effect in the processes listed above.  
For further information please refer to these documents.*

### **New object types required in IFC R2.0**

- *None defined*

### **5.4.1.3. RoadMap Issues**

#### **Interoperability Value**

##### ***Disciplines/Applications from which information is needed:***

- *Architectural*
- *Structural*
- *HVAC*
- *Plumbing / Fire Protection*
- *Electrical*
- *Lighting*

##### ***Disciplines/Applications to which information will be supplied:***

- *Architectural*
- *Structural*
- *HVAC*
- *Plumbing / Fire Protection*
- *Electrical*
- *Lighting*
- *Cost Estimating*
- *Facility Management*

#### **Value of software supporting this process**

In this section, other domain teams will rank the value of software which supports this process, based on IFC.

- *Note assessed*

#### **Sponsor Software Companies**

The following organizations that develop software used by AEC end users have shown interest in developing applications which implement the process:

- *RoCAD Informatik*
- *PHi-Tech*
- *GTS*
- *'ESS*
- *Ziegler Informatics*
- *RoCAD Informatik*
- *Triplan GmbH*
- *Pit-cup GmbH*

#### **5.4.1.4. Issues identified in reviews**

##### ***No reviews recorded***

###### **Issues**

###### **Proposed resolution**

- No issues recorded
- No resolutions recorded

### **5.5. [BS-4] HVAC Loads Calculation**

#### **5.5.1. Process: Building Heating and Cooling Load Calculation**

Load calculations serve as the basis for all design stages of the building services design. The results of the load calculations enable the designer to dimension the plant equipment and to determine the required space for plant room.

Load calculations are an official proofing method in Germany for example the proof for heat loss protection must be given in the course of a project), a mode for calculating the heating cooling load or for the yearly dynamic load simulation:

The process terminates in the complete calculations and the data exchange into the IFC model.

The chapter on hand defines the prerequisites for the computer-aided load calculation using of the thermal building model ( refer to VDI Guideline 6021, green paper).

After the completion of the building model with its geometric and physical building specifications by the architect, the data is to be extracted using the Aspect Model Load Calculations -- The Thermal Building Model. The thermal building model includes all architectural building components of a defined room, the attributes and the relationships of the components to each other. The thermal building model does not include any the description of the neighboring buildings (e.g. input for external shading).

The parameters like the room temperatures, required air changes, people or machine loads or other necessary data is submitted if known to the design team. If certain data is not known to the design team plausible data is assumed to provide preliminary answers.

The data exchange to the thermal building model does not require any exchange of the graphical data. The thermal building model is independent from the calculation method applied because it describes only the physical data.

After the exchange of data, the engineer checks data transmitted for completeness and possibly amends the data. The engineer has to input the boundary conditions as well as the meteorological data for the load calculation method.

The definition of zones, as a result of the assigned plant equipment, can be carried out by simply numbering them. All rooms of one level having common boundaries can be defined as one zone. Another form of zoning can be made by direct plant assignment. This method ensures, that considerations of energy as well as the simultaneity of use conditions within plants are considered.

As a result of load calculations, the physical qualities of building components may be changed and submitted to an optimization process. This is requested to the IFC-building model. After changing the corresponding data a further exchange of basic data is carried out and the process starts once more.

A revision phase is necessary if there is change to the plant assignment or there are variations to the boundary conditions within the process.

At the end of the process the results of the load calculations are provided for the IFC model for further processing. The definition of technical stations, pathway and their space requirements as well as the dimensioning of system components for building services design are based on these results.

### **5.5.1.1. Information Analysis by Task**

Please see the process overview description, process diagram and detailed process definition for this process in the "AEC+FM Industry Process Definitions" section of this document.

#### **5.5.1.1.1. Task A - IFC-Model take-over**

This step contains the import of extracted data from the building model like component geometry and component qualities. The construction of this physical data exchange format corresponds in the construction to a Physical-STEP file. See also - description in the Process definition section above.

**Input Information:**

- *All structural components of a room, referring to the aspect model of the Thermal Building Model*
- *All component parameters of the structural components (thermal storage)*
- *The relationship of structural components with each other or the outside area.*
- *Alternatively usage conditions*

**Output Information:**

- *Preparation of data*

#### **5.5.1.1.2. Task B - Specification of zones**

See description in the Process definition section above.

**Input Information:**

- *Building geometry*
- *Use conditions*
- *Plant assignment*

**Output Information:**

- *Preparation of data*

#### **5.5.1.1.3. Load calculations**

This step contains the execution of the load calculations. See also - description in the Process definition section above.

**Input Information:**

- *Data from the thermal building model*
- *Data preparation and specification of zones*
- *Use conditions*
- *Meteorological and thermal boundary conditions*

**Output Information:**

- *Room-, zones-( plants-) and building wise load calculations as*
- *Energy consumption proof*
- *Heating load*
- *Cooling load*
- *Annual energy requirement*
- *Building simulation*
- *Requirements on the building*

#### **5.5.1.1.4. Task D - Results into IFC-Model**

Exchanging the results of the load calculations to the IFC model. See also - description in the Process definition section above.

**Input Information:**

- *Detailed load calculations*

**Output Information:**

- *Results of calculation in abridged version*

### 5.5.1.1.5. Task E - Design modifications

This step contains the iterative event for the execution of all calculations by variation or change of the zones, usage requirements etc., according to optimization by changing parameters. See also - description in the Process definition section above.

**Input Information:**

- Change of zone division (plant assignment)
- Change of use conditions
- Change of boundary conditions

**Output Information:**

- Calculating variants
- New detailed load calculations
- New calculation results (requirements on the building model)

### 5.5.1.2. IFC Model Impact

This section summarizes the model requirements from all the process tasks analyzed above into two groups  
Extensions to R1.5.1 model object types and proposed new object types for R2.0.

#### Extensions to existing R1.5.1 Object Types

- attributes	comments	
• <b>IfcProject</b>		
- project short name (mark)	ProjectReference	IfcString
- project name		
- client		
- building service engineer		
- created by		
- revision number		
- comment		
• <b>IfcBuilding</b>		
- referenced project	ref(project)	
- building short name		
- building name		
- ground touching floor area	m2	
- ground-level - NNG	m NN	
- building height - h	m	
• <b>IfcBuildingStorey</b>		
- referenced building	ref(building)	
- storey short name		
- storey name		
- storey height (of floor construction)	m NN	

#### New object types required in IFC R2.0

- attributes	comments	
• <b>IfcFunctionalUnit (Zone)</b>		
- referenced building	ref(building)	
- name of functional unit		
• <b>IfcRoom</b>		
- referenced storey	ref(storey)	
- referenced functional unit	ref(functional unit)	
- room short name		
- room name		
- room temperature	oC	

- not full conditioned	Y/N
- storey height for room	m
- room height	m
- floor level (of floor finish)	m
- room perimeter	m
- room ground area	m2
- room volume	m3
• <b>Structural Components (general Type)</b>	
- structure component type number (index)	unique human interpretable number
- structure component type name	
- infiltration coefficient (Window)	m3/(mhPa2/3)
- airflow between layers	Y/N NT
• <b>Non Heat Storing Structural Components</b>	
- structural component number (index)	unique human interpretable number
- structural component type name	
- heat transmission coefficient	W/m2K
- radiation transmission coefficient - glazing	b-value
- grade of energy flow through the component	
- airflow through joints	m3/(hPa2/3)
• <b>Heat Storing Structural Components</b>	
- structural component name	
- heat conducting coefficient	W/mK
- thickness of the layer	m
- density of the layer	kg/m3
- lower value of diffusion coefficient	
- upper value of diffusion coefficient	
- specific heat capacity of the layer	kJ/kgK
• <b>Structural Components</b>	
- referenced type	ref(structural component type)
- structural component number	
- structural component orientation	
- from true north	in degree
- structural component slope	in degree
- structural component width	in m
- structural component height	in m
- structural component area	m2
• <b>Specific - for Non Heat Storing Structural Components</b>	
- referenced type	ref(structural component type for non heat storing components)
- number of horizontal joints	
- number of vertical joints	
- length of all joints	m
- radiation transmission coefficient of the outside sun protection devices	b- value
- radiation transmission coefficient of the indoor sun protection devices	b- value
- window projection length b	in m
- window projection length d	in m
- window projection length f	in m
- window projection length c	in m
- glass area fraction	
• <b>Room Usage Parameters</b>	
- referenced room	ref(room)
- usage unit	see below
- maximum value	see below
- usage grade	see below

- |                          |     |
|--------------------------|-----|
| - constant               | Y/N |
| - value until 1 o'clock  | %   |
| - and so on              | %   |
| - value until 24 o'clock | %   |

*comment: the usage units are described in the following table:*

- |                            |      |                                       |
|----------------------------|------|---------------------------------------|
| - usage unit               | mark | maximum value using grade             |
| - persons                  | P    | number activity (1,2,3)               |
| - lighting                 | B    | W room load factor                    |
| - machines                 | M    | W convective component                |
| - air supply               | ZU   | temperature in oC                     |
| - outside air              | AU   | mass flow in kg/s                     |
| - air extraction           | AB   | temperature of the incoming air in oC |
| - desired room temperature | RT   | temperature in oC                     |
| - air change rate          | LW   | 1/ h                                  |
| - heat supply or removal   | S    | W                                     |

- **Room to Structural Component - Relation**

- |                                   |                            |
|-----------------------------------|----------------------------|
| - referenced structural component | ref(structural component)  |
| - referenced room                 | ref(room)                  |
| - structural component index      | predefined list of indices |
| - orientation                     | front or rear              |

- **Additional information - FOR GERMANY ONLY**

- **GEB / WSV - building data according to DIN 4701 and WSchV (heat loss regulation)**

- |                                      |   |
|--------------------------------------|---|
| - referenced building                | ref(building)   |
| - building type                      | E = single house<br>R = multiple house<br>N = normal                |
| - situation                          |   |
| - F = free (windy)                   |   |
| - kind of building                   | N = normal inside temperature<br>G = lower level inside temperature |
| - building                           | as defined in WSchV   |
| - building between others            | Y/N   |
| - relation l/b from floor slab areas | as defined in DIN 4701  |

### 5.5.1.3. RoadMap Issues

#### Interoperability Value

##### **Disciplines/Applications from which information is needed:**

- Architectural

##### **Disciplines/Applications to which information will be supplied:**

- HVAC Pathway Design and Coordination
- HVAC Duct System Design
- HVAC Hydronic System Design
- Cost Estimating
- Structural
- Architectural

### ***Value of software supporting this process***

In this section, other domain teams will rank the value of software which supports this process, based on IFC. Values from 1-10, 1 being the lowest value, 10 being the highest value

- *Not assessed for this process*

### ***Sponsor Software Companies***

The following organizations that develop software used by AEC end users have shown interest in developing applications which implement the process:

- *None documented*

## ***5.5.1.4. Issues identified in reviews***

### ***No reviews recorded***

#### **Issues**

#### **Proposed resolution**

- No issues recorded
  - No resolutions recorded

## ***5.6. [CS-1] Code Checking - Energy Codes***

### **5.6.1. Process: Commercial and Residential Energy Code Compliance Checking**

#### ***5.6.1.1. Information Analysis by Task***

Please see the process overview description, process diagram and detailed process definition for this process in the "AEC+FM Industry Process Definitions" section of this document.

The processes illustrated above will be employed in code checking applications that address the following codes:

1. ASHRAE/IESNA Standard 90.1-1989 (Std 90.1)
2. Model Energy Code (MEC - all recent years)

The specific tasks illustrated in the diagrams above are all embedded within existing widely-distributed applications.

#### **5.6.1.1.1. All Tasks**

See description in the Process definition section above.

The inputs and outputs of the individual process tasks are not generally shared with other applications and are too numerous to be conveniently listed as separate task inputs and outputs using this format. For now, they have simply be summarized for the entire process below. Use of existing classes has not been noted, except where new attributes are required. Because the product model usage requirements are not broken down by task, they are identical to IFC Model Impact section, and the information is shown once there. [This information is also shown in an accompanying spreadsheet table.]

#### ***Input Information:***

- *Code Requirements*
- *Building Model*
- *Analysis Rules*

#### ***Output Information:***



- . *Object Constraints*
  - . *IfcPropertyConstraints*
  - . *IfcIntent*
- . *IfcAggregateControl*
- . *Code Violation Reports*
- . *Compliance Performance Results*
- . *Compliance Reports*

### 5.6.1.2. IFC Model Impact

This section summarizes the model requirements from all the process tasks analyzed above into two groups  
Extensions to R1.5.1 model object types and proposed new object types for R2.0.

#### Extensions to existing R1.5.1 Object Types

- ***IfcLayeredElement* (Interfaces added to core class)**

- Data**

- *ContinuousRvalue* - *Ifcreal*
      - Continuous R-value of assembly including air films, cladding, gypsum board and sheathing layers
    - *AssemblyUfactor* - *Ifcreal*
      - Overall assembly U-factor

- ***IfcMaterialLayerSet* (Interfaces added to resource schema)**

- Data**

- *ContinuousRvalue* - *Ifcreal*
      - Continuous R-value of assembly including air films, cladding, gypsum board and sheathing layers
    - *AssemblyUfactor* - *Ifcreal*
      - Overall assembly U-factor
    - *ParallelLayer1Material* - *Ref[IfcMaterialLayer]*
      - Reference to first part of parallel portion of layered assembly
    - *ParallelLayer2Material* - *Ref[IfcMaterialLayer]*
      - Reference to second part of parallel portion of layered assembly
    - *AspectRatioOfLayers* - *Ifcreal*
      - Ratio of layer 1 to layer 2

- ***IfcMaterialLayer* (Interfaces added to resource schema)**

- Data**

- *MaterialType* - *Ref[IfcMaterialTypeLibraryEntry]*
      - Type reference for homogenous material -- only used if not a material set
    - *MaterialSet* - *Ref[IfcMaterialLayerSet]*
      - Set of materials for material -- only used if not a homogenous material

- ***IfcWall* (Attribute added to core class)**

- Data**

- *AboveGrade* - *IfcReal*
      - Ratio of wall area that is above grade to total wall area

- ***IfcRoof* (This class to replace *IfcRoofSlab* because there are several other roof types)**

- Data**

- *GenericType* - *IfcRoofTypeEnum*
      - Predefined generic types are specified in an Enum. A Type definition is available for each generic type (as the required attributes differ). Use *TypeDefinition* corresponding to this generic type.
    - *RoofType* - *Ref[IfcTypeDefinition]*
      - Reference to a type definition that links to attributes defining the element (either shared by all instances or added to the *ExAttributeSets*). Specific *TypeDef* determined by the *Generic Type* above.

- **IfcFillingElement**

**Data**

- *FillingElementType* - [Ref [IfcFillingElementTypeLibraryEntry]
  - Predefined generic filling element types specified in a library
- *ProjectionFactor* - IfcReal
  - The ratio of shading projection depth to the height of window

**New object types required in IFC R2.0**

- **IfcPropertyConstraint (To establish a specific limit on an object or attribute of an object)**

**Data**

- *Source* - IfcOwnerId
  - Code/Standard reference
- *ReferenceObject* - IfcProjectObject/ IfcAttributeObject
  - Object / attribute reference for which the constraint is specified
- *Relation* - IfcNumericRelation
  - *ConstraintType* - IfcConstraintLevel
- *NoticeText* - IfcString

- **IfcIntent (A collection of attributes representing design intent)**

**Data**

- *Source* - IfcOwnerId
  - Code/Standard reference ??
- *Description* - IfcString
  - Description of the code requirement

- **IfcAggregateControl (A collection of attributes representing the logical relationships between design intent and constraint)**

**Data**

- *Source* - IfcOwnerId
  - Code/Standard reference
- *Operation* - IfcLogicalOperation
  - Logical relationship between intent and constraint

- **IfcBuildingEnvelope**

**Data**

- *AggregateOf* - Set[0:N] Ref[IfcLayeredElement]
  - Contains references to all instances of layered elements which form the envelope
- *OccupancyType* - IfcEnvelopeOccupancyTypeEnum
  - Envelope occupancy type according to the Standard
- *InternalLoadDensity* - IfcReal
  - Total internal load based on the occupancy
- *ThermalLoad* - IfcReal
  - Envelope load based on the proposed design

- **IfcSkylight**

**Data**

- *GenericType* - IfcSkylightTypeEnum
  - Predefined generic types are specified in an Enum. A Type definition is available for each generic type (as the required attributes differ). Use TypeDefinition corresponding to this generic type.
- *SkylightType* - Ref[IfcTypeDefinition]
  - Reference to a type definition which links to attributes defining the element (either shared by all instances or added to the ExAttributeSets). Specific TypeDef determined by the GenericType above.

- **IfcLightingElement (An aggregation class containing all the lighting fixtures)**

**Data**

- *ReferenceObjects* - Ref[IfcFixture]

- Contains references to all instances of *IfcFixture* that are part of the lighting system
- *OccupancyType* - *IfcLightingOccupancyType*
  - Lighting occupancy type according to the Standard
- *LightingPowerDensity* - *IfcReal*
  - Lighting power density specified by the Code (based on Occupancy type)
- *LightingPower* - *IfcReal*
  - Total lighting power for the proposed design

- ***IfcLightingFixture***

- Data**

- *Category* - *Ref[IfcLightingFixtureType LibraryEntry]*
    - The category of lighting fixture
  - *NumberOfLampsPerFixture* - *IfcReal*
    - Number of lamps per fixture
  - *FixtureIdentification* - *IfcString*
    - Fixture identification on plan
  - *FixtureWattage* - *IfcInteger*
    - Total input wattage of the fixture including lamps and ballast
  - *NumberOfFixtures* - *IfcInteger*
    - Total number of this fixture type used in the building

- ***IfcMaterialType* (Class structure for material properties library--Not addition to Core class)**

- Data**

- *Type* - *IfcMaterialTypeEnum*
    - Describes the function of the material layer as an Enum
  - *ThermalResistance* - *IfcReal*
    - Thermal resistance of the material for unit thickness
  - *HeatCapacity* - *IfcReal*
    - Specific heat capacity of the wall material

- ***IfcFillingElementType* (Class structure for filling element library--Not addition to Core class)**

- Data**

- *FramingType* - *IfcFrameTypeEnum*
    - Enum representing the frame type
  - *GlazingType* - *IfcGlazingTypeEnum*
    - Enum representing the glazing type
  - *ThermalResistance* - *IfcReal*
    - Thermal resistance of the filling material
  - *ShadingCoefficient* - *IfcReal*
    - Shading coefficient of filling material

- ***IfcLightingFixtureType* (Class structure for lighting fixture library--Not addition to Core class)**

- Data**

- *Description* - *IfcString*
    - Description of the lighting Fixture
  - *LampType* - *IfcLampTypeEnum*
    - Lamp type
  - *LampDescription* - *IfcString*
    - Description of the lamp type
  - *WattagePerLamp* - *IfcInteger*
    - Power used by each lamp in the fixture
  - *BallastType* - *IfcBallastTypeEnum*
    - The type of ballast used in the fixture

### **5.6.1.3. RoadMap Issues**

#### ***Interoperability Value***

##### ***Disciplines/Applications from which information is needed:***

- *Architecture*
- *HVAC*
- *Lighting*

##### ***Disciplines/Applications to which information will be supplied:***

- *Architecture*
- *HVAC*
- *Lighting*

#### ***Value of software supporting this process***

In this section, other domain teams will rank the value of software which supports this process, based on IFC. Value from 1-10, 1 being the lowest value, 10 being the highest value.

- *Not assessed for this project*

#### ***Sponsor Software Companies***

The following organizations that develop software used by AEC end users have shown interest in developing applications which implement the process:

- *Pacific Northwest National Laboratory*
- *Autodesk (was Softdesk)*
- *Visio (was Ketiv)*

### **5.6.1.4. Issues identified in reviews**

#### ***No reviews recorded***

##### **Issues**

##### **Proposed resolution**

- No issues recorded
  - No resolutions recorded

## **5.7. [CS-2] Code Checking Extensions**

The project covers specific application of the code compliance enabling mechanism (R2\_CS-1) in serving the disabled access and escape routes code compliance.

The processes are performed by building designers and code enforcement officials during early design and submission stages, respectively.

Codes considered in this project:

- For Access
- For Escape

## 5.7.1. Codes for Access and Escape

### 5.7.1.1. Information Analysis by Task

#### 5.7.1.1.1. Task A - Identify Applicable Code Requirements

This step involves selecting or specific code requirements applicable to a particular type of buildings

**Input Information:**

- *Types, functions and occupancy of building, space and access found on a floor plan*
- *Divisions, sections of and clauses of codes*

**Output Information:**

- *Specific code requirements to be satisfied*

#### 5.7.1.1.2. Task B - Check for Compliance

This step involves accessing information about building components from the building model, performing additional computations to derived more information not capture in the building model but is essential for the code checking.

**Input Information:**

- *Building model*
- *Code requirements to be satisfied resulted from previous step.*
- *All derived information necessary for compliance checks.*

**Output Information:**

- *Compliance checks results*

#### 5.7.1.1.3. Task C - Record Code Violations

This step involves presenting code violation on screen, generating written directions and recording as part of building model for further reference.

**Input Information:**

- *Compliance checks results*
- *Building model.*

**Output Information:**

- *Highlight of the violation*
- *Return directions*
- *Building model*

### 5.7.1.2. IFC Model Impact

This section summarizes the model requirements from all the process tasks analyzed above into two groups  
Extensions to R1.5.1 model object types and proposed new object types for R2.0.

#### **Extensions to IFC R1.5 object types – Disabled Access**

- **IfcSpace**

- Data**

- *IfcSpaceType – IfcTypeDefinition*
    - *Add to predefined type of IfcSpaceType to cover concept of internal and external with respect to the building envelop.*

- **IfcZone**

- Data**

- *IfcZoneType*

- Add to predefined type of *IfcZoneType* to cover zone with disabled access provision so that checking can be more focus.

- **IfcDoor**

- Data**

- *IfcOpenType* – *IfcTypeDefinition*
    - Predefined generic types to describe how door is opened (e.g. Sliding, Swing, one-way or two way)
  - *IfcSwingDirection* – *IfcTypeDefinition*
    - Predefined generic types to describe the swing directions with respect to a pivot (pull and push side of the swing to be indicated)
  - *ClearanceSpace* – *IfcArea*
    - Area of a square bounding the swing of a door.

## **Extensions to IFC R1.5 object types – Disabled Access**

- **IfcBuilding**

- Data**

- *IfcBuildingUsage* – *IfcTypeDefinition*
    - Predefined generic types to describe usage of building e.g. Enum (commercial, residential). This will in turn links to the occupancy load.
  - *IfcOccupancyLoad* – *IfcInteger*
    - Estimated maximum numbers of peoples likely to occupy the building at any one time

- **IfcZone**

- Data**

- *IfcZoneUsage* – *IfcTypeDefinition*
    - Add to predefined type of *IfcZoneUsage* to cover fire compartment or zone with fire-protected provision (including smoke, sprinkler) so that checking can be more focus. provision, so that checking can be more focus.
  - *IfcOccupancyLoad* – *IfcInteger*
    - Estimated maximum numbers of peoples likely to occupy the zone at any one time

- **IfcStorey**

- Data**

- *IfcHasFloorLevel* – *IfcRea*
    - Floor Level above ground
  - *IfcHasExitFacility* – List [1:N] *IfcExitFacility*
    - List of exit facilities that found in the storey
  - *IfcOccupancyLoad* – *IfcInteger*
    - Estimated maximum numbers of peoples likely to occupy the storey at any one time

- **IfcSpace**

- Data**

- *IfcSpaceUsage* – *IfcTypeDefinition*
    - Named types to describe usage of a space (e.g. classroom, staircase). This will in turn links to the occupancy load.
  - *IfcOccupancyLoad* – *IfcInteger*
    - Estimate number of people likely to occupy a space at any one time

## **New object types required – Disabled Access**

- **IfcRamp**

- Data**

- *IfcHasElements* – List [1:N] *IfcRampElement*
    - Consists of a list of *IfcRampElement*

- **IfcRampElements**

- Data**

- *IfcRampElementsType* – *IfcTypeDefinition*
  - *Predefined generic types of ramp elements e.g. Enum (flight and landing).*
- *IfcRampFootPath* – *IfcPolyCurve3D*
  - *Path of the center line of the IfcRampElement*
- *IfcRampOutline* – *IfcCurve3D*
  - *A closed 3D curve profile to describe the outline of the IfcRampElement*
- *IfcRampSideElements* – *List [2:N] IfcSideElement*
  - *Side element can be wall, column or balustrade*
- *IfcRampEffectiveWidth* - *IfcReal*
  - *Minimum clear width of a ramp element*
- *IfcRampFloorMaterial* - *IfcTypeDefinition*
  - *Predefined generic types of approved ramp material.*
- **IfcLanding**
  - Data**
    - *IfcLandingEffectiveLength* – *IfcReal*
      - *Minimum clear length for packing a stationary wheelchair on the landing*
    - *IfcLandingFloorLevel* – *IfcReal*
      - *Floor level of a landing*
- **IfcFlight**
  - Data**
    - *IfcFlightVerticalRise* – *IfcReal*
      - *Change in floor level*
    - *IfcFlightHorizontalRun* – *IfcReal*
      - *Length of the run*
- **IfcSideElement**
  - Data**
    - *IfcSideElementsType* – *IfcTypeDefinition*
      - *Predefined generic types of side elements e.g. Enum (wall, column, balustrade).*
    - *IfcSideBaluster* – *IfcBalusterType*
      - *baluster can also be handrails, railing*
- **IfcBaluster**
  - Data**
    - *IfcBalusterType* - *IfcTypeDefinition*
      - *Predefined generic types of baluster or handrail*
    - *IfcBalusterProfile* – *IfcPolyCurve3D*
      - *Polycurve that defines the path of baluster*
    - *IfcBalusterGrippingArea* – *IfcReal*
      - *Gripping area of a handrail*
- **IfcLift**
  - Data**
    - *IfcLiftType* - *IfcTypeDefinition*
      - *Predefined types of lift e.g. Enum (Disabled, Cargo, Fire etc)*
    - *IfcLiftEffectiveWidth* – *IfcReal*
      - *Minimum clear width for the maneuvering of wheelchair into the lift*
    - *IfcLiftEffectiveLength* – *IfcReal*
      - *Minimum clear length for packing a stationary wheelchair in the lift*
    - *IfcLiftEffectiveTurningArea* – *IfcArea*
      - *Minimum area for turning of a wheelchair in the life and at the doorway of the lift.*
    - *IfcLiftServingStorey* – *List [1:N] IfcBuildingStorey*
      - *Stories being served by the Lift*
- **IfcSymbol**
  - Data**

- *IfcSymbolType* - *IfcTypeDefinition*
- *Predefined types of symbol e.g. Enum (Disabled, Fire etc)*
- *IfcPlacement* - *IfcPoint*
- *Position of symbol*

## **New object types required – Escape Route**

### **• IfcExitFacility**

#### **Data**

- *IfcExitFacilityType* – *IfcTypeDefinition*
- *Predefined generic types of exit facilities e.g. Enum (e.g. exit door, exit approach)*
- *IfcHasFireRating* – *IfcReal*
- *Number of hours*
- *IfcHasCapacity* – *IfcInteger*
- *Maximum numbers of occupant passing through the facility at any one time.*
- *IfcHasEffectiveWidth* – *IfcReal*
- *Effective width of the facility*

### **• IfcExitApproach**

#### **Data**

- *IfcExitApproachType* – *IfcTypeDefinition*
- *Predefined generic types of exit approach e.g. Enum (e.g. exit passageway, exit corridor, exit lobby, exist staircase).*
- *IfcOtherRelatedUsage* – *List [1:N IfcTypeDefinition*
- *Predefined generic types of other usage for exit approach e.g. Enum (e.g. area of refuge, area of fire fighting).*
- *IfcHasFireResistanceProvision* – *List [1:N] IfcFireResistanceProvision*
- *list of fire resistance provision*
- *IfcHasOpening* – *List [1:N] IfcOpening*
- *list of openings*

### **• IfcFireResistanceProvision**

#### **Data**

- *IfcFireResistanceProvisionType* – *IfcTypeDefinition*
- *Predefined generic types of fire resistance provision e.g. Enum (e.g. smoke-free, sprinklered, naturally ventilated, mechanically ventilated equipment).*

## **5.7.1.3. RoadMap Issues**

### **Interoperability issues**

#### **Disciplines from which information is needed:**

- *Architectural*
- *Structural*
- *HVAC*
- *Disciplines for which information is produced:*
  - *Architectural*
  - *HVAC*
  - *Fire Protection*
  - *Cost Estimator*
  - *Code Enforcement*

### **Value to AEC Domains**

- *Not ascertained*



### ***Sponsor Software Companies***

The following organizations that develop software used by AEC end users have shown interest in developing applications which implement the process:

- *National Computer System*

#### ***5.7.1.4. Issues Identified in Reviews***

##### ***No reviews recorded***

###### **Issues**

###### **Proposed resolution**

- No issues recorded
- No resolutions recorded

### ***5.8. [ES-1] Cost Estimating***

#### **5.8.1. Cost Estimating**

The intent of cost estimating is to determine the cost of various objects, tasks and resources in the model. A cost estimator will perform several sub-process to get the estimate. First he will determine the purpose and scope of the estimate. He will identify the objects and processes that lie within that scope. He may project costs directly from the type and dimensions of an object, or he may model the materials, tasks and resources to construct or install an object. Once an object, its parts, and its required tasks and resources have been determined, costs may be calculated and applied to the model. This includes the unit costs of resources, the resulting costs of the tasks, the actual cost of manufactured parts, and the summarized costs of the objects.

##### ***5.8.1.1. Information Analysis by Task***

###### **5.8.1.1.1. Task A - Scope Analysis**

The model is analyzed to determine what objects and object information is available for estimating. The purpose of the estimate is also considered.

###### ***Input Information:***

- *Objects available in the model (spaces, walls, doors, manufactured parts,...)*
- *Type of information in the objects that may be used for estimating. (classifications, material specifications, dimensions...)*
- *Purpose of the estimate (conceptual, detailed, alternate, change order, basis of a bid...)*

###### ***output Information:***

- *Types of objects that will be used as the basis for the estimate. For example, spaces for a conceptual estimate, or more granular objects like doors and walls for a more detailed estimate.*
- *Identification methods to be used to classify the object in terms of the cost estimating system.*

###### **5.8.1.1.2. Task B - Identify Object**

A class of objects is selected for estimating. All instances of that type of object are selected and classified in terms of the cost estimating system. The object selection criterion should be stored so that an estimate of the same scope can be accomplished after changes have been made to the model.

###### ***Input Information:***

- *Types of objects to be estimated.*
- *The object's class.*
- *The object's specification according to some classification system.*
- *The object's material specification (such as wood, metal, ...)*

- The object's specification requirements (such as fire rating)
- The object's dimension attributes.
- The 'context' of the object. (for example, the material type of the wall a door installed in)
- The object's design status (new, changed, deleted) and version number
- Other attributes that may be of use for cost estimating...

**Output Information:**

- Object selection criterion
- Aggregation of objects for estimating and/or scheduling
- Decomposition objects for estimating and/or scheduling
- The classification of the object in terms of the cost estimating system.

**Project Model Usage Requirements:**

**Existing Classes:**

- **Any object that may impact the cost of the project.**

**Data**

- dimensional information
  - lengths, widths, volumes, ...
- specification information
  - material, functional specification, structural specification, ...

- **IfcClassification**

**Data**

- ClassificationPublisher -> IfcString
  - This references the publisher of the cost book or database.
- ClassificationTable -> IfcString
  - This references the specific table used.
- ClassificationNotation -> IfcString
  - This is the code for the object being classified.
- ClassificationDescription -> IfcString
  - This is a readable description of the classification.

**New Classes:**

- **IfcSelectionSpecification**

**Data**

- SelectionSpecification IfcString
  - This is a parsable expression that can describe a group of objects in the model based on class, attributes, and relationships to other objects. For example, an estimator may want to save a specification for selecting all wood doors that are installed in drywall partition walls.

- **IfcAggregation**

**Data**

- AggregationElements Set [0:N] Ref IfcProductObject
  - This groups together objects that are estimated together.

- **IfcConstructionZone**

**Data**

- ConstructionZone IfcSpaceElement
  - An IfcProductObject may be decomposed into several constructions zones. For example, an IfcSlab may be decomposed into several pour zones.

### 5.8.1.1.3. Task C - Identify Tasks Needed to Install the Object

The estimator examines the object to determine its construction method. The construction method will specify the tasks that need to be completed to construct the object.

**Input Information:**

- Class of the object (wall, door, ...)

- *Attributes of the object (material, finish, ...)*
- *Dimensions of the object (height, area...)*

**Output Information:**

- *IfcWorkGroup* - Work objects that group associated tasks.
- *IfcWorkTask* - Tasks required to construct or install the object
- *IfcResourceObject* - Resources required by work tasks..

**Project Model Usage Requirements:**

**Existing Classes:**

• **IfcWorkGroup**

**Data**

- *WorkGroupTitle* IfcString
  - This allows several tasks to be grouped together.
- *HasParts* Set [0:N] ref IfcWorkGroup
  - This allows hierarchical groupings.
- *ConsistsOf* Set [0:N] ref IfcWorkTask
  - This allows several tasks to be grouped together.

• **IfcWorkTask**

**Data**

- *TaskDescription* IfcAttString
  - Describes the task
- *WorkMehod* IfcAttString
  - Describes the work method for the task
- *TotalCost* IfcCost
  - Total cost of the task
- *Resources* List [0:N] IfcResourceObject
  - List of resources needed to complete the task
- *ResourceQuantity* List [0:N] IfcAttReal
  - The Quantities of the above resources
- *ResourceDuration* List [0:N] IfcAttDate
  - Time durations for the above resources are needed

• **IfcResourceObject**

**Data**

- *ResourceType* enum Labor, Equipment, Material
  - Specifies the basic type of resource
- *ResourceDescription* IfcAttString
  - Description of the resource. (e.g. Carpenter, Hoist, Forms.)
- *HasCost* -> IfcUnitCost
  - Cost per unit

**New Classes:**

- **No new classes are required for this functionality.**

**5.8.1.1.4. Task D - Identify Resources Needed to Install the Object**

The estimator determines the resources required to perform each of the tasks.

**Input Information:**

- *IfcTask*
- *Attributes of the object (material, finish, ...)*
- *Dimensions of the object (height, area...)*

**Output Information:**

- *IfcResource*

### **Project Model Usage Requirements:**

#### **Existing Classes:**

- **IfcResourceObject**

##### **Data**

- *ResourceType* enum Labor, Equipment, Material
  - Specifies the basic type of resource
- *ResourceDescription* IfcAttString
  - Description of the resource. (e.g. Carpenter, Hoist, Forms.)
- *HasCost* -> *IfcUnitCost*
  - Cost per unit

#### **New Classes:**

- **No new classes are required for this functionality.**

### **5.8.1.1.5. Task E - Determine Unit Costs**

Once quantities have been determined for the 'overall' object or its tasks and resources, unit costs are applied. If cost is being modeled using tasks and resources, unit costs are selected for the resources. If cost is being modeled based on a unit cost for the overall object, a unit cost is select for the overall object.

#### **Input Information:**

- Object to be costed
- Resources to be costed
- Unit costs (possibly from an estimating system or price book)

#### **Output Information:**

- *IfcUnitCost*

### **Project Model Usage Requirements:**

#### **Existing Classes:**

- **IfcUnitCost**

#### **New Classes:**

- **No new classes are needed.**

### **5.8.1.1.6. Task F - Calculate Costs**

The object and resource quantities and the selected unit costs are used to calculate the cost of the object or its resources.

#### **Input Information:**

- Object's 'overall' quantity
- Resource quantities
- Unit costs

#### **Output Information:**

- Resource cost (if tasks and resources are used to model the cost)
- Object cost (if the cost is based on the object's 'overall' quantity)

### **Project Model Usage Requirements:**

#### **Existing Classes:**

- **IfcCost**
- **IfcUnitCost**

#### **New Classes:**

- **No new classes are needed.**

#### 5.8.1.1.7. Task G - Summarize Costs

If an object's cost is based on the costs of its tasks and resources or on the costs of its component parts, summarize these costs at the task and object level.

You must be able to place a cost on any object in the model, including aggregations and decompositions. Furthermore, objects will need multiple costs. For instance, you may need to store original budget cost for the object, final estimated cost, and actual installed cost for one object.

To organize costs in a format that is meaningful, they are compiled in Cost Schedules. The cost elements in a schedule and the physical objects whose cost they represent, should have references to each other. That is, from the physical object, you should be able to find all cost schedule elements that describe the cost of the object. And from the cost schedule element, you should be able to find the physical object that it references.

##### **Input Information:**

- Resource costs
- Costs of component parts

##### **Output Information:**

- Task costs
- Object cost
- Cost schedule

#### **Project Model Usage Requirements:**

##### **Existing Classes:**

- **IfcWorkTask**

###### **Data**

- TaskCost IfcCost
- Total cost of the task

- **IfcProductObject**

###### **Data**

- ProductCost IfcCost
- Cost impact of the product object.

- **IfcCostScheduleElement**

###### **Data**

- TotalCost IfcCost
  - Total cost of this entry in the cost schedule
- UnitCost IfcUnitCost
  - Cost per unit for this entry in the cost schedule
- Description IfcAttString
  - Description for this entry in the cost schedule
- Quantity IfcAttReal
  - Quantity for this entry in the cost schedule (in terms of UnitCost unit)

- **IfcProjectObject**

###### **Data**

- Costs LIST[0:N] IfcCost
- CostSchedules LIST[0:N] IfcCostSchedule
- CostScheduleElements LIST[0:N] IfcCostScheduleElement

##### **New Classes:**

- **No new classes are needed.**

### 5.8.1.2. IFC Model Impact

This section summarizes the model requirements from all the process tasks analyzed above into two groups  
Extensions to R1.5.1 model object types and proposed new object types for R2.0.

#### Usage/Extensions to R1.5.1 object types

- **IfcProductObject**

**Data**

- **ConstructionZones** Set [0:n] ref IfcConstructionZone
  - The decomposition of a product object into construction zones. For example, an IfcSlab may be decomposed into several pour zones.

- **IfcWorkTask**

**Data**

- We need to make sure that the current IfcWorkTask is able to specify any number of resource usages.
- **Resources** List [0:N] IfcResourceObject
  - List of resources needed to complete the task
- **ResourceQuantity** List [0:N] IfcAttReal
  - The Quantities of the above resources
- **ResourceDuration** List [0:N] IfcAttDate
  - Time durations for the above resources are needed

- **IfcProjectObject**

**Data**

- **Costs** List[0:??] IfcCost
  - We should allow for more than one cost on a project object, since it may have different costs, depending on your viewpoint or the stage of design. For example, is a cost an actual cost or an estimated cost?
- **CostSchedules** List[0:??] IfcCostScheduleObject
  - The IfcProjectObject should be able to reference cost schedules that explain the cost breakdown of the object. This allows an object's costs to be reported in any number of formats.
- **CostScheduleElements** List[0:??] IfcCostScheduleElements
  - The IfcProjectObject should be able to reference cost schedules that display the object's cost in the context of the cost estimate.

- **IfcCost**

**Data**

- **CostType** Enumeration???
- In the current model (1.5), ProductCost is used to represent the cost of an IfcProductObject. But as mentioned above, the meaning of a cost is not precisely defined. For instance, is a ProductCost the sum of the cost of its sub-object and work objects? Is it a manufacturer's cost, or does it include cost of installation?
- We should specify Cost Types that would help define the meaning of an IfcCost. Some possible cost types are:
  - Singular cost - Costs calculated based on a unit cost and a quantity.
  - Aggregate cost - Sum of the costs of an object's parts.
  - Target cost (allowable cost?) - Used to communicate the allowable expenditure for an object. This may also be a range.

#### New object types required

- **IfcSelectionSpecification**

**Data**

- **SelectionSpecification** IfcString

- A parsable expression that identifies a group of objects in the model based on class, attributes, and relationships to other objects. Example: Select all wood doors that are installed in drywall partition walls in a particular construction zone.

- **IfcAggregation**

- Data**

- AggregationElements    Set [0:N] Ref IfcProductObject
    - This groups together objects that are estimated and/or scheduled together

- **IfcConstructionZone**

- Data**

- ConstructionZone    IfcSpaceElement
    - A project may have multiple "construction zones" which are defined by the construction planner, for scheduling tasks and assigning resources and methods. For instance, a construction planner may sequence foundation pours starting at zone 1 and proceeding through the last zone scheduled.

### 5.8.1.3. RoadMap Issues

#### **Interoperability Issues**

##### **Disciplines/Applications from which information is needed:**

- Architecture
- Other disciplines that provide attribute sets to describe objects.

##### **Disciplines/Applications to which information will be supplied:**

- Architecture
- Estimating
- Scheduling
- Facilities Management
- Other disciplines that provide attribute sets to identify objects

#### **Value of software supporting this process**

- Scheduling - 1
- Estimating - 1
- Facilities Management - 3

#### **Sponsor Software Companies**

The following organizations that develop software used by AEC end users have shown interest in developing applications which implement the process:

- Timberline Software

### 5.8.1.4. Issues identified in reviews

#### **No reviews recorded**

##### **Issues**

##### **Proposed resolution**

- No issues recorded
  - No resolutions recorded

## 5.9. [FM-3] Property Management (Building Owner's viewpoint)

### 5.9.1. Grouping IFC objects

This process can be performed at any stage in the lifecycle of the building, but it has been designed for the Property manager. Groups can consist of IFC Object, and the user can use the Group object to make links to the users own private objects.

The need for grouping can be caused by any management purpose, like new department, workgroup, cleaning area, renovation, fire zone etc. In this process the property manager can create new groups from selected objects. These groups can be used for any administrative or management purposes. All material or quantitative information is calculated from the IFC model. The model information can be used together with owner's own or other external database information to evaluate operational costs or other needed values.

#### 5.9.1.1. Information Analysis by Task

There are three processes in the Grouping IFC Objects. Manage requirements is properly supported by a Facility Management Software tool, while Grouping IFC is a IFC based application. Evaluation and other functions can be based on the users own software, it must just be able to read the needed IFC Objects.

The first task is to define the grouping purpose, which defines the classification of the group. Then the objects for new group can be selected through various methods:

- any objects selected by the user
- filtered objects (type, properties or other selection key) selected by the user
- filtered objects in the whole model

After the selection is completed the user can give a description to the group.

##### 5.9.1.1.1. Task A - Management requirements

The user makes decisions about what he would like group.

**Input Information:**

- Any needs for grouping

**Output Information:**

- Selection criteria
- Space type either/or
- Floor type
- Department use of spaces
- Cleaning
- etc.

**Project Model Usage Requirements:**

**Existing Classes:**

- none for this task

**New Classes:**

- none for this task

##### 5.9.1.1.2. Task B - Grouping

The Grouping process reads information about what should be grouped. A number of object is selected from the IFC model either by IFC Objects type/attribute or by the user picks a number of objects from the model. A new grouping object is made and the identification of the selected objects a store/linked to the grouping object.



**Input Information:**

- Section criteria
- IFC Objects (IFC Space, IFC Layered Element etc.)

**Output Information:**

- IFC Grouping object
- Identification
- Description
- Classification of groups

**Project Model Usage Requirements:**

**Existing Classes:**

- **IFC Object**  
**Data**
  - Identification
  - Attribute already in IFC objects

**New Classes:**

- **IFC Grouping Object**  
**Data**
  - Identification
  - Description
  - Classification of group from a project specific list

**5.9.1.1.3. Task C - Management, rental etc.**

Use IFC Grouping object to make connection to private database systems or to makes reports and drawings.

**Input Information:**

- IFC Grouping Object
- Own data: Cost, taxes etc.

**Output Information:**

- Evaluation result (Rental, drawings )

**Project Model Usage Requirements:**

**Existing Classes:**

- **IFC Objects**  
**Data**
  - Identification
  - Attribute already in IFC objects

**New Classes:**

- **{{ Object type name }}**  
**Data**
  - {{ Data description      type }}
  - {{ notes }}

**5.9.1.2. IFC Model Impact**

This section summarizes the model requirements from all the process tasks analyzed above into two groups  
Extensions to R1.5.1 model object types and proposed new object types for R2.0.

**Usage/Extensions to R1.5.1 object types**

- **IFC Space**

**Data**

- Room number (new)
- Name of space (new)
- Equipment (Electrical and HVAC) list in a string (new)

• **IFC DoorType**

**Data**

- Thermal Rating (new)
- Security Rating (new)
- Change door hardware type to hardware type

• **IFC Windowtype**

**Data**

- Thermal Rating (new)
- Numbers of glasses (new)
- Fire Rating for the window (new)
- Acoustic Rating (new)
- Security Rating (new)
- Pointer to hardware type (new)
- External/Internal (new ?)

• **IFC LayeredElement**

**Data**

- Thermal Rating (new)
- Fire Rating for the window (new)
- Acoustic Rating (new)
- External/Internal (new ?)

• **IFC WallType**

**Data**

- Measure areal of an external wall ?
- Remove Thermal Rating
- Remove Fire Rating
- Remove Acoustic Rating

**New object types required**

• **IFC Grouping Object**

**Data**

- Identification
- Description
- Classification of group from a project specific list

### **5.9.1.3. RoadMap Issues**

**Interoperability Issues**

**Applications from which information is needed:**

- Architectural (Spaces, Wall, Floors, Doors, Windows)
- Others in the future

**Applications for which information is produced:**

- Facility Management
- Any program that needs groups of objects

### ***Value of software supporting this process***

- *{{In this section, please allow for the other domains to rank your process in order of precedence for their domain, this allows us to examine the issue on a group as well as an individual level}}*
- *{{ discipline 1 }} - {{value from 1-10, 1 being the highest value, 10 being the lowest}}*
- *{{ discipline 2 }} - {{value from 1-10}}*

### ***Sponsor Software Companies***

The following organizations that develop software used by AEC end users have shown interest in developing applications which implement the process:

- *Viatek FM*
- *Visio Corporation*
- *AIO group (Finland)*

#### ***5.9.1.4. Issues identified in reviews***

##### ***No reviews recorded***

###### **Issues**

###### **Proposed resolution**

- No issues recorded
  - No resolutions recorded

#### **5.9.2. Linking the maintenance objects to the IFC objects**

The different building elements in the building are linked to a maintenance object. The guarantees, maintenance periods and maintenance history of these elements is stored in the maintenance object. The property manager can check from this information when maintenance operations should be done and if all necessary operations are made according to the guarantee terms. The grouping mechanism is identical to the grouping activities

##### ***5.9.2.1. Information Analysis by Task***

There are three processes in the Linking the maintenance objects to the IFC objects: Management requirements, Maintenance linking and Maintenance information handling.

First task is to define the selection criteria for a maintenance group. Then the objects for new group can be selected through various methods:

- any objects selected by the user
- filtered objects (type, properties or other selection key) selected by the user
- filtered objects in the whole model

After the selection is completed the user can give a description to the new maintenance group.

If the selected objects already belong to some maintenance group, the application should warn the user about it and ask for instructions for further operations.

When the maintenance groups are formed the user can use those as the selection criteria for different maintenance operations and reports. All maintenance data is stored in the maintenance object and the IFC object data should be available from the actual objects. The first task is to define the grouping purpose, which defines the classification of this group. Then the objects for new group can be selected through various methods:

- any objects selected by the user
- filtered objects (type, properties or other selection key) selected by the user
- filtered objects in the whole model

After the selection is completed the user can give a description to the group.

#### **5.9.2.1.1. Task A - Management requirements**

The user makes decisions about what he would like maintain.

***Input Information:***

- *Any needs for maintenance*

***Output Information:***

- *Selection criteria*

***Project Model Usage Requirements:***

***Existing Classes:***

- *none for this task*

***New Classes:***

- *none for this task*

#### **5.9.2.1.2. Task B - Maintenance linking**

IFC objects are linked to a Maintenance object. The IFC Objects are selected according to the selection criteria. A new Maintenance object is defined.

***Input Information:***

- *Section criteria*
- *IFC Objects (IFC Space, IFC Layered Element etc.)*

***Output Information:***

- *IFC Maintenance object*

***Project Model Usage Requirements:***

***Existing Classes:***

- *IFC Object*  
*Data*
  - *ID*

***New Classes:***

- *IFC Maintenance Object*  
*Data*
  - *Identification*
  - *Description*
  - *Classification*
  - *Delivery date*
  - *Guarantee terms (Pointer to)*
  - *Guarantee ending date*
  - *Maintenance period*
  - *Last maintenance date*
  - *Maintenance handling*
  - *Maintenance Instruction (Pointer to)*
  - *Maintenance history (Pointer to)*
  - *Inspection intervals*
  - *Condition report*
  - *Last inspection date*
  - *Inspection handling*
  - *Inspection history (Pointer to)*

- *Priority*
- *Cost*

#### **5.9.2.1.3. Task C - Maintenance information handling**

Use Maintenance Object to produce Maintenance operation schedules and instructions. Maintenance instruction are stored outside the IFC model.

***Input Information:***

- *IFC Maintenance Object*
- *External databases/links to maintenance instructions.*

***Output Information:***

- *Maintenance operations*

***Project Model Usage Requirements:***

***Existing Classes:***

- *IfcCost*

#### **5.9.2.2. IFC Model Impact**

This section summarizes the model requirements from all the process tasks analyzed above into two groups  
Extensions to R1.5.1 model object types and proposed new object types for R2.0.

##### ***Extensions to IFC R1.5 object types***

- ***IFC Objects (IFCWindow)***

***Data***

- *Id*
- *Type (IFCWindowtype)*

##### ***New object types required in IFC R2.0***

- ***IFC Maintenance Object***

***Data***

- *Identification*
- *Description*
- *Classification*
- *Delivery date*
- *Guarantee terms (Pointer to)*
- *Guarantee ending date*
- *Maintenance period*
- *Last maintenance date*
- *Maintenance handling*
- *Maintenance Instruction (Pointer to)*
- *Maintenance history (Pointer to)*
- *Inspection intervals*
- *Last inspection date*
- *Inspection handling*
- *State of condition*
- *Inspection history (Pointer to)*
- *Priority*
- *Cost*

### **5.9.2.3. RoadMap Issues**

#### ***Interoperability Issues***

##### ***Disciplines/Applications from which information is needed:***

- *Architectural (Wall, Doors, Windows, Floors)*
- *HVAC*

##### ***Disciplines/Applications to which information will be supplied:***

- *Facility Management (Maintenance)*

##### ***Value of software supporting this process***

- *None provided*

#### ***Sponsor Software Companies***

The following organizations that develop software used by AEC end users have shown interest in developing applications which implement the process:

- *Viatek FM*
- *Visio Corporation*

### **5.9.2.4. Issues identified in reviews**

#### ***No reviews recorded***

##### **Issues**

##### **Proposed resolution**

- No issues recorded
  - No resolutions recorded

## **5.10. [FM-4] Occupancy Planning**

### **5.10.1. Occupancy Planning**

The occupancy planner (includes interior designers, facilities managers, architects, furniture dealers, etc.) applies standards during the assignment of people and organizations to interior spaces. This process occurs during the initial planning of space occupancy, and whenever that occupancy needs to change (company reorganization, company growth, etc.)

#### **5.10.1.1. Information Analysis by Task**

##### **5.10.1.1.1. Task A - Assess Move Request**

Assess request with respect to occupant information, company policies, regulatory requirements. Identify FF&E required for the occupant, and generate space programme.

##### ***Input Information:***

- *Request for Move*
  - *Space area requirements*
  - *Space service requirements (cooling requirements, gases required, etc.)*
  - *Adjacencies/affinities relationships (location)*
  - *FF&E required*

- . *Department requirements*
- . *Occupant list*
- . *Target Occupancy Date*
- . *Budget*
- . *Environmental requirements, e.g. daylight, purification of air*
- . *Special requirements (e.g. raised floor)*
- . *Company policies and standards*
  - . *Relationship between occupant position/title/department and space standard*
  - . *Relationship between occupant position/title/department and equipment standard*
  - . *Relationship between occupant position/title/department and furnishings standard*
- . *Regulatory requirements*
  - . *National or local facilities regulations (e.g. ADA, OSHA)*
  - . *Local Fire/Electrical Codes*

**Output Information:**

- . *Space programme*
  - . *Number and sizes of spaces*
  - . *Requested Space locations*
  - . *Space characteristics*
  - . *Occupant list*
  - . *FF&E lists (existing/new)*
  - . *Target Occupancy Date*
  - . *Budget*
  - . *Special requirements*

**Project Model Usage Requirements:**

**Existing Classes:**

- ***IfcSpaceProgramme (referenced by IfcProgrammeGroup)***
  - *{{ all attributes described in version 1.5 spec + the following }}*
  - *RequestedLocation: Ref. to IfcProductObject*
  - *<this can reference a building, storey, or space>*
  - *ServiceRequirements: Set [0:N] of IfcString*
  - *RequiredFF&E: Set [0:N] of Ref. to IfcTypeDefinition*
  - *TargetDate: IfcDate*
  - *Budget: IfcCost*
  - *SpecialRequirements: Set [0:N] of IfcSpaceRequirement*
- ***IfcActor (referenced in IfcOccupancySchedule, IfcMoveAction, IfcPlan)***
- ***IfcControlObject (supertype of IfcPlan, IfcOccupancySchedule, IfcMoveActionConstraint )***
- ***IfcCost (used in IfcPlan)***
- ***IfcDate (used in Att\_ScheduleData, IfcMoveActionConstraint, IfcPlan)***
- ***IfcElement (referenced in IfcMoveAction)***
- ***IfcPlan (supertype of IfcMovePlan)***
- ***IfcProcessObject (used in IfcOccupancySchedule, supertype of IfcMoveAction)***
- ***IfcProgrammeGroup (referenced in IfcMovePlan)***
- ***IfcProject (referenced in IfcPlan)***
- ***IfcRelSequence (referenced in IfcOccupancySchedule)***
- ***IfcSpace (referenced in IfcMoveAction)***
- ***IfcString (used in IfcPlan, IfcMoveActionConstraint)***
- ***IfcTimeDuration (used in Att\_ScheduleData)***
- ***IfcWorktask (referenced in IfcMovePlan)***

**New classes:**

- **IfcPlan**    *subtype of IfcControlObject, supertype of IfcMovePlan*
  - PlanID: IfcString
  - PlanName: IfcString
  - PlanDescription: Set [0:N] of IfcString
  - Project: Ref. to IfcProject
  - PlanCreators: Set [0:N] of IfcActor
  - CreationDate: IfcDate
  - Approval: Ref. to IfcApproval
  - Budget: IfcCost
- **Att\_ScheduleData**    *Extension Attributeset for any object that uses schedule data set*
  - TotalDuration: IfcTimeDuration
  - ScheduledStartDate: IfcDate
  - ScheduledFinishDate: IfcDate
  - ActualStartDate: IfcDate
  - ActualFinishDate: IfcDate
  - EarlyStartDate: IfcDate
  - EarlyFinishDate: IfcDate
  - LateStartDate: IfcDate
  - LateFinishDate: IfcDate
  - TotalFloat: IfcTimeDuration
  - DaysRemaining: IfcTimeDuration
- **IfcOccupancySchedule**    *subtype IfcControlObject*
  - OccupyingActions: Set [0:N] of Ref. to IfcProcessObject
  - <this contains a set of IfcWorktask and IfcMoveAction>
  - PredAndSuccs: Set [0:N] of Ref. to IfcRelSequence
  - Schedule: Att\_ScheduleData
  - Responsible: Ref. to IfcActor
- **IfcMoveAction**    *subtype of IfcProcessObject*
  - OccupantsToMove: Set [0:N] of Ref. to IfcActor
  - FF&EToMove: Set [0:N] of Ref. to IfcElement
    - <these can be IfcFurniture, IfcEquipment, IfcSystemFurniture, etc.>
  - MoveFrom: Ref. to IfcSpace
  - MoveTo: Ref. to IfcSpace
  - Schedule: Att\_ScheduleData
  - Constraints: Set [0:N] of IfcMoveActionConstraint
  - Responsible: Ref. to IfcActor
- **IfcMoveActionConstraint**    *subtype of IfcControlObject*
  - ConstraintType: IfcString
  - <e.g. must be out by, etc.>
  - ConstraintDate: IfcDate
- **IfcMovePlan**    *subtype of IfcPlan*
  - OccupancySchedule: Ref. to IfcOccupancySchedule
  - RequiredWork: Set [0:N] of Ref. to IfcWorktask
  - ProgramGroupToBeMoved: Ref. to IfcProgrammeGroup
  - <this programme group references a set of Space Programs>

#### 5.10.1.1.2. Task B - Evaluate Candidate Solutions

Compare space programme to available (incl. existing or added) spaces to find candidate solutions including the changes of spaces and FF&E.

**Input Information:**



- . *Space programme*
- . *Space inventory*
- . *List of candidate spaces and characteristics (see Space Programme)*

**Output Information (assuming candidate space exists):**

- . *Schematic Design*
  - . *space assignment*
  - . *schematic drawings*
- . *Required changes*
  - . *Space changes*
  - . *FF&E changes*

**Project Model Usage Requirements:**

**Existing Classes:**

- ***IfcActor* (referenced in *IfcInventory*)**
- ***IfcArea* (used in *IfcSpaceInventory*)**
- ***IfcDate* (used in *IfcInventory*)**
- ***IfcInteger* (used in *IfcSpaceInventory*)**
- ***IfcProductObject* (referenced in *IfcInventory*)**
- ***IfcSpace* (referenced by *IfcSpaceInventory*)**
- ***IfcSpaceElement* (referenced in *IfcSpaceInventory*)**
- ***IfcString* (used in *IfcMovePlan*, *IfcSpaceInventory*, *IfcInventory*)**

**New Classes:**

- ***IfcMovePlan*      *extended from last step***
  - *{{ all items described in previous process steps + the following }}*
    - *Documents: Set [0:N] of Ref. to IfcDocument (to be defined in the next process)*
    - *<e.g. schematic drawings, etc.>*
- ***IfcInventory* <Abstract class>      *supertype of IfcSpaceInventory, IfcFurnitureInventory, and IfcEquipmentInventory***
  - *InventoryDescription: IfcString*
  - *InventoryScope: Ref. to IfcProductObject {{this can reference to a building, storey, or space}}*
  - *InventoryJurisdiction: Ref. to IfcActor*
  - *InventoryResponsible: Set [0:N] of Ref. to IfcActor*
  - *LastUpdateDate: IfcDate*
- ***IfcSpaceInventory*      *subtype of IfcInventory***
  - *HasSpaces: Set [0:N] of Ref. to IfcSpaceElement {{this allows to include zones}}*
  - *TotalSpaces: IfcInteger*
  - *TotalNetArea: IfcArea*

**1.1.1.1.1 Task C - Proposed Move Plan**

During the design and generation of drawings, we allow for client review and approval. Define temporary staging areas, generate schedules, identify sources of all FF&E required and generate a cost estimate.

**Input Information:**

- *Schematic design*
- *Required changes*

**Output Information:**

- . *Proposed move plan*
  - . *Drawing*

- *Schedule*
- *Cost estimate*

### **Project Model Usage Requirements:**

#### **Existing Classes:**

- *IfcCostSchedule* (used in *IfcMovePlan*)

#### **New Classes:**

- *IfcMovePlan*      **extended from last step**
  - {{ all items described in previous process steps + the following }}
  - *ProjectCostEstimate*: *IfcCostSchedule*

### **5.10.1.1.3. Task D - Approval Process**

Occupant and management review proposed move plan and either approve (possibly with constraints) or rejects --> revert to previous steps.

#### **Input Information:**

- *Proposed move plan*
  - *Drawing*
  - *Schedule*
  - *Cost estimate*

#### **Output Information:**

- *Approval constraints*
  - *Limitations on move plan*

### **Project Model Usage Requirements:**

#### **Existing Classes:**

- *None in this step*

#### **New Classes:**

- *IfcMovePlan*

### **1.1.1.1.2 Task E - Complete Move Plan**

Modify proposed plan to comply with constraints. Generate work orders and purchase orders.

#### **Input Information:**

- *Proposed move plan*
- *Approval constraints*

#### **Output Information:**

- *Approved plan*
- *record drawing set*
- *move schedule*
- *installation schedule*
- *work orders*
- *purchase orders*

### **Project Model Usage Requirements:**

#### **Existing Classes:**

- *IfcActor* (referenced in *Att\_PurchaseOrder*, *Att\_WorkOrder*)
- *IfcCost* (used in *Att\_PurchaseOrder*, *Att\_PurchaseOrderItem*)
- *IfcCostSchedule* (used in *Att\_WorkOrder*)

- **IfcDate** (referenced in **Att\_PurchaseOrder**, **Att\_WorkOrder**)
- **IfcInteger** (used in **Att\_PurchaseOrder**, **Att\_PurchaseOrderItem**)
- **IfcProductObject** (referenced in **Att\_WorkOrder**)
- **IfcReal** (used in **Att\_PurchaseOrderItem**)
- **IfcString** (used in **Att\_PurchaseOrder**, **Att\_PurchaseOrder**, **Att\_PurchaseOrderItem**, **Att\_WorkOrder**)
- **IfcWorkTask** (referenced in **Att\_WorkOrder**)
- **IfcUnit** (used in **Att\_PurchaseOrderItem**)

**New Classes:**

- **IfcMovePlan**      **extended from last step**
  - {{ all items described in previous process steps + the following }}
  - **WorkOrders**: Set [0:N] of Ref. to **IfcDocument**
  - {{ List of references to work orders necessary to complete the Occupancy Schedule }}
  - **PurchaseOrders**: Set [0:N] of Ref. of **IfcDocument**
  - {{ List of references to purchase orders necessary to complete the Occupancy Schedule }}
- **WorkOrder**      **of IfcTypeDefinition of DocumentType in IfcDocument**
  - target object = "IfcDocument"
  - shared = **Att\_DocumentType**
  - occurrence = **Att\_WorkOrder**
- **Att\_WorkOrder**
  - **TransactionCode**: **IfcString**
  - **RequestID**: **IfcString**
  - **Facility**: Set [1:N] of Ref. to **IfcProductObject**
  - **DateOfRequest**: **IfcDate**
  - **ShortJobDescription**: **IfcString**
  - **JobDescription**: Set [0:N] of **IfcString**
  - **Justification**: Set [0:N] of **IfcString**
  - **IfNotAccomplished**: Set [0:N] of **IfcString**
  - **WorkRequest**: Ref. to **IfcWorkTask**
  - **EstimatedCost**: **IfcCostSchedule**
  - **ContractType**: Enum (**InHouse**, **SelfHelp**, **Contract**)
  - **Budget**: Ref. to **IfcBudget**
  - **RequestBy**: Ref. to **IfcActor**
  - **RequestTo**: Ref. to **IfcActor**
  - **AdditionalContact**: Ref. to **IfcActor**
  - **Approval**: Ref. to **IfcApproval**
- **PurchaseOrder**      **of IfcTypeDefinition of DocumentType in IfcDocument**
  - target object = "IfcDocument"
  - shared = **Att\_DocumentType**
  - occurrence = **Att\_PurchaseOrder**
- **Att\_PurchaseOrder**
  - **PurchaseOrderNo**: **IfcString**
  - **CompanyTitle**: Ref. to **IfcActor**
  - **SupplierName**: Ref. to **IfcActor**
  - **Date**: **IfcDate**
  - **Remark**: Set [0:N] of **IfcString**
  - **DateRequired**: **IfcString**
  - **DateScheduled**: **IfcDate**
  - **DateActual**: **IfcDate**
  - **FOB**: **IfcBoolean**

- *ShipMethod*: *IfcString*
- *TotalCost*: *IfcCost*
- *TotalItems*: *IfcInteger*
- *PurchaseItems*: List [0:N] of *Att\_PurchaseOrderItem*
- *Approval*: Ref. to *IfcApproval*
- ***Att\_PurchaseOrderItem***
  - *ItemNumber*: *IfcInteger*
  - *Quantity*: *IfcReal*
  - *Code*: *IfcString*
  - *Unit*: *IfcUnit*
  - *UnitPrice*: *IfcCost*
  - *TotalCost*: *IfcCost*
  - *InvoiceAmount*: *IfcCost*
  - *TotalBalance*: *IfcCost*
  - *InPurchaseOrder*: Ref. to *IfcDocument*

#### 1.1.1.1.3 Task F - Implement Move Plan

Purchase FF&E. Perform work orders. Deal with change orders. Complete staging space. Move the occupant.

**Input Information:**

- *Approved plan*

**Output Information:**

- *As-built change* <change notes for drawings and documents>

**Project Model Usage Requirements:**

**Existing Classes:**

- *IfcActor* (referenced by *Att\_ChangeOrder*)
- *IfcDate* (used by *Att\_ChangeOrder*)
- *IfcString* (used by *Att\_ChangeOrder*)

**New Classes:**

- ***IfcMovePlan***      **extended from last step**
  - {{ all items described in previous process steps + the following }}
  - *ChangeOrders*: Set [0:N] of Ref. to *IfcDocument*
  - <set of references to change orders to accomplish adjustments to the Occupancy Schedule>
- ***ChangeOrder***      **of *IfcTypeDefinition* of *DocumentType* in *IfcDocument***
  - target object* = "*IfcDocument*"
  - shared* = *Att\_DocumentType*
  - occurrence* = *Att\_ChangeOrder*
- ***Att\_ChangeOrder***
  - *ChangeOrderNo*: *IfcString*
  - *Description*: Set [0:N] of *IfcString*
  - *Date*: *IfcDate*
  - *IssuedBy*: Ref. to *IfcActor*
  - *IssuedTo*: Ref. to *IfcActor*
  - *Approval*: Ref. to *IfcApproval*

#### 1.1.1.1.4 Task G - Updates

Revised documentation and databases to reflect new and revised spaces and assets.

**Input Information:**

- *Approved plan – as modified through the implementation*
- *As-built changes*
- *Space/FF&E inventory*

**Output Information:**

- *As-built drawings /updated FM models*
- *updated space/FF&E inventory*

**Project Model Usage Requirements:**

**Existing Classes:**

- ***IfcCost* (used in *IfcFurnitureInventory*, *IfcEquipmentInventory*)**
- ***IfcElement* (used in *IfcFurnitureInventory*)**
- ***IfcEquipment* (used in *IfcEquipmentInventory*)**

**New Classes:**

- ***IfcFurnitureInventory* subtype of *IfcInventory***
  - *TotalValueOriginal*: *IfcCost*
  - *TotalValue*: *IfcCost*
  - *FurnitureInventory*: Set [0:N] of Ref. to *IfcElement*
    - <contains set of *IfcFurniture* and *IfcWorkstation*>
- ***IfcEquipmentInventory* subtype of *IfcInventory***
  - *TotalValueOriginal*: *IfcCost*
  - *TotalValue*: *IfcCost*
  - *EquipmentInventory*: Set [0:N] of Ref. to *IfcEquipment*

### **5.10.1.2. IFC Model Impact**

**Usage/Extensions to R1.0 object types**

- ***IfcActor* (referenced by *Att\_ChangeOrder*, *Att\_PurchaseOrder*, *Att\_WorkOrder*, *IfcInventory*, *IfcOccupancySchedule*, *IfcMoveAction*, *IfcPlan*)**
- ***IfcArea* (used in *IfcSpaceInventory*)**
- ***IfcControlObject* (supertype of *IfcPlan*, *IfcOccupancySchedule*, *IfcMoveActionConstraint*)**
- ***IfcCost* (used in *Att\_PurchaseOrder*, *Att\_PurchaseOrderItem*, *IfcFurnitureInventory*, *IfcEquipmentInventory*, *IfcPlan*)**
- ***IfcCostSchedule* (used in *IfcMovePlan*, *Att\_WorkOrder*)**
- ***IfcDate* (referenced in *Att\_PurchaseOrder*, *Att\_WorkOrder*, *Att\_ChangeOrder*, *Att\_ScheduleData*, *IfcMoveActionConstraint*, *IfcPlan*, *IfcInventory*)**
- ***IfcElement* (referenced in *IfcMoveAction*, *IfcFurnitureInventory*)**
- ***IfcEquipment* (used in *IfcEquipmentInventory*)**
- ***IfcInteger* (used in *Att\_PurchaseOrder*, *Att\_PurchaseOrderItem*, *IfcSpaceInventory*)**
- ***IfcPlan* (supertype of *IfcMovePlan*)**
- ***IfcProcessObject* (used in *IfcOccupancySchedule*, supertype of *IfcMoveAction*)**
- ***IfcProductObject* (referenced in *Att\_WorkOrder*, *IfcInventory*)**
- ***IfcProgrammeGroup* (referenced in *IfcMovePlan*)**
- ***IfcProject* (referenced in *IfcPlan*)**
- ***IfcReal* (used in *Att\_PurchaseOrderItem*)**

- **IfcRelSequence** (referenced in **IfcOccupancySchedule**)
- **IfcSpace** (referenced by **IfcSpaceInventory**, **IfcMoveAction**)
- **IfcSpaceElement** (referenced in **IfcSpaceInventory**)
- **IfcSpaceProgramme** (referenced by **IfcProgrammeGroup**)
  - {{ all attributes described in version 1.0 spec + the following }}
  - RequestedLocation: Ref. to **IfcProductObject**
  - <this can reference a building, storey, or space>
  - ServiceRequirements: Set [0:N] of **IfcString**
  - RequiredFF&E: Set [0:N] of Ref. to **IfcTypeDefinition**
  - TargetDate: **IfcDate**
  - Budget: **IfcCost**
  - SpecialRequirements: Set [0:N] of **IfcSpaceRequirement**
- **IfcString** (used in **Att\_ChangeOrder**, **Att\_PurchaseOrder**, **Att\_PurchaseOrder**, **Att\_PurchaseOrderItem**, **Att\_WorkOrder**, **IfcMovePlan**, **IfcSpaceInventory**, **IfcInventory**, **IfcPlan**, **IfcMoveActionConstraint**)
- **IfcTimeDuration** (used in **Att\_ScheduleData**)
- **IfcUnit** (used in **Att\_PurchaseOrderItem**)
- **IfcWorkTask** (referenced in **Att\_WorkOrder**, **IfcMovePlan**)

### **New object types required**

- **IfcPlan**    **subtype of IfcControlObject, supertype of IfcMovePlan**
  - PlanID: **IfcString**
  - PlanName: **IfcString**
  - PlanDescription: Set [0:N] of **IfcString**
  - Project: Ref. to **IfcProject**
  - PlanCreators: Set [0:N] of **IfcActor**
  - CreationDate: **IfcDate**
  - Approval: Ref. to **IfcApproval**
  - Budget: **IfcCost**
- **Att\_ScheduleData**    **Extension Attributeset for any object that uses schedule data set**
  - TotalDuration: **IfcTimeDuration**
  - ScheduledStartDate: **IfcDate**
  - ScheduledFinishDate: **IfcDate**
  - ActualStartDate: **IfcDate**
  - ActualFinishDate: **IfcDate**
  - EarlyStartDate: **IfcDate**
  - EarlyFinishDate: **IfcDate**
  - LateStartDate: **IfcDate**
  - LateFinishDate: **IfcDate**
  - TotalFloat: **IfcTimeDuration**
  - DaysRemaining: **IfcTimeDuration**
- **IfcOccupancySchedule**    **subtype IfcControlObject**
  - OccupyingActions: Set [0:N] of Ref. to **IfcProcessObject**
  - PredAndSuccs: Set [0:N] of Ref. to **IfcRelSequence**
  - Schedule: **Att\_ScheduleData**
  - Responsible: Ref. to **IfcActor**
- **IfcMoveAction**    **subtype of IfcProcessObject**
  - OccupantsToMove: Set [0:N] of Ref. to **IfcActor**
  - FF&EToMove: Set [0:N] of Ref. to **IfcElement**
  - MoveFrom: Ref. to **IfcSpace**

- *MoveTo*: Ref. to *IfcSpace*
- *Schedule*: *Att\_ScheduleData*
- *Constraints*: Set [0:N] of *IfcMoveActionConstraint*
- *Responsible*: Ref. to *IfcActor*
- *OccupancySchedule*: Ref. to *IfcOccupancySchedule*
- *RequiredWork*: Set [0:N] of Ref. to *IfcWorktask*
- *ProgramGroupToBeMoved*: Ref. to *IfcProgrammeGroup*
- *Documents*: Set [0:N] of Ref. to *IfcDocument*
- *ProjectCostEstimate*: *IfcCostSchedule*
- *WorkOrders*: Set [0:N] of Ref. to *IfcDocument*
- *PurchaseOrders*: Set [0:N] of Ref. of *IfcDocument*
- *ChangeOrders*: Set [0:N] of Ref. to *IfcDocument*
- ***IfcMoveActionConstraint*    subtype of *IfcControlObject***
  - *ConstraintType*: *IfcString*
  - *ConstraintDate*: *IfcDate*
- ***IfcInventory* <Abstract class>    supertype of *IfcSpaceInventory*, *IfcFurnitureInventory*, and *IfcEquipmentInventory***
  - *InventoryDescription*: *IfcString*
  - *InventoryScope*: Ref. to *IfcProductObject*
  - *InventoryJurisdiction*: Ref. to *IfcActor*
  - *InventoryResponsible*: Set [0:N] of Ref. to *IfcActor*
  - *LastUpdateDate*: *IfcDate*
- ***IfcSpaceInventory*    subtype of *IfcInventory***
  - *HasSpaces*: Set [0:N] of Ref. to *IfcSpaceElement*
  - *TotalSpaces*: *IfcInteger*
  - *TotalNetArea*: *IfcArea*
- ***WorkOrder*    of *IfcTypeDefinition of DocumentType in IfcDocument***
  - target object* = “*IfcDocument*”
  - shared* = *Att\_DocumentType*
  - occurrence* = *Att\_WorkOrder*
- ***Att\_WorkOrder***
  - *TransactionCode*: *IfcString*
  - *RequestID*: *IfcString*
  - *Facility*: Set [1:N] of Ref. to *IfcProductObject*
  - *DateOfRequest*: *IfcDate*
  - *ShortJobDescription*: *IfcString*
  - *JobDescription*: Set [0:N] of *IfcString*
  - *Justification*: Set [0:N] of *IfcString*
  - *IfNotAccomplished*: Set [0:N] of *IfcString*
  - *WorkRequest*: Ref. to *IfcWorkTask*
  - *EstimatedCost*: *IfcCostSchedule*
  - *ContractualType*: Enum (*InHouse*, *SelfHelp*, *Contract*)
  - *Budget*: Ref. to *IfcBudget*
  - *RequestBy*: Ref. to *IfcActor*
  - *RequestTo*: Ref. to *IfcActor*
  - *AdditionalContact*: Ref. to *IfcActor*
  - *Approval*: Ref. to *IfcApproval*
- ***PurchaseOrder*    of *IfcTypeDefinition of DocumentType in IfcDocument***
  - target object* = “*IfcDocument*”
  - shared* = *Att\_DocumentType*
  - occurrence* = *Att\_PurchaseOrder*
- ***Att\_PurchaseOrder***

- *PurchaseOrder\_No*: *IfcString*
- *CompanyTitle*: Ref. to *IfcActor*
- *SupplierName*: Ref. to *IfcActor*
- *Date*: *IfcDate*
- *Remark*: Set [0:N] of *IfcString*
- *DateRequired*: *IfcString*
- *DateScheduled*: *IfcDate*
- *DateActual*: *IfcDate*
- *FOB*: *IfcString*
- *ShipMethod*: *IfcString*
- *TotalCost*: *IfcCost*
- *TotalItems*: *IfcInteger*
- *PurchaseItems*: List [0:N] of *Att\_PurchaseOrderItem*
- *Approval*: Ref. to *IfcApproval*
- ***Att\_PurchaseOrderItem***
  - *ItemNumber*: *IfcInteger*
  - *Quantity*: *IfcReal*
  - *Code*: *IfcString*
  - *Unit*: *IfcUnit*
  - *UnitPrice*: *IfcCost*
  - *TotalCost*: *IfcCost*
  - *InvoiceAmount*: *IfcCost*
  - *TotalBalance*: *IfcCost*
  - *InPurchaseOrder*: Ref. to *IfcDocument*
- ***ChangeOrder* of *IfcTypeDefinition* of *DocumentType* in *IfcDocument***
  - target object* = “*IfcDocument*”
  - shared* = *Att\_DocumentType*
  - occurrence* = *Att\_ChangeOrder*
- ***Att\_ChangeOrder***
  - *ChangeOrderNo*: *IfcString*
  - *Description*: Set [0:N] of *IfcString*
  - *Date*: *IfcDate*
  - *IssuedBy*: Ref. to *IfcActor*
  - *IssuedTo*: Ref. to *IfcActor*
  - *Approval*: Ref. to *IfcApproval*
- ***IfcFurnitureInventory* subtype of *IfcInventory***
  - *TotalValueOriginal*: *IfcCost*
  - *TotalValue*: *IfcCost*
  - *FurnitureInventory*: Set [0:N] of Ref. to *IfcElement*
- ***IfcEquipmentInventory* subtype of *IfcInventory***
  - *TotalValueOriginal*: *IfcCost*
  - *TotalValue*: *IfcCost*
  - *EquipmentInventory*: Set [0:N] of Ref. to *IfcEquipment*

### 5.10.1.3. RoadMap Issues

***Interoperability Issues (see the last section of this document for more information)***

***Applications from which information is needed:***

- *Architecture (Spaces, Walls)*
- *Construction (As-built information on walls, building systems, etc.)*



- *Electrical (Wiring, cabling)*
- *Communications (Telco, networks)*
- *HVAC System (cooling capacity, airflow, humidity, etc.)*

**Applications for which information is produced:**

- *Architecture (as-builts)*
- *Electrical (Wiring, cabling)*
- *Communications (Telco, networks)*
- *HVAC System (cooling capacity, airflow, humidity, etc.)*

**Value of software supporting this process**

- *FM: Very High (in the top 3)*
- *Architecture: High (in the top 5)*
- *CM/Cost: Very High (in the top 3)*
- *Building Service: High (in the top 5)*
- *HVAC: High (in the top 5)*

**Sponsor Software Companies**

The following organizations that develop software used by AEC end users have shown interest in developing applications which implement the process:

- *Naoki Systems Inc.*
- *Visio Corporation*

**5.10.1.4. Issues identified in reviews**

**No reviews recorded**

**Issues**

**Proposed resolution**

- No issues recorded
  - No resolutions recorded

**5.10.2. Design of Workstations**

The facility manager (also interior designers, architects, furniture manufactures and designers, contract furniture dealers, etc.) designs typical workstations to be used by office staff. The process starts from defining the functional requirements of the workstation based on the work types of the employees who use the workstation. The workstation to be designed must also meet the requirements of basic human dimensions for spaces. Special requirements such as a wheelchair must be considered. The design drawings and specifications should be produced based on the configurations of the workstation components and equipment. Final design must be approved before implementation.

**5.10.2.1. Information Analysis by Task**

**5.10.2.1.1. Task A - Define Workstation Requirements**

Define the basic components, component types and equipment, and the security, privacy and special requirements according to the employee type, work types, and company policies, etc..

**Input Information:**

- *Functional information*
- *Employee Information*
  - *Employee type*

- *secretarial, managerial, technical, programmer, reception, telephone respondent, etc.*
- *Number of employees who share the workstation*
- **Task Information**
  - **Work type**
    - *word processing, programming, drafting, etc.*
  - **Work load**
    - *e.g. average of weekly working hours*
    - *amount of paper files to be stored*
    - *average amount of files produced daily*
- **User requirements**
- *special requirements for the particular user, e.g. a wheelchair, special size requirement of the chairs.*
- **Company policies**
- *Max. and min. for managers or employees*

**Output Information:**

- **Component List**
- **Workstation component types (all following items include dimensions)**
  - **Work surfaces (including size)**
    - *writing & reading surface*
    - *computer surface*
    - *meeting surface*
    - *conference surface*
    - *reference material surface*
    - *printer surface*
  - **Storage and storage types**
    - *overhead storage*
    - *shelf storage*
    - *stationary storage*
    - *office supplies*
    - *personal items*
    - *drawers*
    - *file storage (file cabinets, file trays)*
  - **Light fixtures**
    - *ceiling-mounted lighting*
    - *task lighting*
  - **Panels**
    - *workstation partitions (glazed partitions, partitions with door, curved partitions)*
    - *screens (solid screen, glass screen)*
  - **Seating**
    - *guest seating (number of seats)*
    - *desk seating (number of seats)*
- **List of equipment types**
  - *Telephone, answering machine*
  - *electric typewriter*
  - *Computer, external modem, external CD-ROM, tape drive, speakers, etc.*
  - *Printer, fax machine, copier, scanner*
- **Workstation requirements**
- **Security requirements**
  - *drawers must lock*
  - *files must lock*
  - *fireproof file cabinet*
  - *password required to access computer*
- **Privacy requirements**
  - *speech privacy*
  - *visual privacy*
  - *equipment sharing (sharable or not)*

- *Special requirements*
  - *face-to-face interaction*
  - *files delivery requirements*
  - *aesthetic requirements*

### **Project Model Usage Requirements:**

#### **Existing Classes:**

- **IfcActor** (used by **IfcWorkstation**)
- **IfcArea** (used in **IfcWorkstationCompanyPolicy**)
- **IfcAssembledElement** (superclass of **IfcWorkstation**)
- **IfcBoolean** (used by **Att\_Storage**) <not sure whether **IfcBoolean** exists though>
- **IfcBoundingBox** (used by **IfcWorkstation**)
- **IfcControlObject** (superclass of **IfcWorkstationWorkload**, **IfcWorkstationRequirement**, **IfcWorkstationCompanyPolicy**)
- **IfcCost** (used by **IfcWorkstationCompanyPolicy**)
- **IfcFixture** (used by **Att\_TaskLighting**)
- **IfcInteger** (used by **IfcWorkstationWorkload**, **Att\_Storage**)
- **IfcLength** (used by **Att\_SystemFurnitureType**, **Att\_Worksurface**, **Att\_Panel**, **Att\_Storage**)
- **IfcManufacturedElement** (supertype of **IfcSystemFurniture**, used in **IfcWorkstation**)
- **IfcOfficeEquipment** (used by **IfcWorkstation**)
- **IfcPolyCurve2D** (used by **IfcWorkstation**, **Att\_Panel**)
- **IfcReal** (used by **IfcWorkstationWorkload**)
- **IfcSpace** (referenced in **IfcSystemFurniture**)
- **IfcString** (used by **IfcWorkstationRequirement**, **IfcWorkstationCompanyPolicy**, **IfcWorkstation**, **Att\_SystemFurnitureType**, **Att\_Panel**, **Att\_Worksurface**, **Att\_Storage**)
- **IfcTimeDuration** (used by **IfcWorkstationWorkload**)
- **IfcTypeDefinition** (used by **IfcSystemFurniture**, **Panel**, **Worksurface**, **Storage**)
- **Att\_FurnitureType**
  - <attributes defined in IFC 1.0 spec + following>
  - **Product\_code**: **IfcString**
  - **Width**: **IfcLength** <nominal overall width>
  - **Height**: **IfcLength** <nominal overall height>
  - **Depth**: **IfcLength** <nominal overall depth>
  - **Material**: **IfcString**
  - **Finishing**: **IfcString** <e.g. walnut, fabric>

#### **New classes:**

- **IfcWorkstationWorkload**    **subtype of IfcControlObject**
  - **AverageWorkhourWeekly**: **IfcTimeDuration**
  - **TotalPaperfilesToStore**: **IfcInteger**
    - <used to determine file storage>
  - **AveragePaperfilesProducedDaily**: **IfcInteger**
  - **TotalComputerfiles**: **IfcReal**
    - <used to determine computer equipment>
    - <in unit of MB>
- **IfcWorkstationCompanyPolicy**    **subclass of IfcControlObject**
  - **EmployeeType**: **IfcString**

- <e.g. manager, programmer, secretary, etc.>
  - *MaxWorkstationSize*: *IfcArea*
  - *MinWorkstationSize*: *IfcArea*
  - *FurnitureStyle*: *IfcString*
  - *CostLimit*: *IfcCost*
- ***IfcWorkstation* subclass of *IfcAssembledElement***
  - *Components*: Set [0:N] of Ref. to *IfcManufacturedElement*
  - <list of worksurfaces and storage, tables, chairs, etc., excluding the vertical panels>
  - *Equipment*: Set [0:N] of Ref. to *IfcOfficeEquipment*
  - <list of office equipment>
  - *Panels*: Set [0:N] of Ref. to *IfcSystemFurniture*
  - <list of furniture types, i.e. panel types>
  - *Profile*: *IfcPolyCurve2D*
  - *Group*: Ref. to *IfcWorkstationGroup* (to be defined in the next process)
  - <represents the workstation group that the workstation belongs to >
  - *Has\_boundingBox*: *IfcBoundingBox*
  - *Workload*: *IfcWorkstationWorkload*
  - *Company\_policy*: Ref. to *IfcWorkstationCompanyPolicy*
  - *Assigned\_to*: Set [0:N] of Ref. to *IfcActor*
- ***IfcSystemFurniture* subtype of *IfcManufacturedElement***
  - *Furniture\_type*: Ref. to *IfcTypeDefinition*
  - <Panel, Worksurface, Storage>
  - *Workstation*: Set [0:N] of Ref. to *IfcWorkstation*
  - *Stored\_in*: Ref. to *IfcSpace*
- ***Att\_SystemFurnitureType* shared AttributeSet of *Furniture\_type* in *IfcSystemFurniture***
  - *Group\_code*: *IfcString* <e.g. panels, worksurfaces, storage, etc.>
  - *Width*: *IfcLength* <i.e. nominal width>
  - *Height*: *IfcLength* <i.e. nominal length>
  - *Finishing*: *IfcString* <e.g. walnut, fabric>
- ***Panel* of *IfcTypeDefinition* of *Type* in *IfcSystemFurniture***
  - target object*: *IfcSystemFurniture*
  - shared* = *Att\_SystemFurnitureType*
  - occurrence* = *Att\_Panel*
- ***Worksurface* of *IfcTypeDefinition* of *FurnitureType* in *IfcSystemFurniture***
  - target object*: *IfcSystemFurniture*
  - shared* = *Att\_SystemFurnitureType*
  - occurrence* = *Att\_Worksurface*
- ***Storage* of *IfcTypeDefinition* of *FurnitureType* in *IfcSystemFurniture***
  - target object*: *IfcSystemFurniture*
  - shared* = *Att\_SystemFurnitureType*
  - occurrence* = *Att\_Storage*
- ***Att\_Panel* occurrence AttributeSet for *FurnitureType* *Panel* in *IfcSystemFurniture***
  - *Shape*: *IfcPolyCurve2D*
  - *Opening*: *IfcPolyCurve2D*
  - *Panel\_type*: *IfcString*
  - <e.g. Acoustical, Horz\_Seg, Monolithic, Glazed, Open, Ends, Door, Screen, etc.>
  - *Thickness*: *IfcLength*
- ***Att\_Worksurface* occurrence AttributeSet for *FurnitureType* *Worksurface* in *IfcSystemFurniture***
  - *Use\_Purpose*: *IfcString*
  - <e.g. writing/reading, computer, meeting, printer, reference files, etc.>

- *Support\_type: IfcString*
- *<i.e. Freestanding or supported>*
- *HangingHeight: IfcLength*
- *Thickness: IfcLength*
- *ShapeDescription: IfcString*
- *<corner square, rectangle, etc.>*
- **Att\_Storage occurrence AttributeSet for FurnitureType Storage in IfcSystemFurniture**
  - *IsOverhead: IfcBoolean (not sure whether IfcBoolean exists in the current version)*
  - *Support\_type: IfcString*
  - *<i.e. Freestanding or supported>*
  - *Use\_Purpose: IfcString*
  - *<e.g. shelf, stationary, office supplies, personal items, etc.>*
  - *Number\_of\_drawers: IfcInteger*
  - *HangingHeight: IfcLength <if IsOverhead>*
  - *Depth: IfcLength*
- **Att\_TaskLighting occurrence AttributeSet in IfcFixture**
  - *<<to be defined>>*
- **IfcWorkstationRequirement subclass of IfcControlObject**
  - *Security\_Requirements: Set [0:N] of IfcString*
  - *Privacy\_Requirements: Set [0:N] of IfcString*
  - *Special\_Requirements: Set [0:N] of IfcString*

#### 5.10.2.1.2. Task B - Determine Basic Workstation Spaces

Define spaces of the workstation (including circulation space inside of the workstation) according to the basic requirement of human dimension standards, and company policies.

##### **Input Information:**

- *Human dimension standards (width and height)*
- *worktask zone*
- *sitting zone and chair clearance zone*
- *turnaround zone*
- *Company policies*

##### **Output Information:**

- *Space definitions*
- *circulation space*
- *workstation space dimension*

##### **Project Model Usage Requirements:**

###### **Existing Classes:**

- **IfcString (used in IfcWorkstationZone2D)**
- **IfcLength (used in IfcWorkstationZone2D)**

###### **New Classes:**

- **IfcWorkstationZone2D used by IfcWorkstation**
  - *<this class has no superclass>*
  - *Workstation\_zonetype: IfcString*
  - *<e.g. worktask, circulation, chair\_clearance, etc.>*
  - *Length: IfcLength*
  - *Width: IfcLength*
  - *In\_workstation: Ref. to IfcWorkstation*
- **IfcWorkstation**
  - *<attributes defined in previous steps + the following>*

– Zones: Set [0:N] of *IfcWorkstationZone2D*

#### 5.10.2.1.3. Task C - Define Workstation Configurations

Finalize all workstation components with all detailed dimensions and material information, and spaces.

**Input Information:**

- Workstation information
- Circulation space zone
- Workstation requirements

**Output Information:**

- Workstation configurations
- list of workstation components
  - types
  - dimensions
  - materials
- list of equipment
  - types
  - brands
  - dimensions

**Project Model Usage Requirements:**

**Existing Classes:**

- none from this step

**New Classes:**

- none from this step

#### 5.10.2.1.4. Task D - Design Workstation

Produce the workstation drawings and define the specifications according to the configurations.

**Input Information:**

- Workstation configurations

**Output Information:**

- Workstation layout drawings
  - drawing id, drawing title, author, proof, company, etc.
- Workstation design specifications
  - Materials
  - Installation requirements
  - category id, category name, item id, item name, item description, etc.

**Project Model Usage Requirements:**

**Existing Classes:**

- *IfcControlObject* (superclass of *IfcDocument*)
- *IfcDate* (used in *Att\_ElectronicDocument*, *Att\_DocumentType*)
- *IfcInteger* (used in *Att\_PaperDocument*, *Att\_DocumentType*, *Att\_Specification*)
- *IfcProductObject* (superclass of *IfcDocument*, used by *Att\_PaperDocument*)
- *IfcReal* (used in *Att\_ElectronicDocument*, *Att\_Drawing*)
- *IfcString* (used in *Att\_ElectronicDocument*, *Att\_DocumentType*, *Att\_Drawing*, *Att\_Specification*)
- *IfcTime* (used in *Att\_ElectronicDocument*)

- **IfcTypeDefinition (used in IfcDocument)**
- **IfcUnit (used in Att\_Drawing)**

**New Classes:**

- **IfcDocument** subclass of **IfcControlObject**, subclass of **IfcProductObject**
  - GenericDocumentType: *IfcTypeDefinition*
  - <used to differentiate between an electronic and a paper document>
  - DocumentType: *IfcTypeDefinition*
  - <used to differentiate between a drawing and specification, and etc.>
- **ElectronicDocument** of **IfcTypeDefinition of GenericDocumentType in IfcDocument**
  - target object = "IfcDocument"
  - shared = <none>
  - occurrence = *Att\_ElectronicDocument*
- **PaperDocument** of **IfcTypeDefinition of GenericDocumentType in IfcDocument**
  - target object = "IfcDocument"
  - shared = <none>
  - occurrence = *Att\_PaperDocument*
- **Att\_ElectronicDocument** occurrence **AttributeSet for GenericDocumentType ElectronicDocument in IfcDocument**
  - File\_name: *IfcString*
  - FileExtension\_name: *IfcString*
  - Software: *IfcString*
  - File\_size: *IfcReal* (in unit of KB)
  - Directory: *IfcString*
  - Backup\_file: Ref. to *IfcDocument*
  - Paper\_copy: Ref. to *IfcDocument*
  - Last\_save\_time: *IfcTime*
  - Last\_save\_date: *IfcDate*
  - Type: *IfcString* <hidden, read-only, etc.>
- **Att\_PaperDocument** occurrence **AttributeSet for GenericDocumentType Paper Document in IfcDocument**
  - Location: Ref. to *IfcProductObject* <more appropriate if there is something like *IfcRoot*>
  - Total\_pages: *IfcInteger*
  - Electronic\_copy: Ref. to *IfcDocument*
- **Drawing** of **IfcTypeDefinition of DocumentType in IfcDocument**
  - target object = "IfcDocument"
  - shared = *Att\_DocumentType*
  - occurrence = *Att\_Drawing*
- **Specification** of **IfcTypeDefinition of DocumentType in IfcDocument**
  - target object = "IfcDocument"
  - shared = *Att\_DocumentType*
  - occurrence = *Att\_Specification*
- **Att\_DocumentType** shared **AttributeSet for DocumentType in IfcDocument**
  - Author: *IfcString*
  - Company: *IfcString*
  - Title: *IfcString*
  - Revision\_Code: *IfcString*
  - Revision\_Number: *IfcInteger*
  - Last\_modified\_date: *IfcDate*
  - First\_created\_date: *IfcDate*
- **Att\_Drawing** occurrence **AttributeSet for DocumentType Drawing in IfcDocument**

- *Drawing\_id*: IfcString
- *Specifications*: Set [0:N] of Ref. to IfcDocument
- *Scale*: IfcReal
- *Unit*: IfcUnit
- *Related\_drawings*: Set [0:N] of Ref. to IfcDocument
- **Att\_Specification** occurrence AttributeSet for DocumentType Specification in IfcDocument
  - *Specification\_id*: IfcString
  - *General\_description*: IfcString
  - *Related\_drawings*: Set [0:N] of Ref. to IfcDocument
  - *Total\_words*: IfcInteger

#### 5.10.2.1.5. Task E - Approve Design

The process examines the design and attempts to approve it.

**Input Information:**

- Workstation layout drawings
- Workstation design specifications

**Output Information:**

- Legal/Record Documents
- approved design
- << the drawings and specs from input that are approved >>

**Project Model Usage Requirements:**

**Existing Classes:**

- none from this step

**New Classes:**

- IfcDocument

#### 5.10.2.2. IFC Model Impact

**Usage/Extensions to R1.0 object types**

- **Att\_FurnitureType**
  - <attributes defined in IFC 1.0 spec + following>
  - *Product\_code*: IfcString
  - *Width*: IfcLength <nominal overall width>
  - *Height*: IfcLength <nominal overall height>
  - *Depth*: IfcLength <nominal overall depth>
  - *Material*: IfcString
  - *Finishing*: IfcString <e.g. walnut, fabric>
- **IfcActor** (used by IfcWorkstation)
- **IfcArea** (used in IfcWorkstationCompanyPolicy)
- **IfcAssembledElement** (superclass of IfcWorkstation)
- **IfcBoolean** (used by Att\_Storage) <not sure whether IfcBoolean exists though>
- **IfcBoundingBox** (used by IfcWorkstation)
- **IfcControlObject** (superclass of IfcDocument, IfcWorkstationWorkload, IfcWorkstationRequirement, IfcWorkstationCompanyPolicy)
- **IfcCost** (used by IfcWorkstationCompanyPolicy)



- *IfcDate* (used in *Att\_ElectronicDocument*, *Att\_DocumentType*)
- *IfcFixture* (used by *Att\_TaskLighting*)
- *IfcInteger* (used by *IfcWorkstationWorkload*, *Att\_Storage*)
- *IfcInteger* (used in *IfcWorkstationWorkload*, *Att\_Storage*, *Att\_PaperDocument*, *Att\_DocumentType*, *Att\_Specification*)
- *IfcLength* (used by *Att\_SystemFurnitureType*, *Att\_Worksurface*, *Att\_Panel*, *Att\_Storage*, *IfcWorkstationZone2D*)
- *IfcManufacturedElement* (supertype of *IfcSystemFurniture*, used in *IfcWorkstation*)
- *IfcOfficeEquipment* (used by *IfcWorkstation*)
- *IfcPolyCurve2D* (used by *IfcWorkstation*, *Att\_Panel*)
- *IfcProductObject* (superclass of *IfcDocument*, used by *Att\_PaperDocument*)
- *IfcReal* (used in *IfcWorkstationWorkload*, *Att\_ElectronicDocument*, *Att\_Drawing*)
- *IfcSpace* (referenced in *IfcSystemFurniture*)
- *IfcString* (used by *IfcWorkstationRequirement*, *IfcWorkstationCompanyPolicy*, *IfcWorkstation*, *Att\_SystemFurnitureType*, *Att\_Panel*, *Att\_Worksurface*, *Att\_Storage*, *Att\_ElectronicDocument*, *Att\_DocumentType*, *Att\_Drawing*, *Att\_Specification*, *IfcWorkstationZone2D*)
- *IfcTime* (used in *Att\_ElectronicDocument*)
- *IfcTimeDuration* (used by *IfcWorkstationWorkload*)
- *IfcTypeDefinition* (used by *IfcDocument*, *IfcSystemFurniture*, *Panel*, *Worksurface*, *Storage*)
- *IfcUnit* (used in *Att\_Drawing*)

### **New object types required**

- ***IfcWorkstationWorkload***    *subtype of IfcControlObject*
  - *AverageWorkhourWeekly*: *IfcTimeDuration*
  - *TotalPaperfilesToStore*: *IfcInteger*
  - <used to determine file storage>
  - *AveragePaperfilesProducedDaily*: *IfcInteger*
  - *TotalComputerfiles*: *IfcReal*
  - <used to determine computer equipment>
  - <in unit of MB>
- ***IfcWorkstationCompanyPolicy***    *subclass of IfcControlObject*
  - *EmployeeType*: *IfcString*
  - <e.g. manager, programmer, secretary, etc.>
  - *MaxWorkstationSize*: *IfcArea*
  - *MinWorkstationSize*: *IfcArea*
  - *FurnitureStyle*: *IfcString*
  - *CostLimit*: *IfcCost*
- ***IfcWorkstation***    *subclass of IfcAssembledElement*
  - *Components*: Set [0:N] of Ref. to *IfcManufacturedElement*
  - <list of worksurfaces and storage, tables, chairs, etc., excluding the vertical panels>
  - *Equipment*: Set [0:N] of Ref. to *IfcOfficeEquipment*
  - <list of office equipment>
  - *Panels*: Set [0:N] of Ref. to *IfcSystemFurniture*
  - <list of furniture types, i.e. panel types>
  - *Profile*: *IfcPolyCurve2D*
  - *Group*: Ref. to *IfcWorkstationGroup* (to be defined in the next process)
  - <represents the workstation group that the workstation belongs to >

- *Has\_boundingBox*: *IfcBoundingBox*
- *Workload*: *IfcWorkstationWorkload*
- *Company\_policy*: Ref. to *IfcWorkstationCompanyPolicy*
- *Assigned\_to*: Set [0:N] of Ref. to *IfcActor*
- *Zones*: Set [0:N] of *IfcWorkstationZone2D*
- ***IfcSystemFurniture* subtype of *IfcManufacturedElement***
  - *Furniture\_type*: Ref. to *IfcTypeDefinition*
  - *<Panel, Worksurface, Storage>*
  - *Workstation*: Set [0:N] of Ref. to *IfcWorkstation*
  - *Stored\_in*: Ref. to *IfcSpace*
- ***Att\_SystemFurnitureType* shared *AttributeSet* of *Furniture\_type* in *IfcSystemFurniture***
  - *Group\_code*: *IfcString* <e.g. panels, worksurfaces, storage, etc.>
  - *Width*: *IfcLength* <i.e. nominal width>
  - *Height*: *IfcLength* <i.e. nominal length>
  - *Finishing*: *IfcString* <e.g. walnut, fabric>
- ***Panel* of *IfcTypeDefinition* of *Type* in *IfcSystemFurniture***
  - target object*: *IfcSystemFurniture*
  - shared* = *Att\_SystemFurnitureType*
  - occurrence* = *Att\_Panel*
- ***Worksurface* of *IfcTypeDefinition* of *FurnitureType* in *IfcSystemFurniture***
  - target object*: *IfcSystemFurniture*
  - shared* = *Att\_SystemFurnitureType*
  - occurrence* = *Att\_Worksurface*
- ***Storage* of *IfcTypeDefinition* of *FurnitureType* in *IfcSystemFurniture***
  - target object*: *IfcSystemFurniture*
  - shared* = *Att\_SystemFurnitureType*
  - occurrence* = *Att\_Storage*
- ***Att\_Panel* occurrence *AttributeSet* for *FurnitureType Panel* in *IfcSystemFurniture***
  - *Shape*: *IfcPolyCurve2D*
  - *Opening*: *IfcPolyCurve2D*
  - *Panel\_type*: *IfcString*
  - <e.g. Acoustical, Horz\_Seg, Monolithic, Glazed, Open, Ends, Door, Screen, etc.>
  - *Thickness*: *IfcLength*
- ***Att\_Worksurface* occurrence *AttributeSet* for *FurnitureType Worksurface* in *IfcSystemFurniture***
  - *Use\_Purpose*: *IfcString*
  - <e.g. writing/reading, computer, meeting, printer, reference files, etc.>
  - *Support\_type*: *IfcString*
  - <i.e. Freestanding or supported>
  - *HangingHeight*: *IfcLength*
  - *Thickness*: *IfcLength*
  - *Shape\_description*: *IfcString*
  - <corner square, rectangle, etc.>
- ***Att\_Storage* occurrence *AttributeSet* for *FurnitureType Storage* in *IfcSystemFurniture***
  - *IsOverhead*: *IfcBoolean* (not sure whether *IfcBoolean* exists in the current version)
  - *Support\_type*: *IfcString*
  - <i.e. Freestanding or supported>
  - *Use\_Purpose*: *IfcString*
  - <e.g. shelf, stationary, office supplies, personal items, etc.>
  - *Number\_of\_drawers*: *IfcInteger*
  - *HangingHeight*: *IfcLength* <if *IsOverhead*>

- *Depth: IfcLength*
- **Att\_TaskLighting** occurrence AttributeSet in IfcFixture
  - *<to be defined>*
- **IfcWorkstationRequirement** subclass of IfcControlObject
  - *Security\_Requirements: Set [0:N] of IfcString*
  - *Privacy\_Requirements: Set [0:N] of IfcString*
  - *Special\_Requirements: Set [0:N] of IfcString*
- **IfcWorkstationZone2D** used by IfcWorkstation
  - *<this class has no superclass>*
  - *Workstation\_zonetype: IfcString*
  - *<e.g. worktask, circulation, chair\_clearance, etc.>*
  - *Length: IfcLength*
  - *Width: IfcLength*
  - *In\_workstation: Ref. to IfcWorkstation*
- **IfcDocument** subclass of IfcControlObject  
subclass of IfcProductObject
  - *GenericDocumentType: IfcTypeDefinition*
  - *<used to differentiate between an electronic and a paper document>*
  - *DocumentType: IfcTypeDefinition*
  - *<used to differentiate between a drawing and specification, and etc.>*
- **ElectronicDocument** of IfcTypeDefinition of GenericDocumentType in IfcDocument
  - target object = "IfcDocument"*
  - shared = <none>*
  - occurrence = Att\_ElectronicDocument*
- **PaperDocument** of IfcTypeDefinition of GenericDocumentType in IfcDocument
  - target object = "IfcDocument"*
  - shared = <none>*
  - occurrence = Att\_PaperDocument*
- **Att\_ElectronicDocument** occurrence AttributeSet for GenericDocumentType  
**ElectronicDocument in IfcDocument**
  - *File\_name: IfcString*
  - *FileExtension\_name: IfcString*
  - *Software: IfcString*
  - *File\_size: IfcReal (in unit of KB)*
  - *Directory: IfcString*
  - *Backup\_file: Ref. to IfcDocument*
  - *Paper\_copy: Ref. to IfcDocument*
  - *Last\_save\_time: IfcTime*
  - *Last\_save\_date: IfcDate*
  - *Type: IfcString <hidden, read-only, etc.>*
- **Att\_PaperDocument** occurrence AttributeSet for GenericDocumentType Paper  
**Document in IfcDocument**
  - *Location: Ref. to IfcProductObject <more appropriate if there is something like IfcRoot>*
  - *Total\_pages: IfcInteger*
  - *Electronic\_copy: Ref. to IfcDocument*
- **Drawing** of IfcTypeDefinition of DocumentType in IfcDocument
  - target object = "IfcDocument"*
  - shared = Att\_DocumentType*
  - occurrence = Att\_Drawing*
- **Specification** of IfcTypeDefinition of DocumentType in IfcDocument
  - target object = "IfcDocument"*

*shared* = *Att\_DocumentType*  
*occurance* = *Att\_Specification*

- ***Att\_DocumentType***    ***shared AttributeSet for DocumentType in IfcDocument***
  - *Author: IfcString*
  - *Company: IfcString*
  - *Title: IfcString*
  - *Revision\_Code: IfcString*
  - *Revision\_Number: IfcInteger*
  - *Last\_modified\_date: IfcDate*
  - *First\_created\_date: IfcDate*
- ***Att\_Drawing***    ***occurance AttributeSet for DocumentType Drawing in IfcDocument***
  - *Drawing\_id: IfcString*
  - *Specifications: Set [0:N] of Ref. to IfcDocument*
  - *Scale: IfcReal*
  - *Unit: IfcUnit*
  - *Related\_drawings: Set [0:N] of Ref. to IfcDocument*
- ***Att\_Specification***    ***occurance AttributeSet for DocumentType Specification in IfcDocument***
  - *Specification\_id: IfcString*
  - *General\_description: IfcString*
  - *Related\_drawings: Set [0:N] of Ref. to IfcDocument*
  - *Total\_words: IfcInteger*
- ***IfcWorkstationGroup*** as defined in the next process “*Floor Layout of Workstations*”

### 5.10.2.3. RoadMap Issues

***Interoperability Issues (see the last section of this document for more information)***

***Applications from which information is needed:***

- *Architecture*
- *CM*
- *HVAC*
- *Building Service*

***Applications for which information is produced:***

- *Architecture*
- *CM*
- *Building Service*

***Value of software supporting this process***

- *Facilities Managers/Building Owners: Very High (in the top 3)*
- *Architecture: High (in the top 5)*
- *CM/Cost Est.: High (in the top 5)*
- *have indicated that the FM space and systems furniture information would be useful for building remodeling.*
- *Building Service: High (in the top 5)*

### ***Sponsor Software Companies***

The following organizations that develop software used by AEC end users have shown interest in developing applications which implement the process:

- *Naoki Systems Inc.*
- *Visio Corporation*

#### ***5.10.2.4. Issues identified in reviews***

##### ***No reviews recorded***

###### **Issues**

###### **Proposed resolution**

- No issues recorded
  - No resolutions recorded

#### **5.10.3. Floor Layout of Workstations for an Open Office**

The facility manager (also interior designers, architects, or furniture dealers, etc.) designs the layout of the workstations for an open office. This process is part of the entire floor furniture and equipment planning for the department(s), and occurs after typical individual workstations have been designed. CAD-based computer programs can automate the layout design process and result in cohesive, productive and suitable department offices.

The process starts from defining the employee working relationships so that closely related workstations can be adjacently assembled into workstation groups. Common departmental areas such as circulation or service areas must be considered. The adjacency relationships between the departments or workstation groups must be determined. It is usually necessary and efficient to use block plan mechanism to mark the floor area into different and big plane blocks with each representing a departmental unit, such as a research department. Workstations and groups will then be fit into certain blocks. Actual design drawings and specifications of the workstation layout will be produced based on the workstation layout configurations. The design must be approved before implementation.

##### ***5.10.3.1. Information Analysis by Task***

###### **5.10.3.1.1. Task A - Define Employee Working Relationships**

Define the individual employees working interaction patterns and meeting frequencies according to the work they perform.

###### ***Input Information:***

- *Employee Information*
  - *employee name and title*
  - *work types*
  - *employee roles - roles contain requirements for interactivity*
- *Employee work interaction*
  - *within department and outside department*
    - *with whom (or location)*
    - *daily frequency*
    - *average duration each meeting*

###### ***Output Information:***

- *Employee working relationships (in the form of table)*
  - *department title*
  - *interaction pattern summary*

###### ***Project Model Usage Requirements:***

**Existing Classes:**

- **IfcActor** (referenced in **Att\_ActorInteraction**)
- **IfcControlObject** (superclass of **IfcInteraction**)
- **IfcInteger** (used in **IfcInteraction**)
- **IfcString** (used in **IfcInteraction**, **Att\_ActorInteraction**)
- **IfcTimeDuration** (used in **IfcInteraction**)
- **IfcTypeDefinition** (used in **IfcInteraction**)

**New Classes:**

- **IfcInteraction** → subclass of **IfcControlObject**
  - Description: **IfcString**
  - Interaction\_type: **IfcTypeDefinition**
  - Frequency\_daily: **IfcInteger**
  - Average\_duration: **IfcTimeDuration**
- **ActorInteraction** → of **IfcTypeDefinition** of **Interaction\_type** in **IfcInteraction**
  - target object = "IfcInteraction"
  - shared = <none>
  - occurrence = **Att\_ActorInteraction**
- **Att\_ActorInteraction** → occurrence **AttributeSet** for **Interaction\_type ActorInteraction** in **IfcInteraction**
  - Actors: Set [2:N] of Ref. to **IfcActor**
  - Locations: **IfcString**

#### 5.10.3.1.2. Task B - Define Physically Adjacent Workstation Groups

Define the functional workstation groups according to the individual employees working relationships. A group consists of one or a few different types of typical workstations that have close working relationships, frequent interactions, and perform the same kind of function.

**Input Information:**

- Employee working relationships

**Output Information:**

- Workstation groups
  - Workstation group function name (e.g. programmer 1, marketing 2, etc.)
  - List of workstations
  - workstation group relationships (e.g. probably bubble diagram, or interaction pattern table)

**Project Model Usage Requirements:**

**Existing Classes:**

- **IfcAssembledElement** (superclass of **IfcWorkstationGroup**)
- **IfcString** (used in **IfcWorkstationGroup**)

**New Classes:**

- **IfcWorkstationGroup** → subclass of **IfcAssembledElement**
  - Functional\_name: **IfcString**
  - Workstations: Set [0:N] of Ref. to **IfcWorkstation**

#### 5.10.3.1.3. Task C - Define Departmental Common Areas

Define the areas that are shared by all employees in the department, such as common circulation and conference rooms, etc.

**Input Information:**

- *Minimum standards from company policy or architectural group:*
- *Employee Information*
  - *types, total numbers*
  - *work types*

**Output Information:**

- *Common area space requirements*
  - *circulation space*
  - *coffee room space*

**Project Model Usage Requirements:**

**Existing Classes:**

- *IfcActor (referenced by IfcWorkstationGroup)*

**New Classes:**

- *IfcWorkstationGroup*
  - *<all attributes described in the previous steps + following>*
  - *Department: Ref. to IfcActor*

**5.10.3.1.4. Task D - Produce, Evaluate and Optimize Candidate Block Plans**

Segment large spaces for workstation groups according to the relationships between the workstation groups, and the relationships between departments in case of multiple departments. Floor geometry constraints such as column grids, ceiling grids, window grids, the space footage must be taken into consideration. A floor block can contain one or more workstation groups, or one or more workstations.

**Input Information:**

- *Departmental information*
  - *name, function*
- *Bubble diagram*
  - *e.g. for interdepartmental interactions*
- *Department interaction patterns*
  - *all department names, sizes*
  - *interaction leveling (primary, secondary, tertiary, insignificant, and none)*
  - *interaction directions*
- *Common area space requirements*
- *Workstation groups*
- *Building shell information*
  - *walls*
  - *column grids*
  - *ceiling grids*
  - *window grids*
  - *floor openings (e.g. access for raised floor)*
  - *space openings (e.g. exit area)*
  - *building core (e.g. elevators, restroom, etc.)*
  - *space footage*
- *Future reserved space*
  - *footage*
  - *preferred locations*
  - *least area requirements*

**Output Information:**

- *Floor block plan*
- *floor blocks*
  - *block id, block name, block footage*
  - *owning department*
  - *list of contained workstation groups*
  - *list of contained workstations*

### **Project Model Usage Requirements:**

#### **Existing Classes:**

- *IfcArea* (used in *IfcFloorBlock*)
- *IfcControlObject* (superclass of *IfcFloorBlock*)
- *IfcPolyCurve2D* (used in *IfcFloorBlock*)
- *IfcString* (used by *IfcFloorBlock*, *Att\_SpaceType*)
- *IfcSpace* (referenced in *IfcFloorBlock*)
- *SpaceType* (extended by *Att\_SpaceType*)

#### **New Classes:**

- ***IfcFloorBlock*** → subclass of *IfcControlObject*
  - *Function\_name*: *IfcString*
  - *Workstation\_groups*: Set [0:N] of Ref. to *IfcWorkstationGroup*
  - *In\_space*: Ref. to *IfcSpace*
  - *Profile*: *IfcPolyCurve2D*
  - *Area*: *IfcArea*
- ***Att\_SpaceType*** shared AttributeSet for TypeDefinition *SpaceType* defined in R1.0
  - *Space\_name*: *IfcString*
  - *General\_description*: *IfcString*
  - *Space\_catalog*: *IfcString*

### **5.10.3.1.5. Task E - Define Floor Layout Configurations**

Define all the detailed footage of all the workstations, workstation groups and departmental boundaries.

#### **Input Information:**

- Floor block plan
- Common area space requirements
- Workstation groups
- Building shell information
- Existing inventory
  - furniture in store rooms

#### **Output Information:**

- Floor layout configurations
  - workstations
    - id, name, owning department, and user
    - footage
  - workstation groups
  - departmental boundaries

### **Project Model Usage Requirements:**

#### **Existing Classes:**

- *IfcArea* (referenced in *IfcWorkstationGroup*)
- *IfcManufacturedElement* (referenced by *IfcWorkstationGroup*, etc.)
- *IfcOfficeEquipment* (referenced by *IfcWorkstationGroup*)
- *IfcPolyCurve2D* (referenced in *IfcWorkstationGroup*)
- *IfcSpace* (referenced in *IfcWorkstationGroup*)

#### **New Classes:**

- ***IfcWorkstationGroup*** extended from first step
  - {{all items described in previous steps + the following}}



- *In\_floor\_block*: Ref. to *IfcFloorBlock*
- *In\_space*: Ref. to *IfcSpace*
- *Profile*: *IfcPolyCurve2D*
- *Total\_area*: *IfcArea*
- *Shared\_furniture*: Set [0:N] of Ref. to *IfcManufacturedElement*
- *<shared furniture is not part of any workstations in the workstation group, e.g. a table for supporting a shared printer>*
- *Shared\_equipment*: Set [0:N] Ref. to *IfcOfficeEquipment*
- *<shared equipment is not part of any workstations in the workstation group, e.g. a shared printer>*
- *Workstation\_groups*: Set [0:N] of Ref. to *IfcWorkstationGroup*
- *<a workstation group can contain other groups>*

#### 5.10.3.1.6. Task F - Design Floor Layout

Produce the workstation layout drawings and define the specifications.

**Input Information:**

- *Floor layout configurations*
- *Existing inventory*
- *Architectural layout*

**Output Information:**

- *Floor layout drawings*
  - *drawing id, name, author, proof, company, etc.*
- *Floor layout specifications*
  - *Materials*
  - *Installation requirements*

**Project Model Usage Requirements:**

**Existing Classes:**

- *<none in this step>*

**New Classes:**

- *IfcDocument as defined in the last step of the process “Design of Workstations”*

#### 5.10.3.1.7. Task G - Implement

After the design has been approved, implement the design based on the drawings and specifications.

**Input Information:**

- *Existing inventory*
- *Floor layout drawings*
- *Floor layout specifications*

**Output Information:**

- *As-built drawings*

**Project Model Usage Requirements:**

**Existing Classes:**

- *<none in this step>*

**New Classes:**

- *IfcSpaceInventory (as defined in the 1<sup>st</sup> process: Occupancy Planning)*
- *IfcFurnitureInventory (as defined in the 1<sup>st</sup> process: Occupancy Planning)*
- *IfcEquipmentInventory (as defined in the 1<sup>st</sup> process: Occupancy Planning)*

### 5.10.3.1.8. Task H - Update

This is an on-going process that occurs during the course of design implementation. Inventories are updated. Drawings are changed and as-built drawings are produced overtime.

**Input Information:**

- Existing inventory
- As-built drawings

**Output Information:**

- Updated inventories

**Project Model Usage Requirements:**

**Existing Classes:**

- <none in this step>

**New Classes:**

- <none in this step>

### 5.10.3.2. IFC Model Impact

**Usage/Extensions to R1.0 object types**

- *IfcActor* (referenced by *IfcWorkstationGroup*, *Att\_ActorInteraction*)
- *IfcArea* (referenced in *IfcWorkstationGroup*, *IfcFloorBlock*)
- *IfcAssembledElement* (superclass of *IfcWorkstationGroup*)
- *IfcControlObject* (superclass of *IfcFloorBlock*, *IfcInteraction*)
- *IfcInteger* (used in *IfcInteraction*)
- *IfcManufacturedElement* (referenced by *IfcWorkstationGroup*, etc.)
- *IfcOfficeEquipment* (referenced by *IfcWorkstationGroup*)
- *IfcPolyCurve2D* (referenced in *IfcWorkstationGroup*, *IfcFloorBlock*)
- *IfcSpace* (referenced in *IfcFloorBlock*, *IfcWorkstationGroup*)
- *SpaceType* (extended by *Att\_SpaceType*)
- *IfcString* (used by *IfcFloorBlock*, *Att\_SpaceType*, *IfcInteraction*, *Att\_ActorInteraction*, *IfcWorkstationGroup*)
- *IfcTimeDuration* (used in *IfcInteraction*)
- *IfcTypeDefinition* (used in *IfcInteraction*)

**New object types required**

- *IfcInteraction* → subclass of *IfcControlObject*
  - Description: *IfcString*
  - Interaction\_type: *IfcTypeDefinition*
  - Frequency\_daily: *IfcInteger*
  - Average\_duration: *IfcTimeDuration*
- *ActorInteraction* → of *IfcTypeDefinition* of *Interaction\_type* in *IfcInteraction*
  - target object = "IfcInteraction"
  - shared = <none>
  - occurance = *Att\_ActorInteraction*
- *Att\_ActorInteraction* → occurance *AttributeSet* for *Interaction\_type ActorInteraction* in *IfcInteraction*

- *Actors*: Set [2:N] of Ref. to *IfcActor*
- *Locations*: *IfcString*
- ***IfcWorkstationGroup* → subclass of *IfcAssembledElement***
  - *Functional\_name*: *IfcString*
  - *Workstations*: Set [0:N] of Ref. to *IfcWorkstation*
  - *Department*: Ref. to *IfcActor*
  - *In\_floor\_block*: Ref. to *IfcFloorBlock*
  - *In\_space*: Ref. to *IfcSpace*
  - *Profile*: *IfcPolyCurve2D*
  - *Total\_area*: *IfcArea*
  - *Shared\_furniture*: Set [0:N] of Ref. to *IfcManufacturedElement*
  - <shared furniture is not part of any workstations in the workstation group, e.g. a table for supporting a shared printer>
  - *Shared\_equipment*: Set [0:N] Ref. to *IfcOfficeEquipment*
  - <shared equipment is not part of any workstations in the workstation group, e.g. a shared printer>
  - *Workstation\_groups*: Set [0:N] of Ref. to *IfcWorkstationGroup*
  - <a workstation group can contain other groups>
- ***IfcFloorBlock* → subclass of *IfcAssembledElement***
  - *Function\_name*: *IfcString*
  - *Workstation\_groups*: Set [0:N] of Ref. to *IfcWorkstationGroup*
  - *In\_space*: Ref. to *IfcSpace*
  - *Profile*: *IfcPolyCurve2D*
  - *Area*: *IfcArea*
- ***Att\_SpaceType* shared *AttributeSet* for *TypeDefinition SpaceType* defined in R1.0**
  - *Space\_name*: *IfcString*
  - *General\_description*: *IfcString*
  - *Space\_catalog*: *IfcString*
- ***IfcDocument* as defined in the last step of the process “Design of Workstations”**
- ***IfcWorkstation* as defined in the process “Design of Workstations”**
- ***IfcSpaceInventory* (as defined in the 1<sup>st</sup> process: *Occupancy Planning*)**
- ***IfcFurnitureInventory* (as defined in the 1<sup>st</sup> process: *Occupancy Planning*)**
- ***IfcEquipmentInventory* (as defined in the 1<sup>st</sup> process: *Occupancy Planning*)**

### 5.10.3.3. RoadMap Issues

**Interoperability Issues (see the last section of this document for more information)**

**Applications from which information is needed:**

- *Architecture*
- *CM*
- *HVAC*
- *Building Service*

**Applications for which information is produced:**

- *Architecture*
- *CM*
- *Building Service*

### ***Value of software supporting this process***

- *Facilities Managers/Building Owners: Very High (in the top 3)*
- *Architecture: High (in the top 5)*
- *CM/Cost Est.: High (in the top 5)*
- *have indicated that the FM space and systems furniture information would be useful for building remodeling.*
- *Building Service: High (in the top 5)*
- *HVAC:*

### ***Sponsor Software Companies***

The following organizations that develop software used by AEC end users have shown interest in developing applications which implement the process:

- *Naoki Systems Inc.*
- *Visio Corporation*

### ***5.10.3.4. Issues identified in reviews***

#### ***No reviews recorded***

##### **Issues**

##### **Proposed resolution**

- No issues recorded
  - No resolutions recorded

### ***5.10.3.5. Information needed by FM from other phases***

FM-4 is currently concerned with only three processes

- Occupancy planning
- Design of Workstations
- Layout of Workstations

The info requirements listed below is not limited to these three processes

#### ***5.10.3.5.1. Building Systems Group***

Building systems performance

- Performance characteristics of all mechanical systems (as level of detail typically specified by architect)

HVAC - Air exchanges per hour

- Temperature ranges
- Controls/location/zones
- Operating/maintenance instructions (Also from contractor)
- Solar performance

Mechanical

- restroom/wastewater capacities (also from architect for non mechanical aspects)

Electrical

- Circuit capacities
- locations
- switching

Energy use

- Average energy use
- Control of energy use

Elevator and other vertical transport systems

- Capacities
- Operational characteristics
- Special features/uses

Fire protection

- Zoning/fire ratings
- Location/type

Handicapped features/requirements

- All operational manuals, maintenance, warranty, service contact, inspection info (Also from architecture group)

### 5.10.3.5.2. Architecture Group

A. General Building Information

- Programming info
- "Owners intent"
- When built, Cost, Sq ft.
- Usable, rentable, common space
- Historical issues
- Utilities
  - *Suppliers, contacts*
  - *main controls, shut-off valves, etc.*
- Landscaping & Grounds management
  - *Irrigation system (plan and controls)*
  - *Surface water management' (storm water detention)*

B. Equipment details (Also from mechanical group)

- Operation/training-manuals, materials, schedules
- Warranty, contacts
- Service, customer support, parts & supplies
- Connectivity, Redundancy (e.g. is this the only one)

C. Site and Location Information

- Transportation, access, parking
  - *Registered transportation management plan*
- Disaster plans, flood plain issues
- Community services
  - *Police, traffic enforcement*
  - *EPA office*
  - *Fire station*
  - *Medical*
  - *News media*

D. Building shell information

- Wall, window wall, roofing

E. Systems

- Status and Condition information
- Maintenance records/ schedules
- Replacements- required, planned, desired
- Required service
- Signage plans / guidelines

F. Occupancy

- Operating costs, issues
- Leasing, renting
- Taxes
- Sanitary service
- Water utilities, storm water management
- Insurance

- Local gov inspections/assessments
- Security
- G. Communication & Computing
  - Telephone/ telecommunications contracts/services
  - Service providers/ access/ capacity
  - Networking & cabling
- H. Hazardous materials, waste
  - Management
  - Compliance
- I. Space Information
  - 1) Existing architectural layout and building components (“as-builts”)
    - *Walls, doors, comfort controls and zones, floors, signing, finishes, colors*
  - 2) Architectural performance
    - *Architectural rationale (spaces, lighting, colors - how they “work”)*
    - *Illumination*
    - *Sound/acoustics*
  - 3) Structural (from structural group)
    - *Structural elements and layout*
    - *Layman description of how the structure works, what is important*
    - *Siesmic design stds*
    - *Design loads*
  - 4) Architectural Maintenance
    - *Schedule*
    - *Cost*
  - 5) Mechanical & Ele trical (related to spaces)
    - *Elements, layout, capacities*
  - 6) Safety
  - 7) Security
    - *Penetrations, alarms, monitors*
    - *Locks, keyplans*
  - 8) Access and escape
  - 9) Use and code guidelines
  - 10) What is unusual, what is important?

## 5.11. [SI-1] Photo Accurate Visualization

### 5.11.1. Photo Accurate Visualization

Visualization is performed by architects, lighting engineers and renderers with computer and electronic visualization skills. It can be used at any point in the building, lighting or interior design process, as well as during the occupancy of the building. Three-dimensional representation of a space or a building is the starting point; information about surface materials and sources of light is required for the simulation. The former can be obtained from manuals, manufacturers' catalogues, databases, etc. The later is available in technical literature and from specialised computer models. The resulting images (renderings or animations) and data (luminance) can be used for many purposes: communication about the “looks” of a design solution to making design and engineering decisions.

#### 5.11.1.1. Information Analysis by Task

In the design of a building or other structure, the architect or designer may want to see what the building or the structure will look like, or may want to render images for the client's benefit. Such visualization may be desired at any time from the earliest architectural design or retrofitting to the final interior design.

Visualization is the key to solving lighting and daylighting design problems, and is also important in assessing building performance and human comfort issues. IFC support of this process may reduce input preparation time by 75-85% process (through automatic acquisition of building geometry and all surface properties) and thus make the use of the corresponding applications economically feasible.

#### **5.11.1.1.1. Task A - Select Surface Materials**

Select materials to associate with building surfaces, and define material properties such as reflectance, transmittance, colors, patterns, texture, etc. Input is the three-dimensional building model; output are the materials associated with each modeled surface or solid.

***Input Information:***

- *Three-dimensional building model*

***Output Information:***

- *Materials associated with each 3-d surface (list)*

#### **1.1.1.1.1 Task B - Specify Lighting**

In order to perform a valid visual simulation, it is necessary to select and place light sources (luminaires) and specify daylight conditions. Luminaires may be selected from manufacturer's catalogs, and the sun and sky conditions may be taken from a set of quantitative models appropriate to the building site.

***Input Information:***

- *Light source configuration and distribution data*
- *Daylight models for this site*

***Output Information:***

- *Positions and types of light sources (drawings and specs)*
- *Sky distribution, solar position (from time of day and year)*

#### **1.1.1.1.2 Task C - Rendering**

Compute 2-dimensional images for visual evaluation.

***Input Information:***

- *Selected views for this model*
- *Animation path (optional)*

***Output Information:***

- *Two-dimensional color images (floating point)*
- *Luminance and isolux contour plots (optional)*
- *Animations (optional)*

#### **1.1.1.1.3 Task D - Evaluate Results**

Once one or more images have been produced, it is often desirable to go back and iterate on the material selection and/or light source selection and placement

***Project Model Usage Requirements:***

***Existing Classes:***

- *all that define the geometry of the space or building in the simulation*

***New Classes:***

- *Light source*
- *Surface*

### 5.11.1.2. IFC Model Impact

#### **Usage/Extensions to R1.0 object types**

- **IfcMaterialLayer**
  - *bidirectional scattering distribution function (BSDF) or model thereof*  
*includes: spectral reflectance and transmittance, specularity and roughness*
  - *polarization properties*

#### **New object types required**

- **IfcLightSource**
  - *Spectral powerdistribution (lamp)*
  - *Luminaire geometry*
  - *Photometric output distribution*
- **IfcSurface**
  - *General shape (e.g., polygon, sphere, etc.)*
  - *Dimensions*
  - *Material and parameterization*

### 5.11.1.3. RoadMap Issues

#### **Interoperability Issues**

##### **Applications from which information is needed:**

- *CAD software*

##### **Applications for which information is produced:**

- *to be determined*

#### **Value of software supporting this process**

- *{{In this section, please allow for the other domains to rank your process in order of precedence for their domain, this allows us to examine the issue on a group as well as an individual level}}*
- *{{ discipline 1 }} - {{value from 1-10, 1 being the highest value, 10 being the lowest}}*
- *{{ discipline 2 }} - {{value from 1-10}}*

#### **Sponsor Software Companies**

The following organizations that develop software used by AEC end users have shown interest in developing applications which implement the process:

- *LBNL (Radiance 3.0)*
- *Lightscape Technologies*
- *Arris Integra*
- *3DStudio (rendering)*
- *Pixar (Renderman)*
- *Lightworks*
- *others*



#### **5.11.1.4. Issues identified in reviews**

##### ***No reviews recorded***

##### **Issues**

##### **Proposed resolution**

- No issues recorded
- No resolutions recorded

### **5.12. [XM-2] Project Document Management**

#### **5.12.1. Project Document Management**

##### **5.12.1.1. Information Analysis by Task**

Project Document Management refers to all information pertaining to the documents used to estimate, bid, purchase, and manage the building process as well as for use within the Facilities Management domain. This data identifies the document, the author of the document, changes to the document since the last change, and relationships to other documents.

- *Who performs this process? All software vendors that use drawings, specifications, and sketches during the life cycle of a project. This would include CAD, estimating, scheduling, management, and facilities management software vendors.*
- *When in the project lifecycle it is performed? From the very inception of the project, where these documents are used to define the project, through the construction of the project with all of its changes, through the management of the "building" once the project is complete.*
- *What other processes does it relate to (input from/output to/controlled by)? This process starts in the creation and modification of the documents and outputs to all processes that use the documents as a means of identification. This would include estimating where changes to the work are usually quantified by document, management, where the documents are used to control the flow of work on a project and establish what is being built by document, and Facilities Management, where documents are the prime method of identifying actual conditions in a facility.*

For Contract Drawings and Sketches, the Architect start this process during the creation of the drawings by entering information regarding the drawings. This information would include:

- Document type
- Document Id
- Description
- Document Date
- Revision Number
- Revision Date
- Document Type and Id of related documents. This might include relationships between drawings and sketches, or even objects in the drawings with objects in a sketch or maybe the object as identified within a specification.
- Document Author
- Document Revision Author
- Bulletin/Addenda reference
- Related Documents, Sections, Details, Objects

In addition, the creation of objects onto the drawing will also trigger the saving of information regarding the objects. This process is handled by the CAD software. The information saved would include:

The List of Objects

- Original
- Added
- Deleted
- Modified
- Dates for all of these
- Revisions for all of these
- Possible relationships between the objects of this drawing and the objects on other drawings, specifications, and sketches created by the Architect.

Similar information would be required for implementation of the same for Specifications. These will not be modeled here.

Once the information is provided to the document, software using drawings can take advantage of the information to organize the processes of change throughout a project as well as the interconnection of information between project contract documents, such as between drawings, drawing sections, drawing details, sketches, and specification sections.

#### **5.12.1.1.1. Task A - Identifications Supplied By Author**

The Architect or author of the document provides information regarding the document he/she is creating.

***Input Information:***

- *The document type, whether it is a drawing, specification, sketch, etc.*
- *The document details such as Drawing Number, Drawing Date, Author, etc.*

***Project Model Usage Requirements:***

*To be determined*

#### **5.12.1.1.2. Task B - Identifications Supplied by Vendor**

The CAD or Specifications Software Vendor (or Author?) would assign an identification and information regarding those objects within the document.

***Input Information:***

- *Object Types*
- *Object Specific information such as Object Identification, Creation Date, Author, etc.*

***Project Model Usage Requirements:***

*To be determined*

#### **5.12.1.1.3. Task C - Document Modifications**

The CAD or Specifications Software Vendor (or Author?) would keep track of modifications made to the documents with respect to Revision and date.

***Input Information:***

- *Type of Modification, such as created, modified, deleted*
- *Modification Details, such as Creation Date, Author of Change, Change Identifications*

***Project Model Usage Requirements:***

*To be determined*

#### **5.12.1.1.4. Task D - Identify Relationships with Other Documents**

A link is then made to the appropriate documents, where information is contained not within the current document.

***Input Information:***

- *Document Type*
- *Document Identification*

- *Internal Document Reference*

**output Information:**

- *Document Identification*
- *Document Type*
- *Internal Document Reference*
- *Change Information*

**Project Model Usage Requirements:**

*To be determined*

#### **5.12.1.1.5. Task E - Estimating**

Estimating software packages can now use the information provided above to estimate changes to the project on a document by document and change by change basis. This would include changes made over multiple documents since the change identification can be identical between documents.

**output Information:**

- *Document Type*
- *Document Identification*
- *Internal Document Reference*
- *Change Information*

**Project Model Usage Requirements:**

*To be determined*

#### **5.12.1.1.6. Task F - Scheduling**

Scheduling software packages can now use the information provided above to estimate changes to the project schedule on a document by document and change by change basis. This would include changes made over multiple documents since the change identification can be identical between documents.

**output Information:**

- *Document Type*
- *Document Identification*
- *Internal Document Reference*
- *Change Information*

**Project Model Usage Requirements:**

*To be determined*

#### **5.12.1.1.7. Task G - Project Management**

Project Management software packages can now use the information provided above to estimate changes to the project on a document by document and change by change basis. This would include changes made over multiple documents since the change identification can be identical between documents.

**output Information:**

- *Document Type*
- *Document Identification*
- *Internal Document Reference*
- *Change Information*

**Project Model Usage Requirements:**

*To be determined*

### **5.12.1.2. IFC Model Impact**

#### **Extensions to R1.5.1 object types**

*To be determined*

#### **New object types**

*Document Type Object*

*Document Object*

### **5.12.1.3. RoadMap Issues**

#### **Interoperability issues**

##### **Applications from which information is needed:**

- *Architects*
- *CAD Software*
- *Engineers (those who create contract documents)*
- *Facilities Management*
- *Specifications Software Vendors*

##### **Applications for which information is produced:**

- *Owners*
- *Architects*
- *Engineers*
- *Construction Professionals*
- *Estimators*
- *Purchasers*
- *Facilities Management*

#### **Value of software supporting this process**

- *Construction Professionals {I consider this my highest priority - a definite 10}*

#### **Sponsor Software Companies**

The following organizations that develop software used by AEC end users have shown interest in developing applications which implement the process:

- *Frontrunner, LLC*
- *Turner Corporation Internal Development*
- *Autodesk*
- *Bentley Systems (preliminary interest)*

### **5.12.1.4. Issues identified in reviews**

#### **No reviews recorded**

##### **Issues**

##### **Proposed resolution**

- No issues recorded
  - No resolutions recorded

## 6. Object Type Definition Tables

### 6.1. [AR-1] Architectural Model Extensions

#### 6.1.1. Object Types

##### 6.1.1.1. Building Shell Design

	Object Type Name	Interface name	OPT IN DER					
Subtype of		Attribute / Relation name		Data Type/Related Object Type	Min	Max	Default	Definition
IfcBuildingElement (an assembly, defined using IfcRelAssemblesElements)	1	<b>IfcCurtainWall</b>						Exterior wall of a building which is an assembly of components, hung from the edge of the floor/roof structure rather than bearing on a floor
		<b>I_CurtainWall : ConstructionDetails, SpecSection</b>						
		ConstructionDetails		LIST [0..?] OF IfcDocumentReference	n/a	n/a	empty list	List of references to a detail drawings
		SpecSection	OPT	IfcDocumentReference	n/a	n/a	NIL	Document reference to specification section
IfcBuildingElement	2	<b>IfcCurtainWallElement</b>						Component in an building curtain wall
		<b>I_CurtainWallElement : GenericType</b>						
		GenericType		IfcCurtainWallElementTypeEnum	GlazingPanel	OverhangShade	GlazingPanel	Generic type which keys to type definition for all primary types of elements in Curtain walls. Anything missed will be represented using IfcProxy.
IfcBuildingElement	3	<b>IfcPermeableOpeningCover</b>						Permeable cover for an opening which allows airflow (definition BS 6100)
		<b>I_PermeableOpeningCover : GenericType</b>						
		GenericType		IfcPermeableOpeningCoverTypeEnum	Grate	Screen	Screen	Predefined generic types are specified in an Enum. Type driven Psets are defined for each generic type (as the required attributes differ). The GenericType for a given instance drives determines the type of Pset attached at runtime through the associated TypeDef object (defined at the IfcObject supertype).
IfcFloor	4	<b>IfcRamp</b>						Inclined floor surface
		<b>I_Ramp : Length, Width, Slope, Landings, Railings, ConstructionDetails, SpecSection</b>						
		Length		IfcPositiveLengthMeasure	0.0	see type	0.0	length of ramp
		Width		IfcPositiveLengthMeasure	0.0	see type	0.0	width of ramp
		Slope		IfcAngleMeasure	0.0	see type	0.0	slope of ramp - relative to horizontal (non-sloping) floor
		Landings		LIST [0..2] OF Ref [IfcStairRampLanding]	n/a	n/a	empty list	References to landing objects that are either end of ramp.
		Railings		LIST [0..?] OF Ref [IfcRailing]	n/a	n/a	empty list	List of reference railings (either handrails or guardrails) for this ramp
		ConstructionDetails		LIST [0..?] OF Ref [IfcDocumentReference]	n/a	n/a	empty list	List of references to drawing documents which define construction details (especially dealing with drainage)
		SpecSection		Ref [IfcDocumentReference]	n/a	n/a	NIL	Reference to a section in the construction specifications

### 6.1.1.2. Building Core Design

\*\* None defined for this process \*\*

### 6.1.1.3. Stair Design

	Object Type Name	Interface name	OPT INV DER					
Subtype of		Attribute / Relation name		Data Type/Related Object Type	Min	Max	Default	Definition
IfcBuildingElement (Assembly using IfcRelAssemblesElement s)	9	<b>IfcStair</b>						Assembly of building components allowing occupants to walk (step) from Floor (or Landing) to another at a different elevation.
		<b>I_Stair : GenericType, EnclosingSpace, Protection</b>						
		<b>I_StairComponents(Landings, Flights)</b>						
		GenericType		IfcStairTypeEnum	FireStair	Standard AccessSt air	Standard AccessSt air	Predefined generic types are specified in an Enum. Type driven Psets are defined for each generic type (as the required attributes differ). The GenericType for a given instance drives determines the type of Pset attached at runtime through the associated TypeDef object (defined at the IfcObject supertype).
		EnclosingSpace	OPT	Ref [IfcSpace]	n/a	n/a	NIL	Reference to the Space object in which this stair is enclosed (if any)
		Protection		BOOLEAN	FALSE	TRUE	FALSE	selection of protected or not protected stair set
		Landings		LIST [0:?] OF Ref [IfcStairRampLanding]	n/a	n/a	empty list	list relationships - landings included in this stair assembly
		Flights		LIST [1:?] OF Ref [IfcStairFlight]	n/a	n/a	empty list	list relationships - flights included in this stair assembly
IfcBuildingElement (Assembly using IfcRelAssemblesElement s)	10	<b>IfcStairFlight</b>						Assembly of building components in a single "run" of stair steps (not interrupted by a landing). Also includes stringers, handrails, guardrails, etc.
		<b>I_StairFlight : HeadRoom, Steps, Stringers, Railings, Landings</b>						
		HeadRoom		IfcPositiveLengthMeasure	0.0	see type	0.0	Headroom clearance
		Steps		LIST [1:?] OF IfcStairStep	n/a	n/a	one step minimum	List of references to Stair Steps objects
		Stringers		LIST [0:?] OF IfcBeam	n/a	n/a	empty list	List of references to stringers for this flight. Note: stringers are a type of Beam
		Railings		LIST [0:?] OF IfcRailing	n/a	n/a	empty list	List of references to handrails and guardrails
		Landings		LIST [0:2] OF Ref [IfcStairRampLanding]	n/a	n/a	empty list	list relationships - landings included in this stair assembly
IfcBuildingElement	11	<b>IfcStairStep</b>						Individual step (riser + tread) within a stair flight. Allows human occupants to ascend or descend from one floor to another (at different elevations).
		<b>I_StairStep : RiserHeight, TreadDepth, TreadMaterial, NosingMaterial, ConstructionDetail</b>						
		RiserHeight		IfcPositiveLengthMeasure	0.0	30 cm	0.0	Distance from tread to tread
		TreadDepth		IfcPositiveLengthMeasure	0.0	30 cm	0.0	Distance from the front of the tread to back of the tread
		TreadMaterial		INTEGER	1	see type	1	Composition of tread. Index into the IfcMaterialList defined at the IfcBuildingElement supertype
		NosingMaterial		INTEGER	1	see type	1	Composition of tread. Index into the IfcMaterialList defined at the IfcBuildingElement supertype
		ConstructionDetail		Ref [IfcDocumentReference]	n/a	n/a	NIL	Reference to construction detail drawing
IfcFloor	12	<b>IfcStairOrRampLanding</b>						Floor section to which one or more stair flights connects. May or may not be adjacent to a building storey floor.
		<b>I_StairOrRampLanding : PartOfStair, ConnectedFlights, HeadRoom, ConstructionDetails, Railings</b>						

						PartOfStair	INV	Ref [IfcStair]	n/a	n/a	NIL	reference to the stair for which this landing is a component (inverse for Landings)
						ConnectedFlights	INV	LIST [0..?] OF Ref [IfcStairFlight]	n/a	n/a	empty list	list of Stair Flights connected to this landing
						HeadRoom		IfcPositiveLengthMeasure	0.0	see type	0.0	Headroom clearance
						ConstructionDetail		LIST [0..?] OF Ref [IfcDocumentReference]	n/a	n/a	NIL	Reference to construction detail drawing
						Railings		LIST [0..?] OF IfcRailing	n/a	n/a	empty list	List of references to handrails and guardrails for this landing
Subtype from IfcBuiltIn	13	<b>IfcRailing</b>										
						<b>I_Railing : GenericType, RailingHardware</b>						
						GenericType		IfcRailingTypeEnum	Handrail	Balustrade	Handrail	Predefined generic types are specified in an Enum. Type driven Psets are defined for each generic type (as the required attributes differ). The GenericType for a given instance drives determines the type of Pset attached at runtime through the associated TypeDef object (defined at the IfcObject supertype).
						RailingHardware		LIST [0..?] OF IfcBuiltInAccessory	n/a	n/a	empty list	List of references to accessory/mounting hardware for this railing.
Subtype from IfcBuiltIn	14	<b>IfcCabinet</b>										
						<b>I_Cabinet : GenericType, CabinetHardware</b>						
						GenericType		IfcCabinetTypeEnum	Bathroom	Office	Bathroom	Predefined generic types are specified in an Enum. Type driven Psets are defined for each generic type (as the required attributes differ). The GenericType for a given instance drives determines the type of Pset attached at runtime through the associated TypeDef object (defined at the IfcObject supertype).
						CabinetHardware		LIST [0..?] OF IfcBuiltInAccessory	n/a	n/a	empty list	List of references to accessory hardware for this cabinet.
Subtype from IfcBuiltIn	15	<b>IfcCounterOrShelf</b>										
						<b>I_CounterOrShelf : GenericType, CounterOrShelfHardware</b>						
						GenericType		IfcCounterOrShelfTypeEnum	Bathroom Counter	Shelf	Shelf	Predefined generic types are specified in an Enum. Type driven Psets are defined for each generic type (as the required attributes differ). The GenericType for a given instance drives determines the type of Pset attached at runtime through the associated TypeDef object (defined at the IfcObject supertype).
						CounterOrShelfHardware		LIST [0..?] OF IfcBuiltInAccessory	n/a	n/a	empty list	List of references to accessory hardware for this counter or shelf.

#### 6.1.1.4. Public Toilet Design

	Object Type Name	Interface name	OPT INV DER						
Subtype of		Attribute / Relation name		Data Type/Related Object Type	Min	Max	Default	Definition	
IfcBuildingElement	16	<b>IfcPlumbingFixture</b>							
		<b>I_PlumbingFixture : GenericType</b>							
		GenericType		IfcPlumbingFixtureType	Faucet	Dishwasher	Faucet	Predefined generic types are specified in an Enum. Type driven Psets are defined for each generic type (as the required attributes differ). The GenericType for a given instance drives determines the type of Pset attached at runtime through the associated TypeDef object (defined at the IfcObject supertype).	
IfcBuildingElement	17	<b>IfcElectricalFixture</b>							

#### 6.1.1.5. Roof Design

Copyright © International Alliance for Interoperability - 1996-1999



Copyright © International Alliance for Interoperability - 1996-1999

IfcRelationship	7	IfcRelJoinsElements																Expansion joint, edge condition, control joint.
											I_RelJoinsElements : RelatingObject, RelatedObjects, JointType, RangeOfMovement, ConstructionDetails, SpecSection, WaterProofing, FireRating, VentilationRequired, ManufactureInfo, ObjectLifeCycle							
											RelatingObject		Ref [IfcBuildingElement]	n/a	n/a	NIL	Primary object at the joint defined by this relationship	
											RelatedObjects		LIST [1:?] OF Ref [IfcBuildingElement]	n/a	n/a	empty list	Secondard objects joined at the joint defined by this relationship	
											JointElements		LIST [0:?] OF Ref [IfcBuildingElement]	n/a	n/a	empty list	Objects that make up the joint (fill the gap)	
											JointType		IfcJointTypeEnum	control	expansion	control	Purpose of joint	
											RangeOfMovement		IfcPositiveLengthMeasure	0.00	n	0.00	Distance the joint can open before failing	
											ConstructionDetails		LIST [0:?] OF Ref [IfcDocumentReference]	na	na	na	List of references to drawing documents which define construction details	
											SpecSection		IfcDocumentReference	na	na	NIL	Reference to a section of the specification	
											WaterProofing		BOOLEAN	FALSE	TRUE	FALSE	flag that indicates that the joint should be waterproof or not	
											FireRating		IfcTimeDurationMeasure	see type	see type	60 min	Time duration for fire resistance the roof assembly is rated	
											VentilationRequired		BOOLEAN	FALSE	TRUE	FALSE	Is ventilation required for this joint?	
											ManuafactureInfo		IfcOccurrencePropertySet (Pset_ManufactureInfo)	n/a	n/a	NIL	Reference to information about the manufacturer of this joint assembly (if any). ID of Pset_ManufactureInfo attached to object in the Extension Psets list	
											ObjectLifeCycle		IfcOccurrencePropertySet (Pset_ObjectLifeCycle)	na	na	na	Reference to ObjectLifeCycle Pset - attached to object in the Extension Pset list	
IfcBuildingElement	8	IfcScreen																
											I_Screen : GenericType							
											GenericType		IfcScreenTypeEnum	ScreenAssembly	ScreenDoorOrGate	ScreenPanel	Predefined generic types are specified in an Enum. Type driven Psets are defined for each generic type (as the required attributes differ). The GenericType for a given instance drives determines the type of Pset attached at runtime through the associated TypeDef object (defined at the IfcObject supertype).	

### 6.1.1.6. Componentization of Doors/Windows

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

Copyright © International Alliance for Interoperability - 1996-1999

## 6.1.2. Type Definitions

#	TypeDef Name	Description or definition				
	Class being Typed					
		Generic Type				
		Specific Type	Set #	Shared Pset	Set #	Occurrence Pset
1	<b>BeamType</b>	Supports the definition of standard Beam types and associated PropertySets				
	lfcBeam	Common Pset			#N/A	Pset_BeamCommon
		<b>StairStringer</b>				
		< Any value >			4	Pset_BeamStairStringer
2	<b>BuiltInAccessoryType</b>	Supports the definition of standard Accessory types and associated PropertySets				
	lfcBuiltInAccessory	Common Pset			1	Pset_AccessoryCommon
		<b>Bathroom</b>				
		< Any value >			2	Pset_AccessoryBathroom
		<b>DoorOrWindowHardware</b>	3	Pset_AccessoryDoorOrWindowHardware		
3	<b>CabinetType</b>	Supports the definition of standard Cabinet types and associated PropertySets				
	lfcCabinet	Common Pset			5	Pset_CabinetCommon
		<b>Bathroom</b>				
		< Any value >	6	Pset_CabinetBathroom		
		<b>Kitchen</b>				
		< Any value >	7	Pset_CabinetKitchen		
		<b>Storage</b>				
		< Any value >	8	Pset_CabinetStorage		
		<b>Laundry</b>				
		< Any value >	9	Pset_CabinetLaundry		
		<b>Office</b>				
		< Any value >	10	Pset_CabinetOffice		
4	<b>CounterType</b>	Supports the definition of standard Counter types and associated PropertySets				
	lfcCounterOrShelf	Common Pset			11	Pset_CounterOrShelfCommon
		<b>Counter</b>				
		< Any value >			12	Pset_Counter
		<b>Shelf</b>				
		< Any value >			47	Pset_Shelf
5	<b>CoveringType</b>	Supports the definition of standard Covering types and associated PropertySets				
	lfcCovering	Common Pset			#N/A	Pset_CoveringCommon
		<b>CoveringMillwork</b>				
		< Any value >			13	Pset_CoveringMillwork

6	<b>CurtainWallElementType</b>	Supports the definition of standard CurtainWallElement types and associated PropertySets			
	<b>IfcCurtainWallElement</b>	Common Pset		14	Pset_CurtainWallElementCommon
		<b>Clad Panels</b>			
		< Any value >	15	Pset_CurtainWallCladPanel	
		<b>Glazing Panel</b>			
		< Any value >	16	Pset_CurtainWallGlazingPanel	
		<b>Ornamental Projection</b>			
		< Any value >	17	Pset_CurtainWallProjectionOrnamental	
		<b>Shade or Overhang</b>			
			18	Pset_CurtainWallShadeOverhang	
		<b>Spandrel Panel</b>			
			19	Pset_CurtainWallSpandrelPanel	
7	<b>DistributionElementType</b>	Supports the definition of standard DistributionElement types and associated PropertySets			
	<b>IfcDistributionElement</b>	Common Pset		#N/A	Pset_DistributionElementCommon
		<b>Roof Drainage</b>			
		Drain		21	Pset_DistributionDrain
		Gutter		22	Pset_DistributionGutter
		Scupper		20	Pset_DistributionScupper
8	<b>DocumentReferenceType</b>	Supports the definition of standard DocumentReference types and associated PropertySets			
	<b>IfcDocumentReference</b>	Common Pset		#N/A	Pset_DocumentReferenceCommon
		<b>Specifications</b>			
		< Any value >		23	Pset_DocumentSpecSection
9	<b>EquipmentType</b>	Supports the definition of standard Equipment types and associated PropertySets			
	<b>IfcEquipment</b>	Common Pset		#N/A	Pset_EquipmentCommon
		<b>Elevator</b>			
		< Any value >		25	Pset_EquipmentElevator
		<b>Escalator</b>			
		< Any value >		26	Pset_EquipmentEscalator
		<b>Window Cleaning</b>			
		< Any value >		27	Pset_EquipmentWindowCleaningElement
10	<b>PathwayType</b>	Supports the definition of standard Pathway types and associated PropertySets			
	<b>IfcPathway</b>	Common Pset		#N/A	Pset_PathwayCommon
		<b>RoofAccessPath</b>			
		< Any value >		30	Pset_PathwayRoofAccessPath

11	<b>PermeableOpeningCoverType</b>	Supports the definition of standard PermeableOpeningCover types and associated PropertySets			
	<b>IfcPermeableOpeningCover</b>	Common Pset		34	Pset_PermOpenCoverCommon
		<b>Grill</b>			
		< Any value >		31	Pset_PermOpenCoverGrill
		<b>Louver</b>			
		< Any value >		32	Pset_PermOpenCoverLouver
		<b>Screen</b>			
		< Any value >		33	Pset_PermOpenCoverScreen
12	<b>PlumbingFixtureType</b>	Supports the definition of standard PlumbingFixture types and associated PropertySets			
	<b>IfcPlumbingFixture</b>	Common Pset		35	Pset_PlumbingFixtureCommon
		<b>Faucet</b>			
		< Any value >		#N/A	Pset_PlumbingFixtureFaucet
		<b>Sink</b>			
		< Any value >		#N/A	Pset_PlumbingFixtureSink
		<b>Shower</b>			
		< Any value >		#N/A	Pset_PlumbingFixtureShower
		<b>Toilet</b>			
		< Any value >		#N/A	Pset_PlumbingFixtureToilet
		<b>Urinal</b>			
		< Any value >		#N/A	Pset_PlumbingFixtureUrinal
13	<b>VisualScreenType</b>	Supports the definition of standard Screen types and associated PropertySets			
	<b>IfcVisualScreen</b>	Common Pset		42	Pset_VisualScreenCommon
		<b>Assembly</b>			
		< Any value >		43	Pset_VisualScreenAssembly
		<b>DoorOrGate</b>			
		Restroom Partition Door		41	Pset_VisualScreenRestroomPartitionDoor
		< Any other value >		46	Pset_VisualScreenDoorOrGate
		<b>Panel</b>			
		Restroom Partition		40	Pset_VisualScreenRestroomPartition
		< Any other value >		45	Pset_VisualScreenPanel
		<b>Post</b>			
		< Any value >		44	Pset_VisualScreenPost
10	<b>RailingType</b>	Supports the definition of standard Railing types and associated PropertySets			
	<b>IfcRailing</b>	Common Pset		36	Pset_RailingCommon
		<b>Handrail</b>			
		< Any value >		37	Pset_RailingHandrail
		<b>Guardrail</b>			

				< Any value >			38	Pset_RailingGuardrail
				<b>Balustrade</b>				
				< Any value >			39	Pset_RailingBalustrade
11	<b>SpaceType</b>			Supports the definition of standard Space types and associated PropertySets				
	<b>IfcSpace</b>			Common Pset			#N/A	Pset_SpaceCommon
				<b>CirculationSpace</b>				
				StairShaft			49	Pset_SpaceStairShaft
				< Any other value >			#N/A	Pset_SpaceCirculation
				<b>TechnicalSpace</b>				
				Elevator Shaft			48	Pset_SpaceElevatorShaft
				< Any other value >			#N/A	Pset_SpaceTechnical
12	<b>WallType</b>			Supports the definition of standard Wall types and associated PropertySets				
	<b>IfcWall</b>			Common Pset			#N/A	Pset_WallCommon
				<b>Partition</b>				
				< Any value >			#N/A	Pset_WallPartition
13	<b>WindowType</b>			Supports the definition of standard Window types and associated PropertySets				
	<b>IfcWindow</b>			Common Pset			#N/A	Pset_WindowCommon
				<b>Skylight</b>				
				< Any value >			51	Pset_WindowSkylight
14	<b>Extension Psets</b>			PropertySets which extend the definition of many types of objects				
	<b>Any Object</b>							
				<b>Maintenance</b>			24	Pset_ElementMaintenance
				<b>Maintenance Record</b>			28	Pset_MaintenanceRecord
				<b>Object Life Cycle</b>			29	Pset_ObjectLifeCycle

### 6.1.3. Property Sets

			PropertySet (Pset) Name Attribute / Relation name	Definition	Data Type or Related Object	Min	Max	Default
1			<b>Pset_AccessoryCommon</b>					
			ManufactureInfo	reference to Manufacturer information	ObjectReference (Pset_ManufactureInfo)	n/a	n/a	NIL
			ManufacturerMaterial	Material selection - from the manufacturer's material options for this fixture type	IfcString	n/a	n/a	empty string
			ManufacturerColor	Color selection - from the manufacturer's color options for this fixture type	IfcString	n/a	n/a	empty string
			ManufacturerFinish	Finish selection - from the manufacturer's finish options for this fixture type	IfcString	n/a	n/a	empty string
			<b>Target objects for this PropertySet</b>					
			IfcBuiltInAccessory					
2			<b>Pset_AccessoryBathroom</b>	These are what are commonly referred to as "Bathroom Accessories"				

			CommonAccessoryProperties	Reference to the SharedPropertySet (Pset_AccessoryCommon). Contains the shared values for this type -- of properties that are stored for all Screen elements.	IfcObjectReference (Pset_AccessoryCommon)	n/a	n/a	NIL
			Property2	Not yet defined				
			<b>Target objects for this PropertySet</b>					
			IfcBuiltInAccessory					
3			<b>Pset_AccessoryDoorOrWindow Hardware</b>					
			CommonAccessoryProperties	Reference to the SharedPropertySet (Pset_AccessoryCommon). Contains the shared values for this type -- of properties that are stored for all Screen elements.	IfcObjectReference (Pset_AccessoryCommon)	n/a	n/a	NIL
			ProjectHwGroupReference	Project reference ID for this standard collection of hardware elements for doors	IfcString	see type	see type	empty string
			TypeDescription	Description for this type of frame (note name is captured in the TypeDef object that references this PropertySet)	IfcString	see type	see type	empty string
			DoorHardwareElementIndexList	A list of indices into the enumeration referenced by DoorHardwareElementEnum. Note: this list will be implemented as a shared Pset_DoorHardwareGroupElements - a list of IfcInteger indices into that enum.	LIST [1:?] OF IfcInteger	1	10	1
			DoorHardwareElementEnum	Reference to a Pset enumerating all possible door hardware elements for this hardware group. Note: this will be implemented as a shared PropertySet (Pset_DoorHardwareElementEnum) of IfcString (values enumerated at right).	IfcObjectReference (Pset_DoorHardwareElementEnum - ENUMERATION OF (Hingeset, Lockset, Handset, Deadbolt, Kickplate, Pushplate, Peephole, Knocker, DoorStop, Passthrough))	n/a	n/a	NIL
			<b>Target objects for this PropertySet</b>					
			IfcBuiltInAccessory					
4			<b>Pset_BeamStairStringer</b>					
			Slope	Slope for this stringer - relative to horizontal (0.0 degrees).	IfcAngleMeasure	0.0	see type	0.0
			ConstructionDetails	List of references to construction detail drawings	LIST [0:?] OF ObjectReference (IfcDocumentReference)	n/a	n/a	empty list
			<b>Target objects for this PropertySet</b>					
			IfcBeam					
5			<b>Pset_CabinetCommon</b>					
			ManuafactureInfo	reference to Manufacturer information	ObjectReference (Pset_ManufactureInfo)	n/a	n/a	NIL
			ConstructionDetail	Reference to construction detail drawing	Ref [IfcDocumentReference]	n/a	n/a	NIL
			SpecSection	Reference to a section of the construction specification	ObjectReference (IfcDocumentReference)	n/a	n/a	NIL
			<b>Target objects for this PropertySet</b>					
			IfcCabinet					
6			<b>Pset_CabinetBathroom</b>					
			CommonCabinetProperties	Reference to the SharedPropertySet (Pset_CabinetCommon). Contains the shared values for this type -- of properties that are stored for all types of cabinets.	IfcObjectReference (Pset_CabinetCommon)	n/a	n/a	NIL
			Property2	Not yet defined				
			<b>Target objects for this PropertySet</b>					
			IfcCabinet					



7	<b>Pset_CabinetKitchen</b>						
		CommonCabinetProperties	Reference to the SharedPropertySet (Pset_CabinetCommon). Contains the shared values for this type -- of properties that are stored for all types of cabinets.	IfcObjectReference (Pset_CabinetCommon)	n/a	n/a	NIL
		Property2	Not yet defined				
		<b>Target objects for this PropertySet</b>					
		IfcCabinet					
8	<b>Pset_CabinetStorage</b>						
		CommonCabinetProperties	Reference to the SharedPropertySet (Pset_CabinetCommon). Contains the shared values for this type -- of properties that are stored for all types of cabinets.	IfcObjectReference (Pset_CabinetCommon)	n/a	n/a	NIL
		Property2	Not yet defined				
		<b>Target objects for this PropertySet</b>					
		IfcCabinet					
9	<b>Pset_CabinetLaundry</b>						
		CommonCabinetProperties	Reference to the SharedPropertySet (Pset_CabinetCommon). Contains the shared values for this type -- of properties that are stored for all types of cabinets.	IfcObjectReference (Pset_CabinetCommon)	n/a	n/a	NIL
		Property2	Not yet defined				
		<b>Target objects for this PropertySet</b>					
		IfcCabinet					
10	<b>Pset_CabinetOffice</b>						
		CommonCabinetProperties	Reference to the SharedPropertySet (Pset_CabinetCommon). Contains the shared values for this type -- of properties that are stored for all types of cabinets.	IfcObjectReference (Pset_CabinetCommon)	n/a	n/a	NIL
		Property2	Not yet defined				
		<b>Target objects for this PropertySet</b>					
		IfcCabinet					
11	<b>Pset_CounterOrShelfCommon</b>						
		ManufactureInfo	reference to Manufacturer information	ObjectReference (Pset_ManufactureInfo)	n/a	n/a	NIL
		ConstructionDetail	Reference to construction detail drawing	Ref [IfcDocumentReference]	n/a	n/a	NIL
		SpecSection	Reference to a section of the construction specification	ObjectReference (IfcDocumentReference)	n/a	n/a	NIL
		<b>Target objects for this PropertySet</b>					
		IfcCounterOrShelf					
12	<b>Pset_Counter</b>						
		CommonCounterOrShelfProperties	Reference to the SharedPropertySet (Pset_CounterOrShelfCommon). Contains the shared values for this type -- of properties that are stored for all types of counters and shelves.	IfcObjectReference (Pset_CounterOrShelfCommon)	n/a	n/a	NIL
		Property2	Not yet defined				
		<b>Target objects for this PropertySet</b>					
		IfcCounterOrShelf					
13	<b>Pset_CoveringMillwork</b>						
		CommonCoveringProperties	Reference to a SharedPropertySet (Pset_CoveringCommon). Contains the shared values for this type -- of properties that are stored for all Covering elements.	IfcObjectReference (Pset_CoveringCommon)	n/a	n/a	NIL

			ConstructionDetail	Reference to a construction detail drawing file	ObjectReference (IfcDocumentReference)	n/a	n/a	NIL
			<b>Target objects for this PropertySet</b>					
			IfcCovering					
14			<b>Pset_CurtainWallElementCommon</b>	Defines properties common for all CurtainWall elements.				
			ManufactureInformation	Reference to a SharedPropertySet - Pset_ManufactureInformation, which defines information about the manufacture of this element.	IfcObjectReference (Pset_ManufactureInformation)	n/a	n/a	NIL
			LifecycleInformation	Reference to lifecycle	IfcObjectReference (Pset_ObjectLifecycle)	na	na	NIL
			ConstructionDetails	List of references to a detail drawings	LIST [0..?] OF IfcDocumentReference	n/a	n/a	empty list
			SpecSection	Document reference to specification section	IfcDocumentReference	n/a	n/a	NIL
			BldgCodeRefs	List of document references to building codes	LIST [0..?] OF IfcDocumentReference	n/a	n/a	empty list
			<b>Target objects for this PropertySet</b>					
			IfcCurtainWallElement					
15			<b>Pset_CurtainWallCladPanel</b>					
			CommonCurtainWallElementProperties	Reference to the 'parent' SharedPropertySet (Pset_CurtainWallElementType). Contains the shared values for this type -- of properties that are stored for all CurtainWallElements.	IfcObjectReference (Pset_CurtainWallElementType)	n/a	n/a	NIL
			<b>Target objects for this PropertySet</b>					
			IfcCurtainWallElement					
16			<b>Pset_CurtainWallGlazingPanel</b>					
			CommonCurtainWallElementProperties	Reference to the 'parent' SharedPropertySet (Pset_CurtainWallElementType). Contains the shared values for this type -- of properties that are stored for all CurtainWallElements.	IfcObjectReference (Pset_CurtainWallElementType)	n/a	n/a	NIL
			<b>Target objects for this PropertySet</b>					
			IfcCurtainWallElement					
17			<b>Pset_CurtainWallProjectionOrnamental</b>					
			CommonCurtainWallElementProperties	Reference to the 'parent' SharedPropertySet (Pset_CurtainWallElementType). Contains the shared values for this type -- of properties that are stored for all CurtainWallElements.	IfcObjectReference (Pset_CurtainWallElementType)	n/a	n/a	NIL
			Description	Description of this projecting element	IfcString	n/a	n/a	empty string
			Weight	Total weight of projection	IfcMassMeasure	0.0	see type	0.0
			ConstructionDetails	Reference to detail construction drawings for connection to façade (ie. bolt, screw or fastener detail)	LIST [0..?] OF ObjectReference (IfcDocumentReference)	n/a	n/a	NIL
			Services	References to building services needed (e.g. electrical to an operable canopy)	LIST [0..?] OF ObjectReference (IfcSystem)	n/a	n/a	empty list
			<b>Target objects for this PropertySet</b>					
			IfcCurtainWallElement					
18			<b>Pset_CurtainWallShadeOverhang</b>					
			CommonCurtainWallElementProperties	Reference to the 'parent' SharedPropertySet (Pset_CurtainWallElementType). Contains the shared values for this type -- of properties that are stored for all CurtainWallElements.	IfcObjectReference (Pset_CurtainWallElementType)	n/a	n/a	NIL
			<b>Target objects for this PropertySet</b>					
			IfcCurtainWallElement					

19	<b>Pset_CurtainWallSpandrelPane</b>						
		CommonCurtainWallElementProperties	Reference to the 'parent' SharedPropertySet (Pset_CurtainWallElementType). Contains the shared values for this type -- of properties that are stored for all CurtainWallElements.	IfcObjectReference (Pset_CurtainWallElementType)	n/a	n/a	NIL
		<b>Target objects for this PropertySet</b>					
		IfcCurtainWallElement					
20	<b>Pset_DistributionScupper</b>		General opening/edge condition designed to distribute (convey) overflow drainage from a roof or deck.				
		ManufactureInfo	reference to Manufacturer information	ObjectReference (Pset_ManufactureInfo)	n/a	n/a	NIL
		ConstructionDetail	Reference to a construction detail drawing	ObjectReference [IfcDocumentReference]	na	na	na
		SpecSection	Reference to a section of the specification	ObjectReference (IfcDocumentReference)	na	na	NIL
		<b>Target objects for this PropertySet</b>					
		IfcDistributionElement	Roof or Downspout				
21	<b>Pset_DistributionDrain</b>						
		ManufactureInfo	reference to Manufacturer information	ObjectReference (Pset_ManufactureInfo)	n/a	n/a	NIL
		TributaryAreaDrained	Area for this this is the primary drain. Value of 0.00 means this value has not been set.	IfcAreaMeasure	see type	see type	0.00
		FlowCapacity	Calculated capacity of drain flow. Value of 0.00 means this value has not been set.	IfcFlowMeasure	see type	see type	0.00
		ConstructionDetail	Reference to a construction detail drawing	ObjectReference (IfcDocumentReference)	na	na	NIL
		SpecSection	Reference to a section of the specification	ObjectReference (IfcDocumentReference)	na	na	NIL
		<b>Target objects for this PropertySet</b>					
		IfcDistributionElement					
22	<b>Pset_DistributionGutter</b>						
		Slope	angle of the gutter to allow for drainage	IfcAngleMeasure	0.0	see type	0.0
		FlowCapacity	Calculated capacity of drain flow. Value of 0.00 means this value has not been set.	IfcFlowMeasure	see type	see type	0.00
		ConstructionDetail	Reference to a construction detail drawing	ObjectReference (IfcDocumentReference)	na	na	NIL
		SpecSection	Reference to a section of the specification	ObjectReference (IfcDocumentReference)	na	na	NIL
		<b>Target objects for this PropertySet</b>					
		IfcDistributionElement					
23	<b>Pset_DocumentSpecSection</b>						
		CommonDocumentReferenceProperties	Reference to a SharedPropertySet (Pset_DocumentReferenceCommon), which contains the properties that are stored for all types of Document References.	IfcObjectReference (Pset_DocumentReferenceCommon)	n/a	n/a	NIL
		SectionID	Section number or ID for the referenced section	IfcString	n/a	n/a	empty string
		OffsetToSection	Byte count offset from beginning of file to the beginning of the referenced section. Value of 0 means offset not set.	IfcInteger	0	see type	0
		<b>Target objects for this PropertySet</b>					
		IfcDocumentReference					
24	<b>Pset_ElementMaintenance</b>						

			ElementMaintenanceConditionEnum	Reference to nested enumeration property set Pset_ElementMaintenanceConditionEnum. This enumeration defines the general conditions for a building element requiring routine maintenance.	ENUMERATION OF (GoodCondition, RequiresMonitoring, RequiresRoutineMaintenance, RequiresRepair, RequiresReplacement, Other, NotKnown, Unset)	n/a	n/a	NIL
			ElementMaintenanceConditionIndex	Index into the nested enumeration property set Pset_ElementMaintenanceConditionEnum	IfcInteger	1	N	1
			ServiceActor	The person or maintenance service provider responsible for the maintenance of the element	IfcActorSelect	n/a	n/a	NIL
			MaintenanceRecords	List of references to maintenance records for this element.	LIST [0:?] OF IfcSharedPropertySet (Pset_MaintenanceRecord)	n/a	n/a	empty list
			Target objects for this PropertySet					
			IfcElement					
25			<b>Pset_EquipmentElevator</b>					
			CommonEquipmentProperties	Reference to a SharedPropertySet (Pset_EquipmentCommon) which defines properties that are stored for all types of equipment.	IfcSharedPropertySet (Pset_EquipmentCommon)	n/a	n/a	NIL
			Occupancy	Number of occupants	IfcInteger	0	see type	0
			ManufactureInfo	Nested Pset defining manufacturing info	IfcSharedPropertySet (Pset_ManufactureInfo)	n/a	n/a	NIL
			LoadCapacity	Weight capacity of elevator	IfcMassMeasure	see type	see type	0
			ClientBrief	Reference to program to gain requirements for occupancy	ObjectReference (IfcClientBrief)	n/a	n/a	NIL
			Target objects for this PropertySet					
			IfcEquipment					
26			<b>Pset_EquipmentEscalator</b>					
			CommonEquipmentProperties	Reference to a SharedPropertySet (Pset_EquipmentCommon) which defines properties that are stored for all types of equipment.	IfcSharedPropertySet (Pset_EquipmentCommon)	n/a	n/a	NIL
			Capacity	number of people that can be moved from the top to the bottom	IfcInteger	0	see type	0
			ManufactureInfo	reference to Pset_ManufactureInfo	ObjectReference (Pset_ManufactureInfo)	n/a	n/a	NIL
			ClientBrief	Link to program to gain requirements for occupancy	ObjectReference (IfcClientBrief)	n/a	n/a	NIL
			Target objects for this PropertySet					
			IfcEquipment					
27			<b>Pset_EquipmentWindowCleaningElement</b>					
			CommonEquipmentProperties	Reference to a SharedPropertySet (Pset_EquipmentCommon) which defines properties that are stored for all types of equipment.	IfcSharedPropertySet (Pset_EquipmentCommon)	n/a	n/a	NIL
			WindowCleaningElementTypeEnum	Enumeration of the various	Enum (Apparatus, Carriage, Rails, Rigging, Tracks)	Apparatus	Tracks	Carriage
			WindowCleaningElementTypeIndex	Index (in the enum above) indicating the type of window cleaning system element for this object	IfcInteger	1	5	2
			Target objects for this PropertySet					
			IfcEquipment					
28			<b>Pset_MaintenanceRecord</b>					
			MaintenanceDate	Date maintenance performed	IfcDateTimeSelect	see type	see type	1-Jan-72
			MaintenanceReason	Description of Problem	IfcString	see type	see type	empty string
			MaintenanceDescription	Description of what work was performed	IfcString	see type	see type	empty string

				Crew	Maintenance crew involved	LIST [0..?] OF IfcActorSelect	n/a	n/a	empty list
				<b>Target objects for this PropertySet</b>					
				IfcRoof, Pset_LifeCycle					
29				<b>Pset_ObjectLifeCycle</b>					
				InstallationDate	Date of installation	IfcDateTimeSelect	see type	see type	1-Jan-72
				ServiceLife	Time period in which the object is projected to last without replacement	IfcTimeDurationMeasure	see type	see type	0
				Warranty	Legal description of time period that the manufacturer is responsible for replacement	IfcTimeDurationMeasure	see type	see type	0
				MaintenanceInterval	Time period between each maintenance cycle	IfcTimeDurationMeasure	see type	see type	0
				MaintenanceRequirements	Requirments for maintenance	IfcString	see type	see type	empty string
				MaintenanceHistory	List of links to maintenance records	LIST [0..?] IfcObjectReference (Pset_MaintenanceRecord)	n/a	n/a	empty list
				LifeCycleCost	Total cost of object (may be an assembly) over the LifeCycleCostPeriod	IfcCost	0.0	see type	0.0
				LifeCycleCostPeriod	Life for which the LifeCycleCost has been calculated	IfcTimeDurationMeasure	see type	see type	0.0
				SalvageValue	Value if recycled or returned when replacement	IfcCost	0.0	n	0.0
				<b>Target objects for this PropertySet</b>					
				IfcAssemblyCurtainWall, IfcRoofSlab					
30				<b>Pset_PathwayRoofAccessPath</b>					
				PathLength	Description of walk to mechanical	IfcPositiveLengthMeasure	0.0	see type	0.0
				PathWidth	Distance across path	IfcPositiveLengthMeasure	0.0	see type	0.0
				<b>Target objects for this PropertySet</b>					
				IfcPathway					
31				<b>Pset_PermOpenCoverGrill</b>					
				CommonPermeableOpeningCover Properties	Reference to the 'parent' SharedPropertySet (Pset_PermOpenCoverType). Contains the shared values for this type -- of properties that are stored for all PermeableOpeningCovers.	IfcObjectReference (Pset_PermOpenCoverType)	n/a	n/a	NIL
				GrillMaterial	Primary material from which this grill is made - an index into the MaterialSet associated with this building element	IfcInteger	0	see type	0
				HorzSpacing	Spacing of the screening wire at the angle set by Orientation. "0.0" indicates value not set.	IfcPositiveLengthMeasure	see type	see type	0.0
				VertSpacing	Spacing of the screening wire at the angle perpendicular to that set by Orientation. "0.0" indicates value not set.	IfcPositiveLengthMeasure	see type	see type	0.0
				FinWidth	Width (when viewed from finished side) of the fins in this grill. Value of 0.0 means value not set.	IfcPositiveLengthMeasure	see type	see type	0.0
				FinDepth	depth (finished side to back side) of the fins in this grill. Value of 0.0 means value not set.	IfcPositiveLengthMeasure	see type	see type	0.0
				<b>Target objects for this PropertySet</b>					
				IfcPermeableOpeningCover					
32				<b>Pset_PermOpenCoverLouver</b>	A type of permeable cover for an opening (which allows airflow). Louvers may be placed in any Opening.				
				CommonPermeableOpeningCover Properties	Reference to the 'parent' SharedPropertySet (Pset_PermOpenCoverType). Contains the shared values for this type -- of properties that are stored for all PermeableOpeningCovers.	IfcObjectReference (Pset_PermOpenCoverType)	n/a	n/a	NIL
				LouverMaterial	Primary material from which this louver is made - an index into the MaterialSet associated with this building element	IfcInteger	0	see type	0

				FinSpacing	Distance between adjacent fins. "0.0" indicates value not set.	IfcPositiveLengthMeasure	see type	see type	0.0
				FinAngle	Slope angle of the fins, in cross-sectional view with finished (or exterior) face on the right side of the section. Horizontal fin angle is taken to be zero ("0") angle.	IfcAngleMeasure	0.0	<360.0	0.0
				FinDepth	Fin depth measure, in cross-sectional view. "0.0" indicates value not set.	IfcPositiveLengthMeasure	see type	see type	0.0
				InsideScreen	Reference to a screen on the inside of these louvers	ObjectReference (Pset_PermOpenCoverScreen)	n/a	n/a	NIL
				<b>Target objects for this PropertySet</b>					
				IfcPermeableOpeningCover					
33				<b>Pset_PermOpenCoverScreen</b>					
				CommonPermeableOpeningCover Properties	Reference to the 'parent' SharedPropertySet (Pset_PermOpenCoverType). Contains the shared values for this type -- of properties that are stored for all PermeableOpeningCovers.	IfcObjectReference (Pset_PermOpenCoverType)	n/a	n/a	NIL
				ScreenMaterial	Primary material from which this screen is made - an index into the MaterialSet associated with this building element	IfcInteger	0	see type	0
				HorzSpacing	Spacing of the screening wire at the angle set by Orientation. "0.0" indicates value not set.	IfcPositiveLengthMeasure	see type	see type	0.0
				VertSpacing	Spacing of the screening wire at the angle perpendicular to that set by Orientation. "0.0" indicates value not set.	IfcPositiveLengthMeasure	see type	see type	0.0
				ScreenThickness	Thickness of the screening wire	IfcPositiveLengthMeasure	see type	see type	0.5
				<b>Target objects for this PropertySet</b>					
				IfcPermeableOpeningCover					
34				<b>Pset_PermOpenCoverCommon</b>	Permeable cover for an opening which allows airflow (definition BS 6100)				
				TypeDescription	Description for this type of louver (note name is captured in the TypeDef object that references this PropertySet)	IfcString	see type	see type	empty string
				ManufactureInformation	Reference to a SharedPropertySet - Pset_ManufactureInformation, which defines information about the manufacture of this door hardware.	IfcObjectReference (Pset_ManufactureInformation)	n/a	n/a	NIL
				RequiredOpeningHeight	Overall Height of the required opening for this louver. Note this can be derived from the 'ProductShape' and is included for convenience use by applications that cannot derive this from the shape. Zero means this property has not been set.	IfcPositiveLengthMeasure	0	see type	0
				RequiredOpeningWidth	Overall Width of the required opening for this louver. Note this can be derived from the 'ProductShape' and is included for convenience use by applications that cannot derive this from the shape. Zero means this property has not been set.	IfcPositiveLengthMeasure	0	see type	0
				FrameWidth	Average length measure, when viewed from the finished face, from the edge of the louver to fins.	IfcPositiveLengthMeasure	see type	see type	1.0
				FrameDepth	Measure of the frame depth (front to back)	IfcPositiveLengthMeasure	see type	see type	1.0
				Orientation	Orientation angle, when facing the finished side of installed louvers. Horizontal is taken to be zero ("0") angle. Angle is positive in counter-clockwise rotation.	IfcAngleMeasure	0.0	<360.0	0.0
				ConstructionDetail	Reference to a construction detail drawing	IfcObjectReference (IfcDocumentReference)	see type	see type	NIL
				SpecSection	Reference to a section in the construction specifications	IfcObjectReference (IfcDocumentReference)	see type	see type	NIL
				FreeAreaVentilation	Actual usable Area. Zero means this value has not been set.	IfcAreaMeasure	0	see type	0
				ClearanceSpace	Distance needed for correct operation/air flow	ObjectReference (IfcSpace)	see type	see type	NIL
				Operable	Designation of operability of this cover	IfcBoolean	FALSE	TRUE	FALSE
				Control	Reference to control system if needed	ObjectReference (IfcSystem)	see type	see type	NIL

			<b>Target objects for this PropertySet</b>					
			IfcPermeableOpeningCover					
35			<b>Pset_PlumbingFixtureCommon</b>					
			ManuafactureInfo	reference to Manufacturer information	ObjectReference (Pset_ManufactureInfo)	n/a	n/a	NIL
			FunctionalHeight	Height from floor to functional opening. Value of 0.0 means this property not set.	IfcPositiveLengthMeasure	0.0	see type	0.0
			MountingHeight	height at which the item gets connect to the wall. Value of 0.0 means this property not set.	IfcPositiveLengthMeasure	0.0	see type	0.0
			MountingType	Description of the method for mounting	IfcString	n/a	n/a	empty string
			DrainConnectPoint	Reference to the connection object relating this plumbing fixture to the sewer piping system (the drain)	ObjectReference (IfcRelConnectsElements)	n/a	n/a	NIL
			HwconnectPoint	Reference to the connection object relating this plumbing fixture to the hot water plumbing system.	ObjectReference (IfcRelConnectsElements)	n/a	n/a	NIL
			CWconnectPoint	Reference to the connection object relating this plumbing fixture to the cold water plumbing system	ObjectReference (IfcRelConnectsElements)	n/a	n/a	NIL
			ElectricalConnectPoint	Reference to the connection object relating this plumbing fixture to the electrical power system	ObjectReference (IfcRelConnectsElements)	n/a	n/a	NIL
			ConstructionDetails	List of reference to construction detail drawings	LIST [0..?] OF ObjectReference (IfcDocumentReference)	n/a	n/a	empty list
			SpecSection	Reference to a section of the construction specification	ObjectReference (IfcDocumentReference)	n/a	n/a	NIL
			OperationalSpace	Space around fixture required for proper use by occupants	ObjectReference (IfcSpace)	0	N	0
			ManufacturerMaterial	Material selection - from the manufacturer's material options for this fixture type	IfcString	n/a	n/a	empty string
			ManufacturerColor	Color selection - from the manufacturer's color options for this fixture type	IfcString	n/a	n/a	empty string
			ManufacturerFinish	Finish selection - from the manufacturer's finish options for this fixture type	IfcString	n/a	n/a	empty string
			<b>Target objects for this PropertySet</b>					
			IfcPlumbingFixture					
36			<b>Pset_RailingCommon</b>					
			ManuafactureInfo	reference to Manufacturer information	ObjectReference (Pset_ManufactureInfo)	n/a	n/a	NIL
			ConstructionDetail	Reference to construction detail drawing	Ref [IfcDocumentReference]	n/a	n/a	NIL
			SpecSection	Reference to a section of the construction specification	ObjectReference (IfcDocumentReference)	n/a	n/a	NIL
			<b>Target objects for this PropertySet</b>					
			IfcRailing					
37			<b>Pset_RailingHandrail</b>					
			CommonRailingProperties	Reference to the SharedPropertySet (Pset_RailingCommon). Contains the shared values for this type -- of properties that are stored for all Railing elements.	IfcObjectReference (Pset_RailingCommon)	n/a	n/a	NIL
			HandrailMaterial	Index into the IfcMaterialList defined in the IfcElement supertype	IfcInteger	1	MaterialList length	1
			HandrailHeight	Height to top of handrail - from stair, landing or floor	IfcPositiveLengthMeasure	0.0	see type	0.0
			MaxDistanceFromWall	Distance from the wall to the outside of the handrail. Value of 0.0 means value not set.	IfcPositiveLengthMeasure	0.0	see type	0.0
			<b>Target objects for this PropertySet</b>					
			IfcRailing					
38			<b>Pset_RailingGuardrail</b>					
			CommonRailingProperties	Reference to the SharedPropertySet (Pset_RailingCommon). Contains the shared values for this type -- of properties that are stored for all Railing elements.	IfcObjectReference (Pset_RailingCommon)	n/a	n/a	NIL

				Height	Height to the top of the guardrail - from stair, landing or floor	IfcPositiveLengthMeasure	0.0	see type	0.0
				RepeatingElements	reference to definition of repeating rail stiles - defined in a Pset in the ExtensionPsets for this object	Ref [Pset_RepeatingElement]	n/a	n/a	NIL
				MountedHandrail	Reference to any handrail mounted on this guardrail	Ref [IfcRailing]	n/a	n/a	NIL
				<b>Target objects for this PropertySet</b>					
				IfcRailing					
39				<b>Pset_RailingBalustrade</b>					
				CommonRailingProperties	Reference to the SharedPropertySet (Pset_RailingCommon). Contains the shared values for this type -- of properties that are stored for all Railing elements.	IfcObjectReference (Pset_RailingCommon)	n/a	n/a	NIL
				BalustradeProperty2	Property not defined yet				
				<b>Target objects for this PropertySet</b>					
				IfcRailing					
40				<b>Pset_VisualScreenRestroomPartition</b>					
				CommonVisualScreenElementProperties	Reference to the 'parent' SharedPropertySet (Pset_VisualScreenCommon). Contains the shared values for this type -- of properties that are stored for all VisualScreen elements.	IfcObjectReference (Pset_VisualScreenCommon)	n/a	n/a	NIL
				ManufacturerMaterial	Material selection - from the manufacturer's material options for this fixture type	IfcString	n/a	n/a	empty string
				ManufacturerColor	Color selection - from the manufacturer's color options for this fixture type	IfcString	n/a	n/a	empty string
				ManufacturerFinish	Finish selection - from the manufacturer's finish options for this fixture type	IfcString	n/a	n/a	empty string
				<b>Target objects for this PropertySet</b>					
				IfcVisualScreen					
41				<b>Pset_VisualScreenRestroomPartitionDoor</b>					
				CommonVisualScreenElementProperties	Reference to the 'parent' SharedPropertySet (Pset_VisualScreenCommon). Contains the shared values for this type -- of properties that are stored for all VisualScreen elements.	IfcObjectReference (Pset_VisualScreenCommon)	n/a	n/a	NIL
				HingeSide	Indicates the hinged side of the door - when viewed from outside the partition enclosure. 0=left, 1=right.	IfcLogical	0	1	1
				SwingDirection	Indicates whether this door swings into or out of the partition enclosure. 0=swings in, 1=swings out.	IfcLogical	0	1	1
				ManufacturerMaterial	Material selection - from the manufacturer's material options for this fixture type	IfcString	n/a	n/a	empty string
				ManufacturerColor	Color selection - from the manufacturer's color options for this fixture type	IfcString	n/a	n/a	empty string
				ManufacturerFinish	Finish selection - from the manufacturer's finish options for this fixture type	IfcString	n/a	n/a	empty string
				<b>Target objects for this PropertySet</b>					
				IfcVisualScreen					
42				<b>Pset_VisualScreenCommon</b>					
				VisualScreenElementHeight	Height of the partition panel. Value of 0.0 means property not set.	IfcPositiveLengthMeasure	0.0	see type	0.0
				VisualScreenElementWidth	Width of the partition panel. Value of 0.0 means property not set.	IfcPositiveLengthMeasure	0.0	see type	0.0
				VisualScreenElementThickness	Thickness of the partition panel. Value of 0.0 means property not set.	IfcPositiveLengthMeasure	0.0	see type	0.0
				AssembledTopOfElementHeight	Height, from finish floor, to the top of this partition panel. Value of 0.0 means property not set.	IfcPositiveLengthMeasure	0.0	see type	0.0
				AssemblyHardware	List of references to mounting/assembly hardware components for this panel only	LIST [0..?] OF ObjectReference (IfcBuiltInAccessories)	n/a	n/a	empty list



			<b>Target objects for this PropertySet</b>					
			IfcVisualScreen					
43			<b>Pset_VisualScreenAssembly</b>					
			ManufactureInfo	reference to Manufacturer information	ObjectReference (Pset_ManufactureInfo)	n/a	n/a	NIL
			ConstructionDetails	List of reference to construction detail drawings	LIST [0..?] OF ObjectReference (IfcDocumentReference)	n/a	n/a	empty list
			SpecSection	Reference to a section of the construction specification	ObjectReference (IfcDocumentReference)	n/a	n/a	NIL
			<b>Target objects for this PropertySet</b>					
			IfcVisualScreen					
44			<b>Pset_VisualScreenPost</b>					
			CommonVisualScreenProperties	Reference to the SharedPropertySet (Pset_VisualScreenCommon) - which contains properties that are stored for all types of VisualScreen elements.	IfcSharedPropertySet (Pset_VisualScreenCommon)	n/a	n/a	NIL
			PostProperty2	This property has not yet been defined				
			<b>Target objects for this PropertySet</b>					
			IfcVisualScreen					
45			<b>Pset_VisualScreenPanel</b>					
			CommonVisualScreenProperties	Reference to the SharedPropertySet (Pset_VisualScreenCommon) - which contains properties that are stored for all types of VisualScreen elements.	IfcSharedPropertySet (Pset_VisualScreenCommon)	n/a	n/a	NIL
			VisualScreenProperty2	This property has not yet been defined				
			<b>Target objects for this PropertySet</b>					
			IfcVisualScreen					
46			<b>Pset_VisualScreenDoorOrGate</b>					
			CommonVisualScreenProperties	Reference to the SharedPropertySet (Pset_VisualScreenCommon) - which contains properties that are stored for all types of VisualScreen elements.	IfcSharedPropertySet (Pset_VisualScreenCommon)	n/a	n/a	NIL
			DoorProperty2	This property has not yet been defined				
			<b>Target objects for this PropertySet</b>					
			IfcVisualScreen					
47			<b>Pset_Shelf</b>					
			CommonCounterOrShelfProperties	Reference to the SharedPropertySet (Pset_CounterOrShelfCommon). Contains the shared values for this type -- of properties that are stored for all types of counters and shelves.	IfcObjectReference (Pset_CounterOrShelfCommon)	n/a	n/a	NIL
			Property2	Not yet defined				
			<b>Target objects for this PropertySet</b>					
			IfcCounterOrShelf					
48			<b>Pset_SpaceElevatorShaft</b>	Specific type of Technical Space (generic type defined in R1.5)				
			CommonSpaceProperties	Reference to the 'parent' PropertySet (Pset_SpaceCommon). Contains the shared values for this type -- of properties that are stored for all Spaces.	IfcObjectReference (Pset_SpaceCommon)	n/a	n/a	NIL
			BldgStoriesServed	List of references to all the IfcBuildinStorey objects that are serviced by this elevator shaft	LIST [0..?] OF Ref [IfcBuildingStorey]	n/a	n/a	empty list
			<b>Target objects for this PropertySet</b>					

				IfcSpace						
49				<b>Pset_SpaceStairShaft</b>						
				CommonSpaceProperties	Reference to the 'parent' PropertySet (Pset_SpaceCommon). Contains the shared values for this type -- of properties that are stored for all Spaces.	IfcObjectReference (Pset_SpaceCommon)	n/a	n/a	NIL	
				BldgStoriesServed	List of references to all the IfcBuildinStorey objects that are serviced by this elevator shaft	LIST [0:?] OF Ref [IfcBuildingStorey]	n/a	n/a	empty list	
				<b>Target objects for this PropertySet</b>						
				IfcSpace						
50				<b>Pset_WallParapet</b>						
				CommonWallProperties	Reference to the 'parent' PropertySet (Pset_WallType). Contains the shared values for this type -- of properties that are stored for all walls.	IfcObjectReference (Pset_WallType)	n/a	n/a	NIL	
				RepeatingElements	Reference to a Pset (Pset_RepeatingElement) describing any repeating elements for this wall (NIL pointer if not)	IfcObjectReference (Pset_RepeatingElement)	n/a	n/a	NIL	
				CapMaterial	Index into the Material list defined at the IfcElement level - points to material from which cap is made.	IfcInteger	see type	see type	1	
				CapManufacturerInfo	Reference to a SharedPropertySet - Pset_ManufactureInformation, which defines information about the manufacture of the parapet cap.	IfcObjectReference (Pset_ManufactureInformation)	n/a	n/a	NIL	
				ConstructionDetails	Document references to detail drawings	LIST [0:?] OF IfcDocumentReference	n/a	n/a	empty list	
				ParapetFunctionTypeEnum	Reference to a Pset enumerating possible parapet functional roles. Note: this will be implemented as a shared PropertySet (Pset_ParapetFunctionTypeEnum) of IfcString (values enumerated at right).	IfcObjectReference (Pset_ParapetFunctionTypeEnum - ENUMERATION OF (window washing rigging support, handrail, screen, fire block))	n/a	n/a	NIL	
				ParapetFunctionTypeIndex	List of Integer indicies into the enumeration defined by Pset_ParapetFunctionTypeEnum.	LIST [1:?] OF IfcInteger	1	4	empty list	
				SpecSection	Reference to relevant section of the construction specifications	ObjectReference (IfcDocumentReference)	n/a	n/a	empty list	
				<b>Target objects for this PropertySet</b>						
				IfcWall						
51				<b>Pset_WindowSkylight</b>						
				CommonWindowProperties	Reference to the 'parent' PropertySet (Pset_WindowType). Contains the shared values for this type -- of properties that are stored for all windows.	IfcSharedPropertySet (Pset_WindowType)	n/a	n/a	NIL	
				WindowPanelList	Reference to one or more window panels (defined left to right or bottom to top), as viewed from the finished (exterior) face (see diagram in specifications). NOTES: 1) this will be implemented as a shared Pset_WindowPanelList - which contains a list of s	LIST [1:?] OF IfcObjectReference (Pset_WindowPanel)	n/a	n/a	NIL	
				Operable	Is this Skylight operable?	IfcBoolean	FALSE	TRUE	FALSE	
				<b>Target objects for this PropertySet</b>						
				IfcWindow						

## 6.2. [AR-2] Compartmentation of Buildings

### 6.2.1. Object Types

The following table is pasted from the spreadsheet template "R2\_ObjectDefs\_d4.xls", sheet "Class Definitions"

		Object Type Name	Interface name	OPT INV DER					
Subtype of			Attribute / Relation name		Data Type/Related Object Type	Min	Max	Default	Definition
IfcCharacteristic	1		<b>IfcSpaceOccupancy</b>						IfcSharedSpatialElements schema
			I_SpaceOccupancy						
			OccupancyNumber	OPT	IfcOccupancyNumber	see type	see type	see type	
			Owner	OPT	IfcOccupant	see type	see type	see type	
			Rental	OPT	IfcOccupant	see type	see type	see type	
			Lease	OPT	IfcOccupant	see type	see type	see type	
IfcCharacteristic	2		<b>IfcOccupant</b>						IfcSharedSpatialElements schema
			I_Occupant						
			GenericType		IfcOccupantTypeEnum	Owner	Lessee	Tenant	
			OccupantName	OPT	IfcActorSelect				
IfcCharacteristic	3		<b>IfcOccupancyNumber</b>						IfcSharedSpatialElements schema
			I_OccupancyNumber						
			GenericType		IfcOccupancyNumberTypeEnum	Number	Number	Number	
			ActualOccupancyNumber	OPT	INTEGER	0	see type	1	
			DesignIntentOccupancyNumber	OPT	INTEGER	0	see type	1	
			CumulativeOccupancyNumber	OPT	INTEGER	0	see type	1	
			OccupancyRate	OPT	IfcPersonPerAreaMeasure	0	see type	1	
IfcSpace	4		<b>IfcFireCompartment</b>						IfcSharedSpatialElements schema
			I_FireCompartment						
			calcHeightAboveGrade	OPT	IfcLengthMeasure	see type	see type	1.0	
			MainFireUse	OPT	IfcClassification	see type	see type	see type	Main fire use for the space which is assigned from the Fire Use Classification.
			AncillaryFireUse	OPT	IfcClassification	see type	see type	see type	Ancillary fire use for the space which is assigned from the Fire Use Classification.
			FireRiskFactor	OPT	INTEGER	see type	see type	see type	Fire Risk factor assigned to the space
			NaturalVentilation	OPT	BOOLEAN	see type	see type	see type	Indication whether the space is ventilated natural (true) or mechanical (false).
			SprinklerProtection	OPT	BOOLEAN	see type	see type	see type	Indication whether the space is sprinkler protected (true) or not (false).

## 6.2.2. Type Definitions

None were defined.

## 6.2.3. Property Sets

None were defined.

## 6.3. [BS-1] HVAC System Design

### 6.3.1. Object Types

The following table is pasted from the spreadsheet template "R2\_ObjectDefs\_d4.xls", sheet "Class Definitions"

Class Name					{ { "Ref" = relationship } }					
Interface name					Data Type	Min	Max	Default	Units	
IfcPathwayElement				This class connects together the parts of a networked system.						
InheritsFrom ----->				IfcBuildingElement						
I_PathwayElement										
PathwayElementType				Named type of PathwayElement. References a PathwayElement TypeDef which links to attributes shared by all instances of this type.	Ref [IfcTypeDefinition]	n/a	n/a	NIL	n/a	
InletPointConnections				Specifies which IfcPointConnectors are inlets. All remaining IfcPointConnectors are therefore outlets.	List [0:N] Ref [IfcPointConnector]	n/a	n/a	NIL	n/a	
MaterialLayerSet				Material layer set the pathway element is constructed with. We use a material layer set to allow multiple materials to be used to construct a pathway element.	Ref [IfcMaterialLayerSet]	n/a	n/a	NIL	n/a	
IsMountedOn				IfcObject that the device is mounted upon or attached to, such as a wall or structural support. This relationship allows the PathwayElement to appropriately move if the object it is 'mounted' upon is moved, while maintaining its system interconnectivity.	Ref[IfcObject]	n/a	n/a	NIL	n/a	
Description				A user-defined string description of the pathway element	IfcString	see type	see type	empty string	n/a	
IfcDamper				This class is used to control or reduce air flow in a duct system.						
InheritsFrom ----->				IfcPathwayElement						
I_Damper										
DamperType				Named type of Damper References a Damper TypeDef which links to attributes shared by all instances of this type.	Ref [IfcTypeDefinition]	n/a	n/a	NIL	n/a	
Inlet Connection				Inlet Connection references a Size AttDef which contains the shape and size of the connection (e.g., Att_RoundDuctConnection)	Ref [IfcAttDef]	n/a	n/a	NIL	n/a	
Outlet Connection				Outlet Connection references a Size AttDef which contains the shape and size of the connection (e.g., Att_RoundDuctConnection)	Ref [IfcAttDef]	n/a	n/a	NIL	n/a	
Frame Depth				The length (or depth) of the damper frame	IfcLengthMeasure	see type	see type	0.0	n/a	
SizingMethod				Enumeration that identifies whether the damper is sized nominally or with exact measurements	Enum [ Nominal, Exact ]	n/a	n/a	Nominal	n/a	
Manufacturer				The manufacturer of the damper assembly	IfcString	see type	see type	empty string	n/a	
Model				The manufacturer's model number of the damper assembly	IfcString	see type	see type	empty string	n/a	
WorkingPressure				The actual working pressure of the damper assembly	IfcPressureMeasure	see type	see type	0.0	n/a	

Copyright © International Alliance for Interoperability - 1996-1999

						occurrence =	<none defined>
						<b>DuctFitting</b>	
						< Any value >	
					BS-1	shared =	Pset_DuctFitting
						occurrence =	<none defined>
						<b>DuctSegment</b>	
						< Any value >	
					BS-1	shared =	Pset_DuctSegment
						occurrence =	<none defined>
						<b>Valve</b>	
						< Any value >	
					BS-1	shared =	Pset_Valve
						occurrence =	<none defined>
						<b>PipeFitting</b>	
						< Any value >	
					BS-1	shared =	Pset_PipeFitting
						occurrence =	<none defined>
						<b>PipeSegment</b>	
						< Any value >	
					BS-1	shared =	Pset_PipeSegment
						occurrence =	<none defined>
BS-1					<b>Damper</b>		Allows definition of defined types of dampers
						<b>IfcDamper</b>	
						<b>FireDamper</b>	
						< Any value >	
					BS-1	shared =	Pset_FireDamper
						occurrence =	<none defined>
						<b>SmokeDamper</b>	
						< Any value >	
					BS-1	shared =	Pset_SmokeDamper
						occurrence =	<none defined>
						<b>FireSmokeDamper</b>	
						< Any value >	
					BS-1	shared =	Pset_FireSmokeDamper
						occurrence =	<none defined>
						<b>BackdraftDamper</b>	
						< Any value >	
					BS-1	shared =	Pset_BackdraftDamper
						occurrence =	<none defined>
						<b>ControlDamper</b>	
						< Any value >	
					BS-1	shared =	Pset_ControlDamper
					BS-1	occurrence =	<none defined>
						<b>Louver</b>	
						< Any value >	
					BS-1	shared =	Pset_Louver
					BS-1	occurrence =	<none defined>
BS-1					<b>ControlElement</b>		Allows definition of defined types of control elements
						<b>IfcControlElement</b>	

				<b>Controller</b>		
				< Any value >		
				BS-1	shared =	Pset_Controller
					occurrence =	<none defined>
				<b>Sensor</b>		
				< Any value >		
				BS-1	shared =	Pset_Sensor
					occurrence =	<none defined>
BS-1				<b>Actuator</b>		Allows definition of defined types of actuators
				<b>IfcControlElement</b>		
				<b>LinearActuator</b>		
				< Any value >		
				BS-1	shared =	Pset_LinearActuator
				BS-1	occurrence =	Pset_ElectricActuator, Pset_PneumaticActuator, Pset_HydraulicActuator, Pset_HandOperatedActuator
				<b>RotationalActuator</b>		
				< Any value >		
				BS-1	shared =	Pset_RotationalActuator
				BS-1	occurrence =	Pset_ElectricActuator, Pset_PneumaticActuator, Pset_HydraulicActuator, Pset_HandOperatedActuator

### 6.3.3. Property Sets

The following table is pasted from the spreadsheet template "R3\_ObjectDefs\_d4.xls", sheet "PropertySet Definitions."

Property Set Name	Definition	Data Type	Min	Max	Default	Units
<b>Property name</b>						
<b>PreDefined Property Sets for IFC Release 2</b>						
Note: These tables define property sets for 3 purposes						
1. Shared property sets associated with a type (see TypeDefinition above)						
2. Variable property sets associated with a type (those which vary for each occurrence)						
3. Domain extension model extensions to classes in the IFC Core						
This table is divided into 3 parts, according to the purpose of the property set						
<b>Shared Property Sets defining Type</b>						
<b>BS-1 Model</b>						
<b>PathwayElement</b>	PointConnections, combined with the information in a connection type property set (i.e., Pset_RectangularDuctConnection, Pset_RoundDuctConnection) attached to the referenced IfcPointConnector, provide the required information for the type, size and location of physical connections.					
<b>Pset_AirTerminal</b>						
<b>Purpose</b>	This property set will be used by an IfcPathwayElement object for defining Air Terminals					
<b>AirTerminalType</b>	Enumeration defining the type of Air Terminal	Enum [ Supply, Return, Exhaust, Other ]	n/a	n/a	Supply	n/a
<b>Flowrate</b>	Maximum air flowrate for the terminal device	IfcVolumetricFlowrateMeasure	see type	see type	0.0	n/a
<b>PressureLoss</b>	Pressure loss through the terminal device	IfcPressureMeasure	see type	see type	0.0	n/a
<b>Throw</b>	The distance the air terminal throws the air (optional)	IfcLengthMeasure	see type	see type	0.0	n/a
<b>SoundLevel</b>	Design sound power level	IfcString	see type	see type	empty string	n/a
<b>ADPI</b>	Air diffusion performance index	REAL	0.0	0.0	0.0	n/a
<b>InletConnection</b>	Reference to the size and shape of the inlet connection (e.g., Pset_RoundDuctConnection)	Ref [IfcAttDef]	see type	see type	NIL	n/a
<b>OutletConnection</b>	Reference to the size and shape of the outlet connection (e.g., Pset_RoundDuctConnection)	Ref [IfcAttDef]	see type	see type	NIL	n/a

		<i>FinishType</i>	Enumeration that identifies the type of finish for the air terminal	Enum [ Anodized, Paint, None ]	n/a	n/a	None	n/a
		<i>FinishColor</i>	The finish color for the air terminal	IfcString	see type	see type	empty string	n/a
		<i>MountingFrame</i>	Frame for plaster, drywall, lay-in grid, etc.	IfcString	see type	see type	empty string	n/a
		<i>AdjustableCore</i>	Permits adjustment of throw	IfcString	see type	see type	empty string	n/a
		<i>CoreSetHorizontal</i>	Degree of blade set from the centerline	IfcPlaneAngleMeasure	see type	see type	0.0	n/a
		<i>CoreSetVertical</i>	Degree of blade set from the centerline	IfcPlaneAngleMeasure	see type	see type	0.0	n/a
		<i>IntegralDamper</i>	Reference to a damper object that is integral to the terminal device	Ref [IfcDamper]	see type	see type	NIL	n/a
		<i>IntegralControl</i>	Self powered temperature control	BOOL	FALSE	TRUE	FALSE	n/a
		<b>Pset_TerminalBox</b>						
		<b>Purpose</b>	This property set will be used by an IfcPathwayElement object to define Terminal Boxes					
		<i>TerminalBoxType</i>	Enumeration that identifies the type of terminal box: VAV, CV, VVRH, etc.	Enum [ VAV, CV, VAVReheat, CVReheat, FanPowered, VAVDualDuct, CVDualDuct ]	n/a	n/a	VAV	n/a
		<i>DesignFlowrate</i>	Maximum air flowrate for the terminal box	IfcVolumetricFlowrateMeasure	see type	see type	0.0	n/a
		<i>MinimumFlowrate</i>	Minimum air flowrate for the terminal box	IfcVolumetricFlowrateMeasure	see type	see type	0.0	n/a
		<i>PressureLoss</i>	Pressure loss through the terminal box	IfcPressureMeasure	see type	see type	0.0	n/a
		<i>SoundLevel</i>	Design sound power level	IfcString	see type	see type	empty string	n/a
		<b>Pset_DuctFitting</b>						
		<b>Purpose</b>	This property set will be used by an IfcPathwayElement object to define duct fittings. This property set is used in conjunction with an Pset_DuctDesignCriteria which defines common duct design parameters.					
		<i>PrimaryType</i>	Enumeration that identifies the primary type of fitting (i.e., elbow, transition, junction, etc.)	Enum [ Entry, Exit, Elbow, Transition, Junction, Obstruction, Hood, Other ]	n/a	n/a	Elbow	n/a
		<i>SubType</i>	Subtype of fitting (i.e., 5-gore, pleated, stamped, etc.)	IfcString	see type	see type	empty string	n/a
		<i>EnteringPressure</i>	Actual pressure required for balancing and maintenance	IfcPressureMeasure	see type	see type	0.0	n/a
		<i>Angle</i>	Angle of turn for elbows, transitions, etc.	IfcPlaneAngleMeasure	see type	see type	0.0	n/a
		<b>Pset_DuctSegment</b>						
		<b>Purpose</b>	This property set will be used by an IfcPathwayElement object to define duct segments. This property set is used in conjunction with an Pset_DuctDesignCriteria which defines common duct design parameters					
		<i>Flowrate</i>	Flowrate through the duct	IfcVolumetricFlowrateMeasure	see type	see type	0.0	n/a
		<i>EnteringPressure</i>	Actual pressure required for balancing and maintenance	IfcPressureMeasure	see type	see type	0.0	n/a
		<i>SupportMethod</i>	Reference to a duct hanger or other structural support from roof, floor, etc.	Ref [IfcObject]	see type	see type	NIL	n/a
		<i>FinishedLength</i>	The finished length of the duct segment	IfcLengthMeasure	see type	see type	0.0	n/a
		<i>LongitudinalSeam</i>	The type of seam to be used along the longitudinal axis of the duct segment	IfcString	see type	see type	empty string	n/a
		<i>Reinforcement</i>	The type of reinforcement used for the duct segment	IfcString	see type	see type	empty string	n/a
		<i>ReinforcementSpacing</i>	The spacing between reinforcing elements	IfcLengthMeasure	see type	see type	0.0	n/a
		<b>Pset_Valve</b>						
		<b>Purpose</b>	This property set will be used by an IfcPathwayElement object to define valves					
		<i>WorkingPressure</i>	Working pressure	IfcPressureMeasure	see type	see type	0.0	n/a
		<i>PressureDrop</i>	Pressure drop	IfcPressureMeasure	see type	see type	0.0	n/a
		<i>CloseOffRating</i>	Close off rating	IfcPressureMeasure	see type	see type	0.0	n/a
		<i>ValveCv</i>	Cv value for the valve	REAL	0.0	0.0	0.0	n/a
		<b>Pset_PipeFitting</b>						
		<b>Purpose</b>	This property set will be used by an IfcPathwayElement object to define pipe fittings. This property set is used in conjunction with an Pset_PipeDesignCriteria which defines common pipe design parameters					
		<i>PrimaryType</i>	Enumeration that identifies the primary type of fitting (i.e., elbow, transition, junction, etc.)	Enum [ Entry, Exit, Elbow, Transition, Junction, Obstruction, Other ]	n/a	n/a	Elbow	n/a
		<i>SubType</i>	Subtype of fitting (i.e., long-radius, short-radius,	IfcString	see type	see type	empty	n/a



			etc.)				string	
		EnteringPressure	Actual pressure required for balancing and maintenance	IfcPressureMeasure	see type	see type	0.0	n/a
		Angle	Angle of turn for elbows, transitions, etc.	IfcPlaneAngleMeasure	see type	see type	0.0	n/a
		<b>Pset_PipeSegment</b>						
		<b>Purpose</b>	This property set will be used by an IfcPathwayElement object to define pipe segments. This property set is used in conjunction with an Pset_PipeDesignCriteria which defines common pipe design parameters					
		Flowrate	Flowrate through the pipe	IfcVolumetricFlowrateMeasure	see type	see type	0.0	n/a
		EnteringPressure	Actual pressure required for balancing and maintenance	IfcPressureMeasure	see type	see type	0.0	n/a
		SupportMethod	Reference to a pipe hanger or other structural support from roof, floor, etc.	Ref [IfcObject]	see type	see type	NIL	n/a
		FinishedLength	The finished length of the pipe segment	IfcLengthMeasure	see type	see type	0.0	n/a
		<b>Pset_FireDamper</b>						
		<b>Purpose</b>	This property set will be used by an IfcDamper object to define the characteristics of a fire damper					
		ClosureRating	Enumeration that identifies the closure rating for the damper	Enum [ Dynamic, Static ]	n/a	n/a	Dynamic	n/a
		FireResistanceRating	Enumeration that identifies the fire resistance rating of the damper	Enum [ 1-1/2Hour, 3Hour ]	n/a	n/a	1-1/2Hour	n/a
		Mounting	Enumeration that identifies how the damper is mounted in the building	Enum [ Horizontal, Vertical ]	n/a	n/a	Vertical	n/a
		FusibleLinkTemperature	The temperature that the fusible link melts	IfcThermodynamicTemperatureMeasure	see type	see type	0.0	n/a
		SleeveLength	The length of the damper sleeve	IfcLengthMeasure	see type	see type	0.0	n/a
		SleeveThickness	The thickness of the damper sleeve	IfcLengthMeasure	see type	see type	0.0	n/a
		DamperLocationInSleeve	The location within the sleeve where the damper is mounted (e.g., Center)	IfcString	see type	see type	empty string	n/a
		<b>Pset_SmokeDamper</b>						
		<b>Purpose</b>	This property set will be used by an IfcDamper object to define the characteristics of a smoke damper					
		FrameThickness	The thickness of the damper frame	IfcLengthMeasure	see type	see type	0.0	n/a
		BladeType	The type of blade used in the damper (e.g., Triple Vee, Fabricated Airfoil, Extruded Airfoil, etc.)	IfcString	see type	see type	empty string	n/a
		Mounting	Enumeration that identifies how the damper is mounted in the building	Enum [ Horizontal, Vertical ]	n/a	n/a	Vertical	n/a
		ControlType	The type of control used to operate the damper (e.g., Open/Closed Indicator, Resettable Temperature Sensor, Temperature Override, etc.)	IfcString	see type	see type	empty string	n/a
		SleeveLength	The length of the damper sleeve	IfcLengthMeasure	see type	see type	0.0	n/a
		SleeveThickness	The thickness of the damper sleeve	IfcLengthMeasure	see type	see type	0.0	n/a
		DamperLocationInSleeve	The location within the sleeve where the damper is mounted (e.g., Center)	IfcString	see type	see type	empty string	n/a
		Actuator	Actuator references an Pset_Actuator AttDef which contains the actuator information, if an actuator is part of the damper assembly	Ref [IfcAttDef]	n/a	n/a	NIL	n/a
		<b>Pset_FireSmokeDamper</b>						
		<b>Purpose</b>	This property set will be used by an IfcDamper object to define the characteristics of a combination smoke and fire damper					
		FrameThickness	The thickness of the damper frame	IfcLengthMeasure	see type	see type	0.0	n/a
		FireResistanceRating	Enumeration that identifies the fire resistance rating of the damper	Enum [ 1-1/2Hour, 3Hour ]	n/a	n/a	1-1/2Hour	n/a
		BladeType	The type of blade used in the damper (e.g., Triple Vee, Fabricated Airfoil, Extruded Airfoil, etc.)	IfcString	see type	see type	empty string	n/a
		Mounting	Enumeration that identifies how the damper is mounted in the building	Enum [ Horizontal, Vertical ]	n/a	n/a	Vertical	n/a
		FusibleLinkTemperature	The temperature that the fusible link melts	IfcThermodynamicTemperatureMeasure	see type	see type	0.0	n/a
		ControlType	The type of control used to operate the damper (e.g., Open/Closed Indicator, Resettable Temperature Sensor, Temperature Override, etc.)	IfcString	see type	see type	empty string	n/a
		SleeveLength	The length of the damper sleeve	IfcLengthMeasure	see type	see type	0.0	n/a
		SleeveThickness	The thickness of the damper sleeve	IfcLengthMeasure	see type	see type	0.0	n/a
		DamperLocationInSleeve	The location within the sleeve where the damper is mounted (e.g., Center)	IfcString	see type	see type	empty string	n/a
		Actuator	Actuator references an Pset_Actuator AttDef which contains the actuator information, if an actuator is part of the damper assembly	Ref [IfcAttDef]	n/a	n/a	NIL	n/a
		<b>Pset_BackdraftDamper</b>						
		<b>Purpose</b>	This property set will be used by an IfcDamper object to define the characteristics of a backdraft damper					
		FrameType	The type of frame used by the damper (e.g., Standard, Single Flange, Single Reversed Flange,	IfcString	see type	see type	empty string	n/a

		Actuator	Double Flange, etc.) Actuator references an Pset_Actuator AttDef which contains the actuator information, if an actuator is part of the damper assembly	Ref [IfcAttDef]	n/a	n/a	NIL	n/a
		<b>Pset_ControlDamper</b>						
		<b>Purpose</b>	This property set will be used by an IfcDamper object to define the characteristics of a control damper					
		DesignAirVelocity	The design air velocity for the damper assembly	IfcLinearVelocityMeasure	see type	see type	0.0	n/a
		BladeAction	Enumeration that identifies the blade closing action for the damper	Enum [ Parallel, Opposed ]	n/a	n/a	Parallel	n/a
		BladeType	The type of blade used in the damper (e.g., Triple Vee, Fabricated Airfoil, Extruded Airfoil, etc.)	IfcString	see type	see type	empty string	n/a
		BladeMaterial	The primary material used to construct the damper blade	Ref [IfcMaterial]	n/a	n/a	NIL	n/a
		BladeThickness	The thickness of the damper blade	IfcLengthMeasure	see type	see type	0.0	n/a
		FrameType	The type of frame used by the damper (e.g., Standard, Single Flange, Single Reversed Flange, Double Flange, etc.)	IfcString	see type	see type	empty string	n/a
		FrameMaterial	The primary material used to construct the damper frame	Ref [IfcMaterial]	n/a	n/a	NIL	n/a
		FrameThickness	The thickness of the damper frame	IfcLengthMeasure	see type	see type	0.0	n/a
		Actuator	Actuator references an Pset_Actuator AttDef which contains the actuator information, if an actuator is part of the damper assembly	Ref [IfcAttDef]	n/a	n/a	NIL	n/a
		<b>Pset_Louver</b>						
		<b>Purpose</b>	This property set will be used by an IfcDamper object to define the characteristics of a louver					
		FrameType	The type of frame used by the louver (e.g., Standard, Drainable, etc.)	IfcString	see type	see type	empty string	n/a
		FrameThickness	The thickness of the louver frame	IfcLengthMeasure	see type	see type	0.0	n/a
		BladeType	The type of blade used in the louver (e.g., "J", "K", Chevron, Sightproof, Drainable, etc.)	IfcString	see type	see type	empty string	n/a
		BladeThickness	The thickness of the louver blade	IfcLengthMeasure	see type	see type	0.0	n/a
		ScreenType	The type of screen used in the louver (e.g., Birdscreen, Insect Screen, etc.)	IfcString	see type	see type	empty string	n/a
		Actuator	Actuator references an Pset_Actuator AttDef which contains the actuator information, if an actuator is part of the louver assembly	Ref [IfcAttDef]	n/a	n/a	NIL	n/a
		<b>Pset_LinearActuator</b>						
		<b>Purpose</b>	This property set will be used by an IfcControlElement object to define the characteristics of a linear actuator					
		FailDirection	Enumeration that identifies the behavior of the actuator in case of power failure	Enum [ FailIn, FailOut ]	n/a	n/a	FailIn	n/a
		Force	Indicates the maximum close-off force for the actuator	IfcForceMeasure	see type	see type	0.0	n/a
		Stroke	Indicates the maximum distance the actuator must traverse	IfcLengthMeasure	see type	see type	0.0	n/a
		<b>Pset_RotationalActuator</b>						
		<b>Purpose</b>	This property set will be used by an IfcControlElement object to define the characteristics of a rotational actuator					
		FailDirection	Enumeration that identifies the behavior of the actuator in case of power failure	Enum [ FailClockwise, FailCounterClockwise ]	n/a	n/a	FailClockwise	n/a
		Torque	Indicates the maximum close-off torque for the actuator	IfcTorqueMeasure	see type	see type	0.0	n/a
		Range	Indicates the maximum rotation the actuator must traverse	IfcPlaneAngleMeasure	see type	see type	0.0	n/a
		<b>Pset_Sensor</b>						
		<b>Purpose</b>	This property set will be used by an IfcControlElement object to define the characteristics of a sensor					
		SensorType	Enumeration that identifies the type of sensor	Enum [ Flow, Pressure, Temperature, Gas, Concentration, Volts, Amps, Density, Viscosity, Energy, Humidity, Other ]	n/a	n/a	Flow	n/a
		SensorDescription	Further elaboration on the type of sensor	IfcString	n/a	n/a	empty string	n/a
		SensedMedium	The medium interacting with the sensor	Ref[Pset_Fluid]	n/a	n/a	NIL	n/a
		SensorRange	The range of the sensor	REAL	0.0	0.0	0.0	n/a
		SensorAccuracy	The accuracy of the sensor	REAL	0.0	0.0	0.0	n/a
		<b>Pset_Controller</b>						
		<b>Purpose</b>	This property set will be used by an IfcControlElement object to define the characteristics of a controller					

		<i>InputObjects</i>	<i>Objects having an input to the controller</i>	<i>List [0:N] Ref [IfcObject]</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>
		<i>OutputObjects</i>	<i>Objects that have an output from the controller</i>	<i>List [0:N] Ref [IfcObject]</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>
		<b>Pset_ControlElementAnalogInput</b>						
		<b>Purpose</b>	<i>Analog input for a control element</i>					
		<i>Units</i>	<i>BACnetEngineeringUnits definition</i>	<i>IfcString</i>	<i>see type</i>	<i>see type</i>	<i>empty string</i>	<i>n/a</i>
		<i>HighLimit</i>	<i>The high limit value (optional)</i>	<i>REAL</i>	<i>0.0</i>	<i>0.0</i>	<i>0.0</i>	<i>n/a</i>
		<i>LowLimit</i>	<i>The low limit value (optional)</i>	<i>REAL</i>	<i>0.0</i>	<i>0.0</i>	<i>0.0</i>	<i>n/a</i>
		<i>Deadband</i>	<i>The deadband value (optional)</i>	<i>REAL</i>	<i>0.0</i>	<i>0.0</i>	<i>0.0</i>	<i>n/a</i>
		<i>LimitEnable</i>	<i>BACnetLimitEnable definition (optional)</i>	<i>IfcString</i>	<i>see type</i>	<i>see type</i>	<i>empty string</i>	<i>n/a</i>
		<i>EventEnable</i>	<i>BACnetEventTransitionBits definition (optional)</i>	<i>IfcString</i>	<i>see type</i>	<i>see type</i>	<i>empty string</i>	<i>n/a</i>
		<i>NotifyType</i>	<i>BACnetNotifyType definition (optional)</i>	<i>IfcString</i>	<i>see type</i>	<i>see type</i>	<i>empty string</i>	<i>n/a</i>
		<b>Pset_ControlElementAnalogOutput</b>						
		<b>Purpose</b>	<i>Analog output for a control element</i>					
		<i>Units</i>	<i>BACnetEngineeringUnits definition</i>	<i>IfcString</i>	<i>see type</i>	<i>see type</i>	<i>empty string</i>	<i>n/a</i>
		<i>HighLimit</i>	<i>The high limit value (optional)</i>	<i>REAL</i>	<i>0.0</i>	<i>0.0</i>	<i>0.0</i>	<i>n/a</i>
		<i>LowLimit</i>	<i>The low limit value (optional)</i>	<i>REAL</i>	<i>0.0</i>	<i>0.0</i>	<i>0.0</i>	<i>n/a</i>
		<i>Deadband</i>	<i>The deadband value (optional)</i>	<i>REAL</i>	<i>0.0</i>	<i>0.0</i>	<i>0.0</i>	<i>n/a</i>
		<i>LimitEnable</i>	<i>BACnetLimitEnable definition (optional)</i>	<i>IfcString</i>	<i>see type</i>	<i>see type</i>	<i>empty string</i>	<i>n/a</i>
		<i>EventEnable</i>	<i>BACnetEventTransitionBits definition (optional)</i>	<i>IfcString</i>	<i>see type</i>	<i>see type</i>	<i>empty string</i>	<i>n/a</i>
		<i>NotifyType</i>	<i>BACnetNotifyType definition (optional)</i>	<i>IfcString</i>	<i>see type</i>	<i>see type</i>	<i>empty string</i>	<i>n/a</i>
		<b>Pset_ControlElementBinaryInput</b>						
		<b>Purpose</b>	<i>Binary input for a control element</i>					
		<i>Polarity</i>	<i>BACnetPolarity definition</i>	<i>IfcString</i>	<i>see type</i>	<i>see type</i>	<i>empty string</i>	<i>n/a</i>
		<i>InactiveText</i>	<i>Inactive Text (optional)</i>	<i>IfcString</i>	<i>see type</i>	<i>see type</i>	<i>empty string</i>	<i>n/a</i>
		<i>ActiveText</i>	<i>Active Text (optional)</i>	<i>IfcString</i>	<i>see type</i>	<i>see type</i>	<i>empty string</i>	<i>n/a</i>
		<i>AlarmValue</i>	<i>BACnetBinaryPV definition (optional)</i>	<i>IfcString</i>	<i>see type</i>	<i>see type</i>	<i>empty string</i>	<i>n/a</i>
		<i>EventEnable</i>	<i>BACnetEventTransitionBits definition (optional)</i>	<i>IfcString</i>	<i>see type</i>	<i>see type</i>	<i>empty string</i>	<i>n/a</i>
		<i>AckedTransitions</i>	<i>BACnetEventTransitionBits definition (optional)</i>	<i>IfcString</i>	<i>see type</i>	<i>see type</i>	<i>empty string</i>	<i>n/a</i>
		<b>Pset_ControlElementBinaryOutput</b>						
		<b>Purpose</b>	<i>Binary output for a control element</i>					
		<i>Polarity</i>	<i>BACnetPolarity definition</i>	<i>IfcString</i>	<i>see type</i>	<i>see type</i>	<i>empty string</i>	<i>n/a</i>
		<i>InactiveText</i>	<i>Inactive Text (optional)</i>	<i>IfcString</i>	<i>see type</i>	<i>see type</i>	<i>empty string</i>	<i>n/a</i>
		<i>ActiveText</i>	<i>Active Text (optional)</i>	<i>IfcString</i>	<i>see type</i>	<i>see type</i>	<i>empty string</i>	<i>n/a</i>
		<i>MinimumOffTime</i>	<i>Minimum Off Time (optional)</i>	<i>IfcLocalTime</i>	<i>see type</i>	<i>see type</i>	<i>0:0</i>	<i>n/a</i>
		<i>MinimumOnTime</i>	<i>Minimum On Time (optional)</i>	<i>IfcLocalTime</i>	<i>see type</i>	<i>see type</i>	<i>0:0</i>	<i>n/a</i>
		<i>FeedbackValue</i>	<i>BACnetBinaryPV definition (optional)</i>	<i>IfcString</i>	<i>see type</i>	<i>see type</i>	<i>empty string</i>	<i>n/a</i>
		<i>EventEnable</i>	<i>BACnetEventTransitionBits definition (optional)</i>	<i>IfcString</i>	<i>see type</i>	<i>see type</i>	<i>empty string</i>	<i>n/a</i>
		<i>AckedTransitions</i>	<i>BACnetEventTransitionBits definition (optional)</i>	<i>IfcString</i>	<i>see type</i>	<i>see type</i>	<i>empty string</i>	<i>n/a</i>
		<b>Pset_ControlElementMultiStateInput</b>						
		<b>Purpose</b>	<i>Multi-state input for a control element</i>					
		<i>NumberOfStates</i>		<i>INT</i>	<i>0</i>	<i>32726</i>	<i>0</i>	<i>n/a</i>
		<i>StateText</i>		<i>List [0:?] IfcString</i>	<i>see type</i>	<i>see type</i>	<i>empty string</i>	<i>n/a</i>
		<i>AlarmValues</i>	<i>(optional)</i>	<i>List [0:?] REAL</i>	<i>0.0</i>	<i>0.0</i>	<i>0.0</i>	<i>n/a</i>
		<i>EventEnable</i>	<i>BACnetEventTransitionBits definition (optional)</i>	<i>IfcString</i>	<i>see type</i>	<i>see type</i>	<i>empty string</i>	<i>n/a</i>
		<i>NotifyType</i>	<i>BACnetNotifyType definition (optional)</i>	<i>IfcString</i>	<i>see type</i>	<i>see type</i>	<i>empty string</i>	<i>n/a</i>
		<b>Pset_ControlElementMultiStateOutput</b>						

		<b>Purpose</b>	Multi-state output for a control element					
		NumberOfStates		INT	0	32726	0	n/a
		StateText		List [0:?] IfcString	see type	see type	empty string	n/a
		EventEnable	BACnetEventTransitionBits definition (optional)	IfcString	see type	see type	empty string	n/a
		NotifyType	BACnetNotifyType definition (optional)	IfcString	see type	see type	empty string	n/a
		<b>Pset_ControlElementEventEnrollment</b>						
		<b>Purpose</b>	The events which a control element participates					
		EventType	BACnetEventType definition	IfcString	see type	see type	empty string	n/a
		NotifyType	BACnetNotifyType definition	IfcString	see type	see type	empty string	n/a
		EventParameters	BACnetEventParameter definition	IfcString	see type	see type	empty string	n/a
		ObjectPropertyReference	BACnetObjectPropertyReference definition	IfcString	see type	see type	empty string	n/a
		EventEnable	BACnetEventTransitionBits definition	IfcString	see type	see type	empty string	n/a
		Recipient	BACnetRecipient definition (optional)	IfcString	see type	see type	empty string	n/a
		ProcessIdentifier	BACnetEventTransitionBits definition (optional)	REAL	0.0	0.0	0.0	n/a
		IssueConfirmedNotifications	(optional)	BOOL	FALSE	TRUE	FALSE	n/a
		<b>Pset_ControlElementLoop</b>						
		<b>Purpose</b>	Loop definition for a control element					
		NumberOfStates		INT	0	32726	0	n/a
		OutputUnits	BACnetEngineeringUnits definition	IfcString	see type	see type	empty string	n/a
		ManipulatedVariableReference	BACnetObjectPropertyReference definition	IfcString	see type	see type	empty string	n/a
		ControlledVariableReference	BACnetObjectPropertyReference definition	IfcString	see type	see type	empty string	n/a
		ControlledVariableUnits	BACnetEngineeringUnits definition	IfcString	see type	see type	empty string	n/a
		SetpointReference	BACnetSetpointReference definition	IfcString	see type	see type	empty string	n/a
		Action	BACnetAction definition	IfcString	see type	see type	empty string	n/a
		PriorityForWriting		List [0:?] REAL	0.0	0.0	0.0	n/a
		EventEnable	BACnetEventTransitionBits definition (optional)	IfcString	see type	see type	empty string	n/a
		NotifyType	BACnetNotifyType definition (optional)	IfcString	see type	see type	empty string	n/a
<b>Type driven properties that vary for each occurrence</b>								
<b>BS-1 Model</b>								
<b>Control Elements</b>								
		<b>Pset_ElectricActuator</b>						
		<b>Purpose</b>	This property set will be used by an IfcControlElement object to define the characteristics of an electric actuator					
		ManualOverride	Identifies whether hand-operated operation is provided as an override	BOOL	FALSE	TRUE	FALSE	n/a
		InputPower	Maximum input power requirement	IfcPowerMeasure	see type	see type	0.0	n/a
		<b>Pset_PneumaticActuator</b>						
		<b>Purpose</b>	This property set will be used by an IfcControlElement object to define the characteristics of a pneumatic actuator					
		ManualOverride	Identifies whether hand-operated operation is provided as an override	BOOL	FALSE	TRUE	FALSE	n/a
		InputPressure	Maximum input control air pressure requirement	IfcPressureMeasure	see type	see type	0.0	n/a
		InputFlowrate	Maximum input control air flowrate requirement	IfcVolumetricFlowrateMeasure	see type	see type	0.0	n/a
		<b>Pset_HydraulicActuator</b>						
		<b>Purpose</b>	This property set will be used by an IfcControlElement object to define the characteristics of a hydraulic actuator					
		ManualOverride	Identifies whether hand-operated	BOOL	FALSE	TRUE	FALSE	n/a

				operation is provided as an override					
			InputPressure	Maximum design pressure for the actuator	IfcPressureMeasure	see type	see type	0.0	n/a
			InputFlowrate	Maximum hydraulic flowrate requirement	IfcVolumetricFlowrateMeasure	see type	see type	0.0	n/a
			<b>Pset_HandOperatedActuator</b>						
			<b>Purpose</b>	This property set will be used by an IfcControlElement object to define the characteristics of a hand operated actuator					
			ManualOverride	Identifies whether hand-operated operation is provided as an override	BOOL	FALSE	TRUE	FALSE	n/a
			<b>Design Criteria</b>						
			<b>Pset_DuctDesignCriteria</b>						
			<b>Purpose</b>	This property set will typically be used in conjunction with Pset_Fluid and Pset_Insulation.					
			DesignName	A name for the design values	IfcString	see type	see type	empty string	n/a
			SizingMethod	Enumeration that identifies the methodology to be used to size system components	Enum [ ConstantFriction, ConstantPressure, StaticRegain ]	n/a	n/a	ConstantFriction	n/a
			PressureClass	Nominal pressure rating of the system components	IfcPressureMeasure	see type	see type	0.0	n/a
			LeakageClass	Nominal leakage rating for the system components	IfcPressureMeasure	see type	see type	0.0	n/a
			FrictionLoss	The pressure loss due to friction per unit length	IfcPressureMeasure/IfcLengthMeasure	see type	see type	0.0	n/a
			LiningType	The insulating lining type to be used	Ref[Pset_Insulation]	n/a	n/a	NIL	n/a
			InsulationType	The insulation type to be used	Ref[Pset_Insulation]	n/a	n/a	NIL	n/a
			ScrapFactor	Sheet metal scrap factor	REAL	0.0	0.0	0.0	n/a
			DuctSealant	Type of sealant used on the duct and fittings	IfcString	see type	see type	empty string	n/a
			MaximumVelocity	The maximum design velocity of the air in the duct or fitting	IfcLinearVelocityMeasure	see type	see type	0.0	n/a
			AspectRatio	The default aspect ratio	REAL	0.0	0.0	0.0	n/a
			MinimumHeight	The minimum duct height for rectangular, oval or round duct	IfcLengthMeasure	see type	see type	0.0	n/a
			MinimumWidth	The minimum duct width for oval or rectangular duct	IfcLengthMeasure	see type	see type	0.0	n/a
			<b>Pset_DuctSystemDesignCriteria</b>						
			<b>Purpose</b>	This property set will typically be used in conjunction with Pset_Fluid and Pset_Insulation					
			SystemType	Enumeration that identifies the type of system	Enum [ VariableAirVolume, ConstantVolume, DoubleDuct ]	n/a	n/a	VariableAirVolume	n/a
			SystemDescription	System description	IfcString	see type	see type	empty string	n/a
			SystemLocation	Physical description of the part of the building the system serves	IfcString	see type	see type	empty string	n/a
			<b>Pset_PipeDesignCriteria</b>						
			<b>Purpose</b>	This property set will typically be used in conjunction with Pset_Fluid and Pset_Insulation.					
			DesignName	A name for the design values	IfcString	see type	see type	empty string	n/a
			SizingMethod	Enumeration that identifies the sizing method to be used if different from the system design criteria	Enum [ ConstantFriction, ConstantPressure ]	n/a	n/a	ConstantFriction	n/a
			PressureClass	Nominal pressure rating of the piping system components (i.e., 125, 250, etc.)	IfcPressureMeasure	see type	see type	0.0	n/a
			MaximumVelocity	The maximum allowable fluid velocity	IfcLinearVelocityMeasure	see type	see type	0.0	n/a
			InsulationType	The insulation type to be used	Ref[Pset_Insulation]	n/a	n/a	NIL	n/a
			<b>Pset_PipeSystemDesignCriteria</b>						
			<b>Purpose</b>	This property set will typically be used in conjunction with Pset_Fluid and Pset_Insulation					
			SystemType	Enumeration that identifies the type of system	Enum [ DomesticHotWater, ChilledWater, CondenserWater, HeatingHotWater, Steam ]	n/a	n/a	ChilledWater	n/a
			SystemDescription	System description	IfcString	see type	see type	empty string	n/a
			SystemLocation	Physical description of the part of the building the system serves	IfcString	see type	see type	empty string	n/a
			FluidSourcePressure	Pressure in main for domestic water, sprinklers, system pressure for hydronic systems, etc.	IfcPressureMeasure	see type	see type	0.0	n/a

			<i>FluidLiftHeight</i>	<i>Lift that may be required on open systems with dense fluids</i>	<i>IfcPressureMeasure</i>	<i>see type</i>	<i>see type</i>	<i>0.0</i>	<i>n/a</i>
<b>Physical Connection Sizes</b>									
			<b>Pset_RectangularDuctConnection</b>						
			<b>Purpose</b>	<i>This property set provides size information about a rectangular duct connection</i>					
			<i>Width</i>	<i>Width of rectangular duct</i>	<i>IfcLengthMeasure</i>	<i>see type</i>	<i>see type</i>	<i>0.0</i>	<i>n/a</i>
			<i>Height</i>	<i>Height of rectangular duct</i>	<i>IfcLengthMeasure</i>	<i>see type</i>	<i>see type</i>	<i>0.0</i>	<i>n/a</i>
			<i>ConnectionType</i>	<i>Enumeration that identifies the type of connection</i>	<i>Enum [ DriveSlip, S-Slip, Flanged, SlipOn, StandingSeam, Angles, Other ]</i>	<i>n/a</i>	<i>n/a</i>	<i>Flanged</i>	<i>n/a</i>
			<b>Pset_RoundDuctConnection</b>						
			<b>Purpose</b>	<i>This property set provides size information about a round duct connection</i>					
			<i>Diameter</i>	<i>Diameter of round duct</i>	<i>IfcLengthMeasure</i>	<i>see type</i>	<i>see type</i>	<i>0.0</i>	<i>n/a</i>
			<i>ConnectionType</i>	<i>Enumeration that identifies the type of connection</i>	<i>Enum [ BeadedSleeve, Drawband, OutsideSleeve, Flanged, Crimp, Swedge, Other ]</i>	<i>n/a</i>	<i>n/a</i>	<i>Flanged</i>	<i>n/a</i>
			<b>Pset_OvalDuctConnection</b>						
			<b>Purpose</b>	<i>This property set provides size information about an oval duct connection</i>					
			<i>Width</i>	<i>Width of oval duct</i>	<i>IfcLengthMeasure</i>	<i>see type</i>	<i>see type</i>	<i>0.0</i>	<i>n/a</i>
			<i>Height</i>	<i>Height of oval duct</i>	<i>IfcLengthMeasure</i>	<i>see type</i>	<i>see type</i>	<i>0.0</i>	<i>n/a</i>
			<i>ConnectionType</i>	<i>Enumeration that identifies the type of connection</i>	<i>Enum [ BeadedSleeve, Drawband, OutsideSleeve, Flanged, Crimp, Swedge, Other ]</i>	<i>n/a</i>	<i>n/a</i>	<i>Flanged</i>	<i>n/a</i>
			<b>Pset_PipeConnection</b>						
			<b>Purpose</b>	<i>This property set provides size information about a pipe connection</i>					
			<i>NominalDiameter</i>	<i>Nominal diameter of pipe</i>	<i>IfcLengthMeasure</i>	<i>see type</i>	<i>see type</i>	<i>0.0</i>	<i>n/a</i>
			<i>ConnectionType</i>	<i>Enumeration that identifies the type of connection</i>	<i>Enum [ Flanged, Screwed, Welded, BellAndSpigot, Threaded, Other ]</i>	<i>n/a</i>	<i>n/a</i>	<i>Flanged</i>	<i>n/a</i>
<b>CoordinationRequirement</b>									
			<b>Pset_CoordinationRequirement</b>						
			<b>Purpose</b>	<i>This property set provides a placeholder for interoperable coordination requirements between different disciplines</i>					
			<i>OriginatingActor</i>	<i>The actor which originates the coordination requirement</i>	<i>Ref [IfcActor]</i>	<i>see type</i>	<i>see type</i>	<i>NIL</i>	<i>n/a</i>
			<i>AffectedActor</i>	<i>The actor which must act upon the coordination requirement</i>	<i>Ref [IfcActor]</i>	<i>see type</i>	<i>see type</i>	<i>NIL</i>	<i>n/a</i>
			<i>Requirement</i>	<i>The coordination requirement</i>	<i>IfcString</i>	<i>see type</i>	<i>see type</i>	<i>empty string</i>	<i>n/a</i>

## 6.4. [BS-3] Pathway Design and Coordination

### 6.4.1. Object Types

None defined in this project

### 6.4.2. Type Definitions

None defined in this project

### 6.4.3. Property Sets

None defined in this project

## 6.5. [BS-4] HVAC Loads Calculation

### 6.5.1. Object Types

None defined in this project

### 6.5.2. Type Definitions

None defined in this project

### 6.5.3. Property Sets

None defined in this project

## 6.6. [CS-1] Code Checking - Energy Codes

### 6.6.1. Object Types

Class name		OPTIONal, INVERSE flags, SELF - redeclared relationship				
Interface			Data type/Related type			
	Attribute/Relationship		or Superclasses	Min	Max	Default
<b>IfcBuildingEnvelope</b>			<i>IfcBuildingObject</i>			
	<b>I_BuildingEnvelope</b>					
	ThermalElements	OPT	Set[0:N] Ref[IfcLayeredElement]	see type	see type	NIL
	OccupancyType	OPT	IfcEnvelopeOccupancyTypeEnum	n/a	n/a	NIL
	InternalLoadDensity	OPT	IfcReal	0	10	0
	ThermalLoad	OPT	IfcReal	0	1.00E+16	0
<b>IfcIntent</b>			<i>IfcControlObject</i>			
	<b>I_Intent</b>					
	Source	IfcOwnerId	n/a	n/a	n/a	
	Description	IfcString	n/a	n/a	Unknown	
<b>IfcLightingFixture</b>			<i>IfcFixture</i>			
	<b>I_LightingFixture</b>					
	Category	OPT	Ref[IfcLightingFixtureTypeLibraryEntry]	n/a	n/a	n/a
	LampType	OPT	IfcLampTypeEnum	n/a	n/a	n/a
	LampDescription	OPT	IfcString	n/a	n/a	n/a
	WattagePerLamp	OPT	IfcInteger	0	2000	0
	NumberOfLampsPerFixture	OPT	IfcReal	0	4.00E+01	0
	FixtureIdentification	OPT	IfcString	n/a	n/a	n/a
	FixtureWattage	OPT	IfcInteger	0	3000	0
	BallastType	OPT	IfcBallastTypeEnum	n/a	n/a	n/a

		NumberOfFixtures	OPT	IfcInteger	0	1000	0
		<b>IfcLightingFixtureType</b>					
		<b>I_LightingFixtureType</b>					
		Description	OPT	IfcString	n/a	n/a	n/a
		LampType	OPT	IfcLampTypeEnum	n/a	n/a	n/a
		LampDescription	OPT	IfcString	n/a	n/a	n/a
		WattagePerLamp	OPT	IfcInteger	0	2000	0
		BallastType	OPT	IfcBallastTypeEnum	n/a	n/a	n/a
		<b>IfcPropertyConstraint</b>					
		<b>I_PropertyConstraint</b>					
		Source	OPT	IfcOwnerId	n/a	n/a	n/a
		ReferenceObject	OPT	IfcProjectObject/ IfcAttributeObject	n/a	n/a	NIL
		Relation	OPT	IfcNumericRelation	see type	see type	NIL
		ConstraintType	OPT	IfcConstraintLevel	see type	see type	NIL
		NoticeText	OPT	IfcString	n/a	n/a	NIL

## 6.6.2. Type Definitions

<b>Type</b>
IfcEnvelopeOccupancyTypeEnum
IfcLightingOccupancyType
IfcLightingScopeEnum

## 6.6.3. Property Sets

PreDefined PropertySets in CS1 Code Checking - Energy Codes						
PropertySet (Pset) Name						
	Attribute or Relation name	Definition	Data Type or Related Object	Min	Max	Default
Shared PropertySets defining Type						
(** No SharedPropertySets defined in this schema **)						
Type driven PropertySets that vary for each occurrence						
Pset_SystemLighting						
	LightingScope		IfcLightingScopeEnum	See type	See type	Zone
	SystemElements	Contains references to all instances of IfcFixture that are part of the lighting system	Ref[IfcFixture]	see type	see type	NIL
	OccupancyType	Lighting occupancy type according to the Standard	IfcLightingOccupancyType	n/a	n/a	NIL



		LightingPowerDensity	Lighting power density specified by the Code (based on Occupancy type)	IfcReal	0	10	0
		LightingPower	Total lighting power for the proposed design	IfcReal	0	1.00E+16	0

## 6.7. [CS-2] Code Checking Extensions

### 6.7.1. Object Types

	Class Name								
				Interface name		{( "Ref" = relationship )}			
				Attribute / Relation name	Definition	Data Type or Related Object Type	Min	Max	Default Units
				<b>IFC R2.0 CS-2 Project</b>					
				<b>--&gt; Classes/Interfaces/Attributes/Relationships/Defined Types</b>					
1				IfcRamp	This class provide an inclined way connecting one level to another.				
				InheritsFrom ----->	IfcAssembledElement				
				I_Ramp					
				hasElements	list of IfcRampElement which can be a flight or landing	List [1:N] IfcRampElement	n/a	n/a	NIL n/a
2				IfcRampElements					
				InheritsFrom ----->	IfcBuildingElement				
				I_RampElements					
				RampElementsType	Predefined generic types of ramp element which can be a landing or a flight	Ref[IfcTypeDefinition]	n/a	n/a	NIL n/a
				hasFootPath	center line of the path of IfcRampElement	IfcPolyCurve3D	n/a	n/a	NIL n/a
				hasElementOutline	closed 3D curve profile to describe the outline of the IfcRampElement	IfcCurve3D	n/a	n/a	NIL n/a
				hasSideElements	side element is building object that attached to ramp element e.g. wall, column, balustrade	List [2:N] IfcSideElement	n/a	n/a	NIL n/a
				hasEffectiveWidth	Minimum clear width of the ramp element	IfcReal	n/a	n/a	NIL n/a
				hasFloorMaterial	Predefined generic types of approved ramp material which can be clay tiles, carpet, rubber sheet	Ref[IfcTypeDefinition]	n/a	n/a	NIL n/a
3				IfcLanding					
				InheritsFrom ----->	IfcBuildingElement				
				I_Landing					
				hasEffectiveLength	Minimum clear length for packing a stationary wheelchair on the landing	IfcReal	n/a	n/a	NIL n/a

							<i>hasFloorLevel</i>	Floor level of A landing	<i>IfcReal</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>
4							<b>IfcFlight</b>						
							<i>InheritsFrom -----&gt;</i>	<i>IfcBuildingElement</i>					
							<b>I_Flight</b>						
							<i>hasVerticalRise</i>	<i>change in floor level</i>	<i>IfcReal</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>
							<i>hasHorizontalRun</i>	<i>length of the run</i>	<i>IfcReal</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>
5							<b>IfcSideElement</b>						
							<i>InheritsFrom -----&gt;</i>	<i>IfcBuildingElement</i>					
							<b>I_SideElement</b>						
							<i>SideElementType</i>	<i>Predefined generic types of side elements e.g. Enum (wall, column, balustrade)</i>	<i>Ref[IfcTypeDefinition]</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>
							<i>hasBaluster</i>	<i>baluster can also be handrails, railing</i>	<i>IfcBalusterType</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>
6							<b>IfcBaluster</b>						
							<i>InheritsFrom -----&gt;</i>	<i>IfcBuildingElement</i>					
							<b>I_Baluster</b>						
							<i>BalusterType</i>	<i>Predefined generic types of baluster or handrail</i>	<i>Ref[IfcTypeDefinition]</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>
							<i>hasProfile</i>	<i>Polycurve that defines the Path of baluster</i>	<i>IfcPolyCurve3D</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>
							<i>hasGrippingArea</i>	<i>Gripping area of the baluster</i>	<i>IfcArea</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>
7							<b>IfcLift</b>						
							<i>InheritsFrom -----&gt;</i>	<i>IfcEquipment</i>					
							<b>I_Lift</b>						
							<i>LiftType</i>	<i>Predefined types of lift e.g. Enum (Disabled, Cargo, Fire etc)</i>	<i>Ref[IfcTypeDefinition]</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>
							<i>hasEffectiveWidth</i>	<i>Minimum clear width for the maneuvering of wheelchair into the lift</i>	<i>IfcReal</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>
							<i>hasEffectiveLength</i>	<i>Minimum clear length for packing A stationary wheelchair in the lift</i>	<i>IfcReal</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>
							<i>hasEffectiveTurningArea</i>	<i>Minimum area for turning of A wheelchair in the life and at the doorway of the lift</i>	<i>IfcArea</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>
							<i>ServingStore</i>	<i>Stories being served by the lift</i>	<i>List [1:N] IfcBuildingStorey</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>
8							<b>IfcSymbol</b>						
							<i>InheritsFrom -----&gt;</i>	<i>IfcEquipment</i>					
							<b>I_Symbol</b>						
							<i>SymbolType</i>	<i>Predefined types of symbol e.g. Enum (Disabled, Fire etc)</i>	<i>Ref[IfcTypeDefinition]</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>
							<i>Placement</i>	<i>Position of symbol</i>	<i>IfcPoint</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>
9							<b>IfcExitFacility</b>						
							<i>InheritsFrom -----&gt;</i>	<i>IfcSpace</i>					
							<b>I_ExitFacility</b>						
							<i>ExitFacilityType</i>	<i>Predefined types of symbol e.g. Enum (Disabled, Fire etc)</i>	<i>Ref[IfcTypeDefinition]</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>

								<i>hasFireRating</i>	Number of hours	<i>IfcReal</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>
								<i>hasCapacity</i>	Maximum numbers of occupant passing through the facility at any one time	<i>IfcInteger</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>
								<i>hasEffectiveWidth</i>	Effective width of the facility	<i>IfcReal</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>
10								<b>IfcExitApproach</b>						
								<i>InheritsFrom</i> ----->	<i>IfcSpace</i>					
								<b>I_ExitApproach</b>						
								<i>ExitApproachType</i>	Predefined generic types of exit approach e.g. Enum (e.g. exit passageway, exit corridor, exit lobby, exist staircase).	<i>Ref[IfcTypeDefinition]</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>
								<i>OtherRelatedUsage</i>	Predefined generic types of other usage for exit approach e.g. Enum (e.g. area of refuge, area of fire fighting).	List [1:n] of <i>[IfcTypeDefinition]</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>
								<i>HasFireResistanceProvision</i>	list of fire resistance provision	List [1:N] <i>IfcFireResistanceProvision</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>
								<i>HasOpening</i>	list of openings	List [1:N] <i>IfcOpening</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>
11								<b>IfcFireResistanceProvision</b>						
								<i>InheritsFrom</i> ----->	<i>IfcEquipment</i>					
								<b>I_FireResistanceProvision</b>						
								<i>FireResistanceProvisionType</i>	- Predefined generic types of fire resistance provision e.g. Enum (e.g. smoke-free, sprinklered, naturally ventilated, mechanically ventilated equipment).	<i>Ref[IfcTypeDefinition]</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>
12								<b>IfcDoor</b>						
								<i>InheritsFrom</i> ----->	<i>IfcFillingElement</i>					
								<b>I_Door</b>						
								<i>OpenType</i>	Predefined generic types to describe how door is opened (e.g. Sliding, Swing, one-way or two way)	<i>Ref[IfcTypeDefinition]</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>
								<i>SwingDirection</i>	Predefined generic types to describe the swing directions with respect to A pivot (pull and push Side of the swing to be indicated)	<i>Ref[IfcTypeDefinition]</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>
								<i>ClearanceSpace</i>	area of a square bounding the swing of a door	<i>IfcArea</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>
13								<b>IfcBuilding</b>						
								<i>InheritsFrom</i> ----->	<i>IfcBuildingObject</i>					
								<b>I_Building</b>						
								<i>BuildingUsage</i>	- Predefined generic types to describe usage of building e.g. Enum (commercial, residential). This will in turn links to the occupancy load	<i>Ref[IfcTypeDefinition]</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>
								<i>OccupancyLoad</i>	Estimated maximum numbers of peoples likely to occupy the building at any one time	<i>IfcInteger</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>
14								<b>IfcZone</b>						
								<i>InheritsFrom</i> ----->	<i>IfcSpaceElement</i>					
								<b>I_Zone</b>						
								<i>ZoneUsage</i>	Add to Predefined type of <i>IfcZoneUsage</i> to cover Fire compartment or zone with Fire-protected provision (including smoke, sprinkler) and disabled access provision	<i>Ref[IfcTypeDefinition]</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>
								<i>OccupancyLoad</i>	Estimated maximum numbers of peoples likely to occupy the zone at any one time	<i>IfcInteger</i>	<i>n/a</i>	<i>n/a</i>	<i>NIL</i>	<i>n/a</i>

[illegible]

### 6.7.2. Type Definitions

IfcFireProtectionProvisionEnum	
	smokeFree
	sprinklered
	naturallyVentilated
	mechanicallyVentilated

### 6.7.3. Property Sets

PreDefined PropertySets in CS1 Code Checking - Energy Codes							
PropertySet (Pset) Name							
	Attribute or Relation name	Definition	Data Type or Related Object	Min	Max	Default	
Pset_SystemLighting							
	LightingScope		IfcLightingScopeEnum	See type	See type	Zone	
	SystemElements	Contains references to all instances of IfcFixture that are part of the lighting system	Ref[IfcFixture]	see type	see type	NIL	
	OccupancyType	Lighting occupancy type according to the Standard	IfcLightingOccupancyType	n/a	n/a	NIL	
	LightingPowerDensity	Lighting power density specified by the Code (based on Occupancy type)	IfcReal	0	10	0	
	LighingPower	Total lighting power for the proposed design	IfcReal	0	1.00E+16	0	





					<b>IfcPlan</b>	general class for all types of plans for AEC/FM projects						
					InheritsFrom ----->	IfcControlObject						
					<b>I_Plan</b>							
					PlanID	identifier of the plan	IfcString	n/a	n/a	empty string	n/a	
					PlanName	name of the plan	IfcString	n/a	n/a	empty string	n/a	
					PlanDescription	general description of the plan	Set [0:N] of IfcString	n/a	n/a	empty set	n/a	
					PlanCreator	the authors of the plan	Set [0:N] of Ref. to IfcActor	n/a	n/a	empty set	n/a	
					CreationDate	the date that the plan is created	IfcDate	see type	see type	see type	see type	
					<b>I_PlanProject</b>							
					Project	the project that the plan is created for	Ref. to IfcProject	see type	see type	NIL	see type	
					<b>I_PlanApproval</b>							
					Approval	the approval information about the plan, such as approving persons, approving status, etc.	Ref. to IfcApproval	see type	see type	NIL	see type	
					<b>IfcOccupancySchedule</b>	represents a space occupancy schedule						
					InheritsFrom ----->	IfcControlObject						
					<b>I_OccupancySchedule</b>							
					OccupyingActions	represents all the occupancy actions such as move actions and work tasks for the occupancy plan	Set [0:N] of Ref. to IfcProcessObject	n/a	n/a	empty set	n/a	
					PredsAndSuccs	sequential relationships between the occupancy actions for the schedule	Set [0:N] of Ref. to IfcRelSequence	n/a	n/a	empty set	n/a	
					ScheduleData	all the time related scheduling data about the schedule such as start time, finish time, etc.	Att_ScheduleData	see type	see type	see type	see type	
					<b>I_OccupancyScheduleResponsible</b>							
					Responsible	the person who is responsible for this schedule	Ref. to IfcActor	see type	see type	NIL	see type	
					<b>IfcMoveAction</b>	represent each of the move of people						
					InheritsFrom ----->	IfcProcessObject						
					<b>I_MoveActionElement</b>							
					OccupantsToMove	people who are moving out or in the spaces	Set [0:N] of Ref. To IfcActor	n/a	n/a	empty set	n/a	Yes
					FF&EToMove	the furniture, fixture and equipment that are moved out or in the spaces	Set [0:N] of Ref. To IfcElement	n/a	n/a	empty set	n/a	Yes
					<b>I_MoveAction</b>							
					MoveFrom	the space from which people or FF&E are moving out of	Ref. To IfcSpace	n/a	n/a	NIL	n/a	Yes
					MoveTo	the space to which people or FF&E are moving into	Ref. To IfcSpace	n/a	n/a	NIL	n/a	No
					Schedule	time related information for this move action such as start time, etc.	Att_ScheduleData	see type	see type	see type	see type	Yes
					Constraints	the constraints that tie this move action	Set [0:N] of IfcMoveActionConstraint	n/a	n/a	empty set	n/a	Yes
					Responsible	the person who is responsible for this action	Ref. To IfcActor	n/a	n/a	NIL	n/a	Yes
					<b>IfcMoveActionConstraint</b>	the ocnstraint for a move action						
					InheritsFrom ----->	IfcControlObject						
					<b>I_MoveActionConstraint</b>							
					ConstraintType	type of the constraint such as as soon as possible, as late as possible, must move out by, etc.	IfcString	n/a	n/a	empty string	n/a	No
					ConstraintDate	the date requiement for certain constrainttype such as must move out by 'date', etc.	IfcDate	see type	see type	see type	see type	Yes
					<b>IfcMovePlan</b>	the plan for moving people and FF&E						
					InheritsFrom ----->	IfcPlan						
					<b>I_MovePlan</b>							
					OccupancySchedule	the schedule for the move plan	Ref. To	n/a	n/a	NIL	n/a	Yes

[illegible]



					<b>IfcInventory</b>	represents a general inventory information; supertype of space inventory, furniture inventory and equipment inventory								
					<b>I_Inventory</b>									
					InventoryDescription	general description of the inventory	IfcString	n/a	n/a	empty sting	n/a	Yes		
					InventoryScope	this can reference to a building, storey, or space	Ref. to IfcProductObject	n/a	n/a	NIL	n/a	No		
					InventoryJurisdiction	the organizational unit of the inventory	Ref. to IfcActor	n/a	n/a	NIL	n/a	No		
					InventoryResponsible	persons who are responsible for the inventory	Set [0:N] of Ref. to IfcActor	n/a	n/a	empty set	n/a	Yes		
					LastUpdateDate	date of last update	IfcDate	see type	see type	see type	see type	No		
					<b>IfcDocument</b>	represents a general document of anytype								
					InheritsFrom ----->	IfcControlObject, IfcProductObject								
					<b>I_Document</b>									
					GenericDocumentType	used to differentiate between an electronic and a paper document	IfcTypeDefinition	see type	see type	see type	see type	No		
					DocumentType	used to differentiate between a drawing and specification, and etc.	IfcTypeDefinition	see type	see type	see type	see type	No		
					<b>IfcInteraction</b>	represents interactive relationships between two IFC objects								
					InheritsFrom ----->	IfcControlObject								
					<b>I_Interaction</b>									
					Description	general description of the interaction	IfcString	see type	see type	empty sting	see type	Yes		
					InteractionType	the type of interaction, e.g. between actors. (see TypeDef)	IfcTypeDefinition	see type	see type	see type	see type	No		
					FrequencyDaily	number of interactions daily	IfcInteger	0	n/a	0	n/a	No		
					AverageDuration	average time duration of each interaction	IfcTimeDuration	0	see type	0	see type	Yes		
					ImportanceRating	represents the level of importance of interaction	IfcString	n/a	n/a	empty string	n/a	Yes		
<b>Extensions to IFC FM Model</b>														
<b>--&gt; Classes/Interfaces/Attributes/Relationships/Defined Types</b>														
					<b>IfcSpaceInventory</b>	inventory for spaces								
					InheritsFrom ----->	IfcInventory								
					<b>I_SpaceInventory</b>									
					HasSpaces	all the spaces stored in the inventory; this allows to include zones	Set [1:N] of Ref. to IfcSpaceElement	n/a	n/a	NIL	n/a	No		
					TotalSpaces	total number of spaces in the inventory	IfcInteger	0	see type	0	n/a	No		
					TotalNetArea	total net area of all the spaces; can be derived from each space inventory for furniture	IfcArea	see type	see type	see type	see type	Yes		
					<b>IfcFurnitureInventory</b>	inventory for furniture								
					InheritsFrom ----->	IfcInventory								
					<b>I_FurnitureInventory</b>									
					TotalValueOriginal	the original total value of all the furniture	IfcCost	see type	see type	see type	see type	Yes		
					TotalValue	the current total value of all the furniture	IfcCost	see type	see type	see type	see type	Yes		
					FurnitureInventory	contains set of IfcFurniture and IfcWorkstation	Set [1:N] of Ref. to IfcElement	n/a	n/a	NIL	n/a	No		
					<b>IfcEquipmentInventory</b>									
					InheritsFrom ----->	IfcInventory								
					<b>I_EquipmentInventory</b>									
					TotalValueOriginal	the original total cost of all the equipment	IfcCost	see type	see type	see type	see type	Yes		
					TotalValue	the current total cost of all the equipment in the inventory	IfcCost	see type	see type	see type	see type	Yes		

					EquipmentInventory	all the equipment in the inventory	Set [1:N] of Ref. to IfcEquipment	n/a	n/a	NIL	n/a	No
					<b>IfcWorkstationWorkload</b>	represents the workload of a workstation						
					InheritsFrom ----->	IfcControlObject						
					<b>I_WorkstationWorkload</b>							
					AverageWorkhourWeekly	average workhours each week	IfcTimeDuration	0	n/a	0	see type	Yes
					TotalPaperfilesToStore	used to determine file storage	IfcInteger	0	n/a	0	see type	Yes
					AveragePaperfilesProducedDaily	average total number of papers of paper files produced daily in the workstation	IfcInteger	0	n/a	0	see type	Yes
					TotalComputerfiles	used to determine computer equipment, in unit of MB	IfcReal	0.0	n/a	0.0	see type	Yes
					<b>IfcWorkstationCompanyPolicy</b>							
					InheritsFrom ----->	IfcControlObject						
					<b>I_WorkstationCompanyPolicy</b>							
					EmployeeType	e.g. manager, programmer, secretary, etc.	IfcString	n/a	n/a	empty string	n/a	No
					MaxWorkstationSize	the maximum area of the workstation designed for the type of employee	IfcArea	see type	see type	see type	see type	Yes
					MinWorkstationSize	the minimum area of the workstation designed for the type of employee	IfcArea	see type	see type	see type	see type	Yes
					FurnitureStyle	the style of furniture for the workstation designed	IfcString	see type	see type	empty string	see type	Yes
					CostLimit	the maximum cost limit for the workstation	IfcCost	see type	see type	see type	see type	Yes
					<b>IfcWorkstation</b>							
					InheritsFrom ----->	IfcAssembledElement						
					<b>I_Workstation</b>							
					WorkstationComponents	list of worksurfaces and storages, tables, chairs, etc., excluding the vertical panels	Set [1:N] of Ref. to IfcManufacturedElement	n/a	n/a	empty set	n/a	Yes
					WorkstationEquipment	all the equipment needed for the workstation	Set [1:N] of Ref. to IfcOfficeEquipment	n/a	n/a	empty set	n/a	Yes
					WorkstationPanels	all the vertical panels for the workstation	Set [0:N] of Ref. to IfcSystemFurniture	n/a	n/a	empty set	n/a	Yes
					Group	workstation group that the workstation belongs to	Ref. to IfcWorkstationGroup	n/a	n/a	NIL	n/a	Yes
					<b>I_WorkstationProgram</b>							
					Workload	the workload of the workstation	Ref. to IfcWorkstationWorkload	n/a	n/a	NIL	n/a	Yes
					AssignedTo	the persons who are assigned to the workstation	Set [0:N] of Ref. to IfcActor	n/a	n/a	empty set	n/a	Yes
					CompanyPolicy	the compancy policy that ties the design of the workstation	Ref. to IfcWorkstationCompanyPolicy	n/a	n/a	NIL	n/a	Yes
					WorkstationInsideZones	2D zones inside of the workstation, e.g. work task zone, chair clear zone, circulation zone	Set [0:N] of Att_WorkstationZone2D	n/a	n/a	empty set	n/a	Yes
					WorkstationRequirement	the space requirement for the workstation designed	Ref. to IfcSpaceRequirement	n/a	n/a	NIL	n/a	Yes
					<b>IfcSystemFurniture</b>	represents any component of systems furniture such as worksurface, storage, etc.						
					InheritsFrom ----->	IfcManufacturedObject						
					<b>I_SystemFurniture</b>							
					FurnitureType	Panel, Worksurface, Storage	IfcTypeDefinition	see type	see type	see type	see type	No
					Workstation	the workstation composed with the component	Set [0:N] of Ref. to IfcWorkstation	n/a	n/a	NIL	n/a	Yes
					<b>IfcWorkstationGroup</b>	represents a workstation group						
					InheritsFrom ----->	IfcAssembledElement						

## Extensions to Existing R1.5.1 Objects

								BudgetLimit	the budget limit for the space	IfcCost	see type	see type	see type	see type	Yes
								SpaceRequirements	the requirements for the space	Ref. to IfcSpaceRequirement	n/a	n/a	NIL	n/a	Yes

## 6.10.2. Type Definitions

#	TypeDef Name	Description
	<b>Class being Typed</b>	
	<b>Generic Type</b>	
	Specific Type / domain defining type	
	Att_Set #	Attribute Sets
	<b>DocumentType</b>	
	IfcDocument	
	<b>WorkOrder</b>	
		shared = Att_DocumentType
	Core	occurrence = Att_WorkOrder
	<b>PurchaseOrder</b>	
		shared = Att_DocumentType
	Core	occurrence = Att_PurchaseOrder
	<b>ChangeOrder</b>	
		shared = Att_DocumentType
	Core	occurrence = Att_ChangeOrder
	<b>Drawing</b>	
		shared = Att_DocumentType
	Core	occurrence = Att_Drawing
	<b>Specification</b>	
		shared = Att_DocumentType
	Core	occurrence = Att_Specification
	<b>GenericDocumentType</b>	
	IfcDocument	
	<b>ElectronicDocument</b>	
		shared = <none>
	Core	occurrence = Att_ElectronicDocument
	<b>PaperDocument</b>	
		shared = <none>
	Core	occurrence = Att_PaperDocument
	<b>FurnitureType</b>	
	IfcSystemFurniture	
	<b>Panel</b>	
		shared = Att_SystemFurnitureType
	FM	occurrence = Att_Panel
	<b>Worksurface</b>	
		shared = Att_SystemFurnitureType
	FM	occurrence = Att_Worksurface
	<b>Storage</b>	
		shared = Att_SystemFurnitureType

			FM		occurrence =	Att_Storage
			<b>InteractionType</b>			
			IfcInteraction			
			ActorInteraction			
					shared =	<none>
			Core		occurrence =	Att_ActorInteraction

### 6.10.3. Property Sets

Attribute Set Name								
		Attribute or Relation name	Definition	Data Type or Related Object	Min	Max	Default	Units
<b>Shared Attribute sets defining Type</b>								
<b>Core Model</b>								
<b>DocumentType</b>								
		Att_DocumentType	common attributes for all different types of documents	IfcDocument				
		Author	the author of the document	IfcString	n/a	n/a	empty string	n/a
		Company	the owner company of the document	IfcString	n/a	n/a	empty string	n/a
		Title	the title of the document	IfcString	n/a	n/a	empty string	n/a
		RevisionCode	revision code of the revision	IfcString	n/a	n/a	empty string	n/a
		RevisionNumber	revision number of the revision	IfcInteger	0	see type	0	see type
		LastModifiedDate	the date that the file last modified	IfcDate	see type	see type	see type	see type
		FirstCreatedDate	the date that the file first created	IfcDate	see type	see type	see type	see type
<b>FM Domain Extension Model</b>								
<b>FurnitureType</b>								
		Att_SystemFurnitureType	common attributes for all systems furniture types	IfcSystemFurniture				
		Workstations	i.e. the workstations that the system furniture is assembled with or placed in as required by the design	set [0:n] of Ref. to IfcWorkstation	n/a	n/a	empty set	n/a
		GroupCode	e.g. panels, worksurfaces, storages, etc.	IfcString	n/a	n/a	empty string	n/a
		Width	i.e. nominal width	IfcLength	see type	see type	see type	see type
		Height	i.e. nominal length	IfcLength	see type	see type	see type	see type
		Finishing	e.g. walnut, fabric	IfcString	n/a	n/a	empty string	n/a
<b>Type driven attributes that vary for each occurrence</b>								
<b>Core Model</b>								
<b>DocumentType</b>								
		Att_WorkOrder	occurrence attribute sets for WorkOrder typedef	IfcDocument				
		TransactionCode	trasaction code	IfcString	n/a	n/a	empty string	n/a
		RequestID	ID code of the request	IfcString	n/a	n/a	empty string	n/a
		Facility	the building element that the work needs to be done for	Set [1:N] of Ref. to IfcProductObject	n/a	n/a	NIL	n/a
		DateOfRequest	date of requested	IfcDate	see type	see type	see type	see type
		ShortJobDescription	short description of the job requested	IfcString	n/a	n/a	NIL	n/a
		JobDescription	description of the job requested	Set [0:N] of IfcString	n/a	n/a	empty set	n/a
		Justification	the organizational unit that requests the job	Set [0:N] of IfcString	n/a	n/a	empty set	n/a
		IfNotAccomplished	comments the job is not accomplished	Set [0:N] of IfcString	n/a	n/a	empty set	n/a
		WorkRequest	work task requested	Ref. to IfcWorkTask	n/a	n/a	NIL	n/a
		EstimatedCost	estimated cost	IfcCostSchedule	see type	see type	see type	see type
		ContractualType	the contractual type of the work	Enum (InHouse, SelfHelp, Contract)	InHouse	Contract	InHouse	n/a

		Budget	the budget requested	Ref. to IfcBudget	n/a	n/a	NIL	n/a
		RequestBy	the person who requests the budget	Ref. to IfcActor	n/a	n/a	NIL	n/a
		RequestTo	the person who receives the request	Ref. to IfcActor	n/a	n/a	NIL	n/a
		AdditionalContact	additional contact person regarding the request	Ref. to IfcActor	n/a	n/a	NIL	n/a
		Approval	the approval process of the	Ref. to IfcApproval	n/a	n/a	NIL	n/a
		<b>Att_PurchaseOrder</b>	occurrence attribute sets for PurchaseOrder typedef	IfcDocument				
		PurchaseOrderNo	the identification ID of the purchase order	IfcString	n/a	n/a	empty string	n/a
		CompanyTitle	the compancy that issues the purchase order	Ref. to IfcActor	n/a	n/a	NIL	n/a
		SupplierName	the supplier company	Ref. to IfcActor	n/a	n/a	NIL	n/a
		Date	the date when the purchase order is issued	IfcDate	see type	see type	see type	see type
		Remark	the remark comment	Set [0:N] of IfcString	n/a	n/a	empty set	n/a
		DateRequired	the required date	IfcString	n/a	n/a	NIL	n/a
		DateScheduled	the date scheduled	IfcDate	see type	see type	see type	see type
		DateActual	actual date of receiving the items	IfcDate	see type	see type	see type	see type
		FOB	Free of Board; 'yes' or 'no'	IfcBoolean	see type	see type	see type	see type
		ShipMethod	method of shipping	IfcString	n/a	n/a	empty string	n/a
		TotalCost	total cost of the purchase	IfcCost	see type	see type	see type	see type
		TotalItems	total number of items to purchase	IfcInteger	0	see type	0	n/a
		PurchaseItems	the items to purchase	List [0:N] of Att_PurchaseOrderItem	n/a	n/a	empty list	n/a
		Approval	approval process information of the purchase order	Ref. to IfcApproval	n/a	n/a	NIL	n/a
		<b>Att_ChangeOrder</b>	occurrence attribute sets for ChangeOrder typedef	IfcDocument				
		ChangeOrderNo	the identification of the change order	IfcString	n/a	n/a	empty string	n/a
		Description	general description of the change order	Set [0:N] of IfcString	n/a	n/a	empty set	n/a
		Date	the date that the change order created	IfcDate	see type	see type	see type	see type
		IssuedBy	the person who issued the change order	Ref. to IfcActor	n/a	n/a	NIL	n/a
		IssuedTo	the person who receives the change order	Ref. to IfcActor	n/a	n/a	NIL	n/a
		Approval	approval process information of the change order	Ref. to IfcApproval	n/a	n/a	NIL	n/a
		<b>Att_Drawing</b>	occurrence AttributeSet for DocumentType Drawing	IfcDocument				
		DrawingId	the identification id of the drawing	IfcString	n/a	n/a	empty string	n/a
		Specifications	the specification documents related to the drawing	Set [0:N] of Ref. to IfcDocument	n/a	n/a	empty set	n/a
		Scale	the scale used for the drawing. E.g. if '1:100', the value is '100'	IfcReal	0.0	see type	0.0	see type
		Unit	the measuring unit used for the drawing	IfcUnit	see type	see type	see type	see type
		RelatedDrawings	other drawings that related to this drawing	Set [0:N] of Ref. to IfcDocument	n/a	n/a	empty set	n/a
		<b>Att_Specification</b>	occurrence AttributeSet for DocumentType Specification	IfcDocument				
		SpecificationId	the identification of the specification	IfcString	n/a	n/a	empty string	n/a
		GeneralDescription	description of the specification	IfcString	n/a	n/a	empty string	n/a
		RelatedDrawings	drawings related to the specification	Set [0:N] of Ref. to IfcDocument	n/a	n/a	empty set	n/a
		TotalWords	total number of words	IfcInteger	0	see type	0	see type
		<b>Att_ElectronicDocument</b>	occurrence AttributeSet for GenericDocumentType ElectronicDocument	IfcDocument				
		FileName	name of the file	IfcString	n/a	n/a	empty string	n/a
		FileExtension_name	the extension name of the file	IfcString	n/a	n/a	empty string	n/a
		Software	the software that creates the file	IfcString	n/a	n/a	empty string	n/a
		FileSize	(in unit of KB)	IfcReal	0.0	see type	0.0	see type
		Directory	the directory of the file	IfcString	n/a	n/a	empty string	n/a
		BackupFile	the backup version of the file	Ref. to IfcDocument	n/a	n/a	NIL	n/a
		PaperCopy	the paper print copy of the file	Ref. to IfcDocument	n/a	n/a	NIL	n/a

		LastSaveTime	the time that the file last saved	IfcTime	see type	see type	see type	see type
		LastSaveDate	the date that the file last saved	IfcDate	see type	see type	see type	see type
		Type	hidden, readonly, etc.	IfcString	n/a	n/a	empty string	n/a
		<b>Att_PaperDocument</b>	occurrence AttributeSet for GenericDocumentType Paper Document	IfcDocument				
		Location	more appropriate if there is something like IfcRootObject	Ref. to IfcProductObject	n/a	n/a	NIL	n/a
		TotalPages	total number of pages	IfcInteger	0	see type	0	see type
		ElectronicCopy	the electronic copy of the paper copy	Ref. to IfcDocument	n/a	n/a	NIL	n/a
		<b>Att_Panel</b>	occurrence AttributeSet for FurnitureType Panel	IfcSystemFurniture				
		Shape	the vertical boundary shape of the panel	IfcPolyCurve2D	see type	see type	see type	see type
		Opening	an opening	IfcPolyCurve2D	see type	see type	see type	see type
		PanelType	e.g. Acoustical, Horz_Seg, Monolithic, Glazed, Open, Ends, Door, Screen, etc.	IfcString	n/a	n/a	empty string	n/a
		Thickness	the thickness of the panel	IfcLength	see type	see type	see type	see type
		<b>Att_Worksurface</b>	occurrence AttributeSet for FurnitureType Worksurface	IfcSystemFurniture				
		UsePurpose	e.g. writing/reading, computer, meeting, printer, reference files, etc.	IfcString	n/a	n/a	empty string	n/a
		SupportType	i.e. Freestanding or supported	IfcString	n/a	n/a	empty string	n/a
		HungingHeight	the hanging height of the worksurface	IfcLength	see type	see type	see type	see type
		Thickness	the thickness of the worksurface	IfcLength	see type	see type	see type	see type
		ShapeDescription	corner square, rectangle, etc.	IfcString	n/a	n/a	empty string	n/a
		<b>Att_Storage</b>	occurrence AttributeSet for FurnitureType Storage	IfcSystemFurniture				
		IsOverhead	is overhead storage or not	IfcBoolean	see type	see type	see type	see type
		SupportType	i.e. Freestanding or supported	IfcString	n/a	n/a	empty string	n/a
		UsePurpose	e.g. shelf, stationary, office supplies, personal items, etc.	IfcString	n/a	n/a	empty string	n/a
		NumberOfDrawers	number of drawers	IfcInteger	0	see type	0	see type
		HungingHeight	hanging height if IsOverhead	IfcLength	see type	see type	see type	see type
		Depth	depth of the storage	IfcLength	see type	see type	see type	see type
<b>Extension Attribute sets</b>								
		<b>Att_ScheduleData</b>	Attribute set for any object that uses schedule data set					
		TotalDuration	time duration	IfcTimeDuration	see type	see type	see type	see type
		ScheduledStartDate	scheduled start date	IfcDate	see type	see type	see type	see type
		ScheduledFinishDate	scheduled finish date	IfcDate	see type	see type	see type	see type
		ActualStartDate	actual start date	IfcDate	see type	see type	see type	see type
		ActualFinishDate	actual finish date	IfcDate	see type	see type	see type	see type
		EarlyStartDate	early start date	IfcDate	see type	see type	see type	see type
		EarlyFinishDate	early finish date	IfcDate	see type	see type	see type	see type
		LateStartDate	late start date	IfcDate	see type	see type	see type	see type
		LateFinishDate	late finish date	IfcDate	see type	see type	see type	see type
		TotalFloat	total float	IfcTimeDuration	see type	see type	see type	see type
		DaysRemaining	number of days remaining	IfcTimeDuration	see type	see type	see type	see type
		<b>Att_PurchaseOrderItem</b>	attribute set for purchase order items used in Att_PurchaseOrder	Att_PurchaseOrder				
		ItemNumber	the number of the purchase item in the list	IfcInteger	0	see type	see type	see type

		Quantity	quantity of the item	IfcReal	0.0	see type	0.0	see type
		Code	code of the item	IfcString	n/a	n/a	empty string	n/a
		Unit	unit describing the number of items	IfcUnit	see type	see type	see type	see type
		UnitPrice	unit price	IfcCost	see type	see type	see type	see type
		TotalCost	the cost of the item	IfcCost	see type	see type	see type	see type
		InvoiceAmount	cost amount of the item on invoice	IfcCost	see type	see type	see type	see type
		TotalBalance	cost balance of the item	IfcCost	see type	see type	see type	see type
		InPurchaseOrder	the purchase order that the item is referred	Ref. to IfcDocument	n/a	n/a	NIL	n/a
		<b>Att_WorkstationZone2D</b>	attribute set to represent functional 2D zones in IfcWorkstation	IfcWorkstation				
		WorkstationZoneType	e.g. worktask, circulation, chair_clearance, etc.	IfcString	n/a	n/a	empty string	n/a
		Length	length of the workstation	IfcLength	see type	see type	see type	see type
		Width	width of the workstation	IfcLength	see type	see type	see type	see type

### *Attribute sets that extend R1.5.1*

		<b>Att_FurnitureType</b>	shared attribute set for all type of furniture	IfcFurniture				
		ProductCode	manufacture product code for the furniture type	IfcString	n/a	n/a	empty string	n/a
		Width	nominal overall width	IfcLength	see type	see type	see type	see type
		Height	nominal overall height	IfcLength	see type	see type	see type	see type
		Depth	nominal overall depth	IfcLength	see type	see type	see type	see type
		Material	the main material the furniture of this type is made of, e.g. walnut, etc.	IfcString	n/a	n/a	empty string	n/a
		Finishing	e.g. walnut, fabric	IfcString	n/a	n/a	empty string	n/a
		<b>Att_SpaceType</b>	shared attribute set for all type of space	IfcSpace				
		SpaceName	the name of the space	IfcString	n/a	n/a	empty string	n/a
		GeneralDescription	general description of the space type	IfcString	n/a	n/a	empty string	n/a
		SpaceCatalog	description of space catalog	IfcString	n/a	n/a	empty string	n/a





## 6.11.2. Type Definitions

None defined in this project

## 6.11.3. Property Sets

None defined in this project

## 6.12. [XM-2]

### 6.12.1. Object Types

Class Name													
					Interface name	OPT, INV, DER	{ "Ref" = relationship }						
	2	3	4	5	6	Attribute / Relation name		Data Type/Related Object Type	Min	Max	Default	Definition	
1	IfcDocumentTypeRegistry											Reference to a project document	
						I_DocumentTypeRegistry : DocumentTypes							
						DocumentTypes		LIST [0:?] OF IfcDocumentTypeDef	n/a	n/a	empty list	Semantic definitio for attribute 1	
2	IfcDocumentTypeDef											Reference to a project document	
						I_DocumentTypeDef : DocumentTypeID, Description							
						DocumentTypeID		STRING	n/a	n/a	n/a	Unique ID for this document type	
						FileExtension		STRING [3]				File extension used by computer OS	
						Description		STRING	n/a	n/a	n/a	Semantic definition for attribute 1	
3	IfcDocumentReference											Reference to a project document	
						I_DocumentReference : xxx							
						DocumentType		INTEGER	n/a	n/a	0	Index into DocumentTypeRegistry - identifying the type of document referenced. Zero indicates no type has been specified	
						DocumentName		STRING	n/a	n/a	empty string	File name or document name assigned by owner	
						Location		STRING	n/a	n/a	empty string	URL, pathname or physical location of the document	
						DocSectionReference	OPT	STRING	n/a	n/a	empty string	Optional reference to a section within the document.	
						DocumentOwner		INTEGER	n/a	n/a	0	Index into ProjectTeamRegistry - identifying the team member who "owns" this document. Zero indicates no owner has been specified	
						ObjectSelectionSet		IfcObjectSelectionSet	n/a	n/a	empty list	selection set of objects "presented" in this document	
4	IfcObjectSelectionSet											Reference to a project document	
						I_ObjectSelectionSet : xxx							
						Objects		LIST [0:?] OF IfcObjectID	n/a	n/a	n/a	Semantic definitio for attribute 1	
						ReferencingDocuments	INV	SET [0:?] OF IfcDocumentReferenc e	n/a	n/a	n/a	Semantic definitio for attribute 2	

### 6.12.2. Type Definitions

None defined in this project

### **6.12.3. Property Sets**

None defined in this project